AL-BATTĀNĪ

The Sabian Zīj

al-Zīj al-Ṣābi'

the canons, translated from the Arabic

in Nallino's edition, Part III (Rome, 1899)

This is an English translation of the canons of al-Battānī's *Zīj*, made from the Arabic text as Nallino printed it. Every sentence of the Arabic is translated, in the order of the text; the numbers are given in figures. Words added for the sense stand in square brackets. The notes identify quotations, record where the translation follows a correction of Nallino's, and explain terms. The pages of the Arabic text are given in the margin. Nallino's Latin translation (Part I, Milan, 1903) was used as a check on the meaning throughout; its wording is not followed.

This version holds all the canons: the list of chapters, chapters 1 to 57 and the eight short chapters without numbers that follow chapter 57 in the Escorial codex (Nallino's A to H); and all that Part III prints of the tables: Nallino's notice, the chronological tables, the geographical tables, the two figures of pp. 243 and 244, the star catalogue and the tables of the stars for the year 1211. It is AI-integrated work (Claude), 2026; no person has proofread it. It is dedicated to the public domain (CC0 1.0).

Ar. p. 1

In the name of God, the Merciful, the Compassionate. God bless the Prophet Muḥammad, God's noble Messenger, and the Prophet's family and companions, and grant them peace.

This is the whole of what Muḥammad ibn Jābir ibn Sinān al-Ḥarrānī, known as al-Battānī — may God pardon them — set down on the computation of the stars and on the places of their courses as they have been tested. The book contains fifty-seven chapters in all, and this is an account of them.[1]

1. The opening of the book.
2. On dividing the circle of the sphere, and on multiplying degrees by one another, taking their roots, and dividing them by one another.
3. On finding the lengths of the chords of the parts of the circle, on entering in tables the halves of the chords of double the arcs, and on the procedures with them that follow from this.[2]
4. On the amount of the inclination of the ecliptic to the equator; on the division of this inclination, its directions, and its stages as it rises and descends. It is the declination of the sun from the right sphere.[3]
5. On finding the amounts of the equator that rise together with given arcs of the ecliptic [in places] under the equator, which is called the line of equality. By these same amounts, too, the signs pass over the meridian circle in every place on the earth; this is why they are called the ascensions of the signs in the right sphere.[4]
6. On the properties of each of the lines parallel to the equator that lie away from it towards the north, and an account of the places of the inhabited earth whose longitude and latitude are known from the book *The Form of the Earth*. Ar. p. 2
7. On finding the amplitudes of the winter and summer risings and settings on the horizon circles of the localities. These are the arcs of the horizon between the equator and the places of the ecliptic, and they are called the azimuths of the risings and settings on the horizon circle.
8. On finding the altitude of the north pole from the excess of the longest day, when this is given.
9. On finding the excess of the longest day from the given altitude of the pole.
10. On finding the altitude and the shadow, each from the other, when the shadow is horizontal, and on finding them when the shadow is vertical.
11. On finding the azimuth of the altitude and of the shadow on the horizon circle, in every locality, at every time of the day, for all degrees of the ecliptic. This is the part of the horizon circle, counted from the limit of rising and setting, that is cut off by the arc passing through the zenith and the sun.
12. On finding the meridian line in every locality, which is the direction of the south, and the direction of the equinoctial rising that becomes known with it; and on finding it in various ways.

[1] The heading gives the author's name as «Muḥammad ibn Jābir ibn Sinān»; the title page that Nallino set above it has «ibn Sinān ibn Jābir». «Tested» (*al-mumtaḥan*) is the word al-Battānī uses for what has been verified by observation.

[2] The halves of the chords of double the arcs are the sines; chapter 3 introduces them under this name.

[3] The print has «ونجزية»; Nallino's corrigenda read «وتجزية», «the division», which is translated.

[4] Nallino suspects that the words «in the localities that are» have fallen out before «under the equator»; the bracket supplies their sense. «The line of equality» (*khaṭṭ al-istiwā'*) is the terrestrial equator.

13. On finding the amount of the equator that rises together with given degrees of the ecliptic from the horizon in every place on the earth, which is called the ascensions of the signs in each locality; and what follows from this: finding the ascensions of any portion you wish in these ascensions and in the ascensions of the right sphere, finding the degrees of the ecliptic from these ascensions, the amount of the arc of the day and of the night, their equal hours, the times of the seasonal hours of the day and of the night, and converting the one kind of hours into the other.[5]

14. On finding the latitudes of the localities, which is the altitude of the north pole above their horizon, by observation.

15. On finding the altitude of the sun at noon on any day.

16. On finding how many hours of the day have passed and what is rising, by measuring the sun and knowing the altitude and the vertical shadow.

17. On finding the altitude from the hours of the day that have passed.

18. On finding the distances of the fixed or the wandering stars from the equator when they lie away from the belt of the signs in latitude, and the degrees of the ecliptic that culminate with them, from their places in longitude and latitude with respect to the ecliptic.[6] Ar. p. 3

19. On finding the half of the arc of the day of a star, which is half of its stay above the earth, and also below it, and the times of its hours above the earth and below it.[7]

20. On finding the degree of the ecliptic with which a star rises and the degree with which it sets.

21. On finding how many hours of the night have passed, by measuring some of the stars.

22. On finding the altitude of some of the stars from the hours of the night that have passed.

23. On finding the azimuth of a star from its altitude above the horizon.

24. On finding the distance of a star from the equator, and the parts of the ecliptic that culminate with it, from the azimuth of the place on the horizon circle where it rises or sets. By this the declination of a degree of the ecliptic from the equator is also known.[8]

25. On finding the degree of the ecliptic in which a star is, and the latitude of the star, from its distance from the equator and the degree that culminates with it, when these are known.

26. On finding the distances between the stars according to the arrangement of their places on the sphere in longitude and latitude.

27. On finding the length of the times of the solar year as found by observation, and from it the mean motion of the sun in days, months and years.

28. On finding the irregularity of the motion of the sun, and what appears with it of the degrees of the signs from the places of its farthest distance.[9]

29. On finding the amounts of the difference between days with their nights, when the daytime of one day together with its night is compared with the daytime of another day together

[5] Nallino notes that Plato of Tivoli's copy seems to have had «degree» (*daraja*) for «portion» (*wajh*), which may be the better reading.

[6] The number of this chapter is printed «يج», 13, a misprint for «يح», 18, which the corrigenda do not list.

[7] «The half» is supplied by Nallino; the codex and Plato have «the arc of the day».

[8] Al-Battānī distinguishes the distance of a star from the equator, when the star lies off the ecliptic, from the declination (*mayl*) of the degrees of the ecliptic and of the sun; so the last sentence of the title does not repeat the first.

[9] The Arabic is as ambiguous as Plato's Latin. Nallino takes the sense to be the longitude of the sun reckoned from its apogee, as it comes out from the irregular motion of the sun.

with its night, and how they are converted and transferred from one to the other.

30. On the description of the spheres of the moon and its motions; the irregularity that appears in them at the times of the conjunctions and oppositions with the sun, and the second irregularity that is compounded with it on account of the moon's distances from the sun; the causes of the two kinds of eclipse; the distance of the two luminaries from the earth; and the waxing and waning of the moon's light with its distance from the sun. Ar. p. 4

31. On the description of the spheres of the wandering stars and their states.

32. On finding the eras of the Arabs, the Rūm, the Persians and the Copts, and finding each of them from another.

33. On finding the place of the ecliptic in which the sun is seen, by the era of the Rūm or of the Arabs, whichever of the two you wish.

34. On finding the hours of computation in every locality. These are the mean equal hours after noon at the city of al-Raqqa, by which the motions are found at any time, so that the mean position of a star is known at that time of the day or the night; and on converting these hours into the hours of the localities.

35. On setting up the ascendant and the twelve houses from the hours of the day and the night, and finding the hours from the ascendant.

36. On finding the true place of the moon on the ecliptic on any day and at any time.

37. On finding the place of the northern and the southern node, which are the head and the tail, through which the moon passes in latitude.

38. On finding the latitude of the moon, which is its distance from the belt of the signs towards the south and the north.

39. On finding the parallax that the moon undergoes in longitude and latitude, its amounts in the quarters of the horizon, and the cause from which it arises; in various ways.

40. On finding the distance of the moon from the earth from its parallax in the circle of altitude that lies between the zenith and the horizon and passes through the place of the moon on the ecliptic.

41. On the sighting of the crescent at the beginning and the end of the months; the azimuth of the place in the sky where it is seen; its altitude above the horizon at that time; and its form, according to the light that is in it and to whether its two horns are level or tilted.

42. On finding the mean and the true conjunctions and oppositions of the sun and the moon, by the era of the Rūm or of the Copts, whichever you wish.

43. On finding the lunar eclipses, their amounts and their times in the localities; the side of the moon's disc on which the eclipse begins and the side on which the clearing takes place; and its figure, and working it out by computation and by the tables.

44. On finding the eclipse of the sun, its different amounts in every locality and its times there; the side of the sun's disc on which the eclipse begins and the side on which it clears; and its figure, and working it out by computation and by the tables. Ar. p. 5

45. On finding the places of the five wandering stars on the ecliptic at any time.

46. On finding the stations of the five wandering stars and their retrogradation.

47. On finding the latitudes of the five wandering stars and their directions.

48. On finding the appearance and the disappearance of the five wandering stars.

49. On finding the nine configurations that the fixed stars and some of the wandering stars have

with respect to the sun.

50. An account of the distances of the stars from the earth, their diameters, the sizes of their bodies and the extent of their spheres.

51. On finding the motion of the other stars by observation, and on entering in the table the places of those that are needed, in longitude and latitude.[10]

52. On what the masters of talismans have said, that the sphere has a motion of displacement going forwards and backwards, and the error that appears in this.[11]

53. On finding the times of the revolutions of the years, which take place when the sun returns to the place in which it was at the beginning.

54. On determining the amounts of the applications according to the latitudes of the stars, when they cast their rays on the ecliptic.[12]

55. On finding the ascensions of the signs between the quadrants of the sphere.

56. On making the vertical and the horizontal sundial for finding the seasonal hours of the day in every locality; on setting it up correctly and on the direction of the south; and how the direction of the qibla, which is the direction of Mecca the protected, is found on the sundial.[13]

57. The conclusion of the book, and a description of the making of the instrument in the shape of the sphere, which is called «the egg», and of the making of the two instruments for observation.[14]

This is the account of the contents of the book in detail, which comprises fifty-seven sections. Praise be to God for divine help, and God bless Muḥammad.

Chapter 1. The opening of the book

Ar. p. 6

Al-Battānī said: The first thing with which every matter is begun and every discourse is opened is the praise of God, exalted be God's mention, thanks to God for the divine benefits, and the blessing on the Seal of God's messengers and prophets — upon them be peace, and the mercy and blessings of God.[15]

Praise be to God, who created the creatures by divine power, ordered all things by divine will and perfected them by divine wisdom; who «encompasses all things in knowledge» and «has counted all things in number»; from whom «not the weight of an atom in the heavens or on the earth escapes, nor anything smaller than that or greater, but it is in a clear book».[16]

I bear witness that there is no god but God alone, who has no partner, and I bear witness that Muḥammad is God's servant and messenger, whom God «sent with the guidance and the religion of truth, to make it prevail over all religion, though the idolaters dislike it». Through the Prophet God guided the believers and «cut off the last of the unbelievers», and made the Prophet a proof for all the worlds. God bless the Prophet, the Prophet's good family, the chosen companions and those who follow the Prophet's practice, until the Day of Judgement.[17]

[10] Where this list has «the other stars», the heading of the chapter itself and Plato's Latin have «the fixed stars».

[11] This is the theory later known as trepidation, an oscillation of the equinoxes. Nallino translates «the masters of talismans» (*aṣḥāb al-ṭilasmāt*) as «the astrologers».

[12] The applications (*ittiṣālāt*) are the astrological aspects between stars.

[13] The sundial is *al-rukhāma*, literally «the marble slab».

[14] Nallino suspects «making» (*ṣanʿa*) where the codex has *ḍaʿa*, «placing»; Plato has «making». The translation follows Plato.

[15] The Seal of the messengers and prophets is Muḥammad (cf. Qurʾān 33:40).

[16] Qurʾān 65:12, 72:28 and 34:3. The «clear book» is the book that is with God.

[17] Qurʾān 9:33 and 61:9 (Nallino's note has XLI, 9, a misprint for LXI, 9); for «cut off the last of the unbelievers», cf.

To proceed. After the knowledge of the laws and the practice of religion, of which no one may be ignorant, the science of the art of the stars is among the sciences that are highest in rank and most exalted in standing, finest in adornment, that cling most to the heart and shine most in the soul, and that do most to sharpen thought and reflection, to quicken understanding and to train the mind. For there is a great share of good in it and great benefit: the knowledge of the length of the years and months, of the appointed times, of the seasons, of the lengthening and shortening of the day and the night, of the places of the two luminaries and their eclipses, of the courses of the stars in their direct and retrograde motion, of the changes in their configurations, of the order of their spheres and of all their other relations; and beyond this, what is attained through it by one who examines it closely and reflects on it constantly: the proof of the unity of God, and the knowledge of the essence of the Creator's greatness, of the breadth of divine wisdom, the majesty of divine power and the subtlety of divine handiwork.[18]

Ar. p. 7

God has said — mighty is the Speaker: «In the creation of the heavens and the earth, and in the alternation of night and day, there are signs for those who have understanding.» God, blessed and exalted, has said: «Blessed is the One who has placed signs in the sky.» God, mighty and majestic, has said: «It is the One who has made the night and the day to follow one another.» God, to whom be glory, has said: «It is the One who has made the sun a radiance and the moon a light, and has measured out its stations, so that you may know the number of the years and the reckoning.» And God, whose mention be exalted, has said: «The sun and the moon run by a reckoning.» There is much more of this kind in the book of God, mighty and majestic, which it would take long to describe and much space to mention and cite.[19]

When I had studied this science at length and reflected on it constantly, I came to know how the books composed on the motions of the stars disagree, and into what errors some of their authors fell in the procedures they set down in them as foundations and in what they built on these. I also came to know what has accumulated in the motions of the stars over long periods of time, when their observations are compared with the ancient observations; that the inclination of the ecliptic to the equator has been found to be smaller; and what has changed with this change in the various kinds of computation, in the lengths of the years, in the times of the seasons, and in the conjunctions of the two luminaries that are inferred from the times and hours of the eclipses. So I set about correcting all this and making it exact according to the method of Ptolemy in the book known as the Almagest, after close study, long reflection and consideration, following in Ptolemy's footsteps and keeping to what was laid down there. For Ptolemy had investigated these matters from every side and had shown their causes and the reasons that occur in them by a geometrical and numerical proof whose soundness cannot be rejected and whose truth cannot be doubted. After that, Ptolemy ordered that they be tested and examined by those who came after, and said that Ptolemy's own observations might be improved upon in the course of time, just as Ptolemy had improved upon Hipparchus and other peers; for the art is a lofty one, and, being heavenly and vast, it can be grasped only approximately.[20]

I have composed a book on this, in which I have made clear what was obscure, opened what was closed and explained what was difficult in the principles of this science and out of the way in its branches. With it I have made the path of guidance easy for those who follow it and work by it

7:72 and 8:7.

[18] The configurations of the stars are the nine configurations with the sun that chapter 49 explains (Nallino).

[19] Qur'ān 3:190, 25:61, 25:62, 10:5 and 55:5. The signs (*burūj*) of 25:61 are the word that al-Battānī uses for the signs of the zodiac throughout the book. In the third quotation the text prints «the night and the moon a light, in succession», a slip that mixes this verse with the next quotation; the Qur'ān (25:62) has «the night and the day», which Nallino translates and the translation follows.

[20] «Has been found to be smaller» renders *mā wujida … min al-taqārub*, literally «the drawing together that was found»: al-Battānī's observations gave a smaller obliquity of the ecliptic than the Greek value (chapter 4). Nallino stresses that the words do not show knowledge of a continuous decrease of the obliquity. For Ptolemy's remark see the Almagest, III 1 (in Heiberg's numbering; Nallino cites Halma's III, 2).

in the art of the stars. In it I have corrected the motions of the stars and their places on the belt of the ecliptic, as I found them by observation and by the computation of the two kinds of eclipse, together with all the other procedures that are needed, and I have added other things that are needed. I have arranged that the motions of the stars are found from the tables for noon of the day for which the computation is made, at the city of al-Raqqa, where the observation and the testing that establish all this took place — if God, the Exalted, wills. Success comes from God.

Chapter 2. On the division of the circle of the sphere, and on multiplication, roots and division

Ar. p. 8

Al-Battānī said: The ancients divided the circle of the sphere into 360 parts, and they gave more than one reason for this. One is that the number of these parts is close to the number of days of the year, which is completed when the sun passes a fixed point of the sphere until it returns to it. Another is that it is a number that has a half, a third, a quarter and other fractions that do not come out whole for many numbers. They placed the sun at four points of the sphere, which bring about two equinoxes and two solstices and divide the year into four distinct parts, spring, summer, autumn and winter; and they named each of these points after the season that begins when the sun passes it.

Since everything that has extension has a middle and two ends, each of these seasons divides into three parts, and so the circle of the sphere had to have twelve parts. They found the spring point the best of these points and the most fitting to begin with. For from it, after the equinox, the day begins to lengthen, and the sun is rising into the northern half of its sphere, so that the heat grows; and the nature of this season is moist and inclines to heat, which suits the beginning of growth and the coming into being of things. So they made the reckoning of the sphere begin from it.[21]

Then they found that the constellations next to these twelve parts, which are called signs, were twelve constellations, and they named each sign after the constellation next to it, although over a long time these constellations move away from the places of the signs named after them. So the first part became Aries, followed by Taurus, Gemini, Cancer, Leo, Virgo, Libra, Scorpio, Sagittarius, Capricorn, Aquarius and Pisces.[22]

Each of these signs therefore has 30 parts as its share of the 360 parts of the circle of the sphere. These parts are also called degrees. Each degree is divided into 60 parts, called minutes; each minute is likewise divided into 60 parts, called seconds; each second is divided into 60 thirds; and so on, by the same rule of division, to tenths and the separate orders that come after them.

Ar. p. 9

As for the meaning of multiplication: it is repeating one of two numbers as many times as there are units in the other — I mean the multiplication of units by units. Multiplying fractions by units is repeating the fractions as many times as there are units, or taking of the units the part that the fractions are of one. Multiplying fractions by fractions is taking of one of the two fractions, whichever you wish, the part that the other fraction is of one.

Thus, when degrees are multiplied by degrees, the product is degrees; when they are multiplied by minutes, it is minutes; when they are multiplied by seconds, the product is seconds; and so with what is multiplied by thirds, fourths and the following orders: the product is of the order of the smaller one, by which it was multiplied. As for the orders below degrees, minutes and the others: when each of them is multiplied by itself, the product falls below it by as much as it falls below

[21] Nallino notes the same account of the spring point in Abū Maʿshar (d. 886), *Introductorium* II 5, and, almost word for word, in Abraham bar Ḥiyya's *Sphaera mundi* (1165), ch. 2.

[22] The Arabic names are al-Ḥamal (the Ram), al-Thawr (the Bull), al-Jawzāʾ (Gemini), al-Saraṭān (the Crab), al-Asad (the Lion), al-Sunbula (the Ear of Grain), al-Mīzān (the Balance), al-ʿAqrab (the Scorpion), al-Qaws (the Bow), al-Jady (the Kid), al-Dalw (the Bucket) and al-Ḥūt (the Fish). The translation uses the Latin names by which the same signs are known in English.

degrees. For example, minutes multiplied by minutes give seconds, and multiplied by seconds they give thirds, and what is multiplied by thirds and fourths falls by the same rule. Seconds multiplied by seconds give fourths, and multiplied by thirds they give fifths; and whatever lies further from these orders goes the same way, by the same rule.

When any number of one of these orders, obtained by multiplication or by addition, is divided by sixty, the number at which every order ends and to which all the fractions are related, the result belongs to the next higher order. When, in a number made up of two or more of these orders, more has to be subtracted from one of them than it contains, one unit is broken off from the next higher order for it, counted as 60 parts and added to it; then as much as needed is subtracted, and what remains is counted together with what remains of the higher order.

As for degrees: whatever accumulates of them when the parts of the motions are added is reckoned in revolutions. If the sum is more than one revolution, or than several revolutions, a revolution being 360 degrees, the revolutions are dropped and what remains is counted. When more has to be subtracted from the degrees than they contain, a revolution is added to them; then as much as needed is subtracted from the sum, and what remains is counted.

Ar. p. 10

If you wish to multiply one of the orders of degrees or of fractions by another of them, and to know from this table of which order the product will be, take on one of the two lines AB the cell in which the order you wish to multiply by any other order is written, and go straight on from that cell until you are level with the other order that you want: the cell level with it, among the orders of fractions, gives the order of the product. For example, suppose you wish to multiply fourths by thirds. Take on the line AB that runs across the width of the page either of the two orders — let it be the thirds first — and go on from it until you are level with the fourths on the line AB that runs along the length of the page; in the cell level with it you find sevenths, and this is the order of the product. Likewise, if you took the fourths on a line AB and went from them to the level of the thirds on the other line AB, you would find sevenths there. Do the same with any orders you wish, if God wills.

The orders of products[23]

degrees	minutes	seconds	thirds	fourths	fifths	sixths	sevenths	eighths	ninths	tenths
minutes	seconds	thirds	fourths	fifths	sixths	sevenths	eighths	ninths	tenths	elevenths
seconds	thirds	fourths	fifths	sixths	sevenths	eighths	ninths	tenths	elevenths	twelfths
thirds	fourths	fifths	sixths	sevenths	eighths	ninths	tenths	elevenths	twelfths	thirteenths
fourths	fifths	sixths	sevenths	eighths	ninths	tenths	elevenths	twelfths	thirteenths	fourteenths
fifths	sixths	sevenths	eighths	ninths	tenths	elevenths	twelfths	thirteenths	fourteenths	fifteenths
sixths	sevenths	eighths	ninths	tenths	elevenths	twelfths	thirteenths	fourteenths	fifteenths	sixteenths
sevenths	eighths	ninths	tenths	elevenths	twelfths	thirteenths	fourteenths	fifteenths	sixteenths	seventeenths
eighths	ninths	tenths	elevenths	twelfths	thirteenths	fourteenths	fifteenths	sixteenths	seventeenths	eighteenths
ninths	tenths	elevenths	twelfths	thirteenths	fourteenths	fifteenths	sixteenths	seventeenths	eighteenths	nineteenths
tenths	elevenths	twelfths	thirteenths	fourteenths	fifteenths	sixteenths	seventeenths	eighteenths	nineteenths	twentieths

[23] The print reads from right to left; here the columns are set from left to right. The first row is the line AB across the width of the page, the first column the line AB along its length. The cell of the fourth row and second column is printed «ورابع», a misprint for «روابع», «fourths».

Ar. p. 11

As for the meaning of the root: the root of any absolute number, whatever number it is, is that which, multiplied by itself, gives the given number. But the roots of these orders do not keep this rule, because of the difference that we have described in what results from multiplying these orders by one another. The rule holds only for the order of degrees: the root of degrees is also degrees, since degrees multiplied by degrees give degrees. As for the fractions below degrees, of the remaining orders: those of even rank, such as seconds, fourths, sixths and the like, have their root in the higher order whose rank is half of theirs — seconds, whose root is minutes, and fourths, whose root is seconds. Those of odd rank, such as minutes, thirds and the like, have no definite root unless they are converted into the order below them, so that they come to an even rank; then this rule applies to them: minutes are converted into seconds, and thirds into fourths.[24,25]

Division is finding how many times the smaller number goes into the larger, when the larger is measured by the smaller, and finding what part of the larger the smaller is, when the smaller is the number divided. Here we proceed in the reverse of what we did in multiplications and roots, by the same rule: if we divide degrees by degrees, the quotient is degrees. As for the other orders below degrees: when a lower order is divided by a higher one, whatever its rank and whether or not it is next to it, the quotient is of the order which, multiplied by the order divided by, gives back the order of the number divided. Thus seconds divided by minutes give minutes, and sixths divided by fourths give seconds. But when a higher order is divided by a lower one, the way to do it is to convert the higher order into the lower and then divide by it, and the quotient is degrees. So with minutes divided by sixths: when they are converted into sixths and then divided by those sixths, the result of the division is degrees, as we have described.

Ar. p. 12

If you wish to know, with the table given here, what results from dividing the lower orders of fractions by the orders above them, look up in the line AB or in the line AD, whichever you wish, the order that you wish to divide by an order of higher rank, whether or not it is next to it, and go on level with it until you are level with the higher order on the other line. The order of fractions at which you arrive is the order that you obtain by dividing the number divided, and it is the order which, multiplied by the higher order that you divided by, gives back the order of the number divided. Likewise, if you wish to divide a higher order by a lower one, convert the higher into the lower, look up in one of the two lines the order into which it has been converted, and go on level with it until you are level with the order that you wish to divide by: you obtain degrees. And whenever you divide an order by the same order, the result is degrees, if God, the Exalted, wills. Success comes from God.[26]

[24] An absolute number (*ʿadad muṭlaq*) is a number taken by itself, not counted in one of the sexagesimal orders.

[25] The print has «فتلزَمه» (p. 11, line 7), a misprint for «فتلزَمه», «applies to them», which the corrigenda do not list.

[26] «With the table given here»: the Arabic says «with this table mentioned before»; the table is printed at the head of the next page.

The orders of quotients[27]

degrees	minutes	seconds	thirds	fourths	fifths	sixths	sevenths	eighths	ninths	tenths
minutes	degrees	minutes	seconds	thirds	fourths	fifths	sixths	sevenths	eighths	ninths
seconds	minutes	degrees	minutes	seconds	thirds	fourths	fifths	sixths	sevenths	eighths
thirds	seconds	minutes	degrees	minutes	seconds	thirds	fourths	fifths	sixths	sevenths
fourths	thirds	seconds	minutes	degrees	minutes	seconds	thirds	fourths	fifths	sixths
fifths	fourths	thirds	seconds	minutes	degrees	minutes	seconds	thirds	fourths	fifths
sixths	fifths	fourths	thirds	seconds	minutes	degrees	minutes	seconds	thirds	fourths
sevenths	sixths	fifths	fourths	thirds	seconds	minutes	degrees	minutes	seconds	thirds
eighths	sevenths	sixths	fifths	fourths	thirds	seconds	minutes	degrees	minutes	seconds
ninths	eighths	sevenths	sixths	fifths	fourths	thirds	seconds	minutes	degrees	minutes
tenths	ninths	eighths	sevenths	sixths	fifths	fourths	thirds	seconds	minutes	degrees

[27] The columns are set from left to right, as in the first table. The first row is the line AB, the first column the line AD. The cells of the second row and fourth column and of the fourth row and second column are printed «ثولنٍ» and «توانٍ», misprints for «ثوانٍ», «seconds».

Chapter 3. On finding the lengths of the chords of the parts of the circle, on entering in tables the halves of the chords of double the arcs, and on all the procedures with them that follow from this[28]

Ar. p. 13

Al-Battānī said: The ancients disagreed about the size of the diameter of the circle in relation to its circumference, although they came close to it. Some said that the circumference of the circle is 3 times its diameter and 1/7 of it. Others said that it is 3 times [the diameter] and a little more than 10 parts of 71. What the excellent Ptolemy and the astronomers worked with lies between these two amounts: 3 times [the diameter] together with 1/10 of it and 1/4 of 1/6 of it. We do not need to know the truth of this in setting out the chords, since arcs and chords have no known measure in relation to one another, and this is known only from their chords. Nor does it do us any harm to take the diameter as large as we wish. This is why Ptolemy made it 120 parts, because the computation comes out easily this way; and we also work with it in this book.[29]

Ar. p. 14

It has been shown by proof that the chord of a sixth of any circle is equal to its radius. A sixth of the circle of the sphere is evidently 60 parts, according to the basis of the computation, in the measure in which the circle is 360 parts; and the chord of the sixth is also 60 parts, in the measure in which the diameter is 120. If the chord of a sixth of the circle is multiplied by itself and subtracted from the whole diameter multiplied by itself, the root of the remainder is the chord of a third of the circle. In the same way, for any arc of a circle whose chord is known: if the chord of that arc is multiplied by itself, the product is subtracted from the whole diameter multiplied by itself, and the root of the remainder is taken, the result is the chord of the arc that remains to complete the semicircle. The chord of a quarter of the circle is the root of twice the product of its radius by itself. The chord of a tenth of any circle is found thus: to the radius multiplied by itself add a quarter of the diameter multiplied by itself, take the root of the sum, and subtract from it a quarter of the diameter of the circle; what remains is the chord of a tenth of that circle. The chord of a fifth of the circle is found thus: multiply the chord of its tenth by itself, add to it the radius multiplied by itself, and take the root of the sum; this is [the chord of] the fifth of that circle.

For any two arcs of a circle whose chords are known, the chord of the arc by which they differ is also known. Multiply the chord of each of the two arcs by the chord of what remains of the other to complete the semicircle, take the difference between [the two products] and divide it by the diameter; the result is the chord of the arc by which the two arcs differ.

For any arc of a circle whose chord is known, the chord of its half is also known. Subtract the chord of what remains of that arc to complete the semicircle from the whole diameter of the circle, take half of the remainder, multiply it by the whole diameter, and take the root of the product; the result is the chord of half that arc.

For any two arcs of a circle whose chords are known, when one is placed on the other and we join them so that they become one arc, the chord of the combined arc is also known. Multiply the chord of each of the two arcs by [that of] the other, and the chord of what remains of each of them to complete the semicircle by [that of] the other as well; take the difference between [the two products] and divide it by the whole diameter. The result is the chord of what remains of the combined arc to complete the semicircle. If it is multiplied by itself and subtracted from the whole diameter multiplied by itself, the root of the remainder is the chord of the arc combined of

[28] The translation follows Nallino's corrigenda in three places: «لتمام» for «لتمام» (p. 14, line 4), «وتر» for «وثر» (p. 14, line 18) and «حاجتنا» for «جاجتنا» (p. 15, line 19). It also reads «نحتاج» for «نحناج» (p. 15, line 11), «والوتر» for «واوتر» (p. 16, line 14), «يتلوه» for «بتلوه» and «فزدته» for «فردته» (p. 16, line 17) and «الوتر» for «اوتر» (p. 17, line 11), misprints that the corrigenda do not list.

[29] 3 1/7 and 3 10/71 are the two bounds that Archimedes proved for this ratio in the *Measurement of the Circle*. Ptolemy's value, 3 + 1/10 + 1/24 = 3 17/120, is 3;8,30 in sexagesimal fractions (*Almagest* VI 7). The ratio that is known only from the chords is that of the chord of one arc to the chord of another (Nallino).

the two arcs. By this rule and in these ways all the remaining chords in the semicircle that can be known are found.

As for the chords that are not known by proof, such as the chord of one degree and its doublings, two, four, eight and the like: they are not found by computation in the way of proof, as those arcs and those chords are. But it is known by proof that the ratio of the chord of a smaller arc to its arc is greater than the ratio of the chord of a greater arc to its arc. Now the chord of one and a half degrees and the chord of a half and a quarter [of a degree] are known by proof, and 2/3 of the chord of one and a half degrees is equal to the chord of a half and a quarter of a degree increased by a third of itself; there is no perceptible difference between them, and no harm to the computation comes from it. If the chord of three quarters [of a degree] is taken and a third of it is added to it, the sum is the chord of one degree. Once the chord of one degree is known in this way, all the chords of the degrees of the semicircle become known as well.[30]

Ar. p. 15

What is needed about the amounts of arcs that intersect one another in known arcs is found only through the chords of double the known arcs. When a circle is divided by two lines that intersect at its centre at right angles, it is divided into four equal quarters, at four angles; each angle takes in 90 parts of the circumference and is enclosed by two lines that go out from the centre to the circumference, each of them the radius. The two right angles under two quarters together are enclosed by one straight line, the whole diameter, which is plainly twice each of the two lines that enclose the one right angle under one quarter. So the ratio of each of the two lines that enclose a right angle to the diameter that encloses the two right angles is as the ratio of a quarter of the circle to its half. Hence the diameter divides the chords of the remaining arcs in the semicircle into two halves, and it divides the arcs with them into halves on its two sides. So the ratio of the chord of each of these arcs to the whole diameter is as the ratio of half that chord, which lies under half that arc, to the radius; and this is half the chord of twice the arc that lies on either side of the diameter, half of it in each of the two quarters. This is what we mean, and it is what we use in the procedures of computation, so that we do not need to double the arc in what we seek to find. Ptolemy did that only to establish the proof.[31]

We, however, have taken half the chord of twice each arc of the quarter of the circle and entered it under the entry for that arc in the quarter, and we have made the arcs in the tables increase by half a degree up to the full 90 degrees that make up the whole quarter. So half the chord of one degree stands under half a degree; half the chord of 60 under 30 degrees; half the chord of 120 under 60; and half the chord of 180 degrees — the semicircle, whose chord is the whole diameter — under 90, the degrees of the whole quarter: this is the radius, whose amount is 60 parts. All these halved chords entered in this book are related to it. So that we need not repeat ourselves in what follows, we state that whenever we speak of chords in this book, we mean these halved chords, except where we name one specially and call it a full chord; and for the most part we seldom need these.[32]

Ar. p. 16

If you want to find from the tables the sine of any degree you like, look in the table of sines, in the column of the numbers that increase by half a degree; where you find the number that you have, take the degrees, minutes and seconds entered opposite it in the table of sines: that is the sine of the degrees you wanted. If there are minutes with the degrees, more or less than 30 minutes, take what stands opposite the whole degrees, or the degrees and halves, whichever is nearest to the degrees and minutes you have and smaller than them, and keep what you find opposite

[30] This is Ptolemy's procedure for the chord of 1° (*Almagest* I 10). By the inequality just stated, the chord of 1° lies between 2/3 of the chord of 1½° and 4/3 of the chord of ¾°, and these two bounds agree to the precision of the tables.

[31] The first sentence is obscure; Nallino, following Schiaparelli, takes it to mean that every computation that combines several arcs is made through the chords of the doubled arcs.

[32] From here on the translation calls these halved chords «sines», as Nallino does in the Latin; al-Battānī calls them «halved chords» (*awtār munaṣṣafa*) or simply «chords». Other Arabic authors call the sine *jayb*. Since the radius is 60, al-Battānī's sine of an arc is 60 times its sine in modern terms. The full chords are needed in chapters 26, 50 and 54 (Nallino).

it in the table of sines. Then subtract the number you found in the column from the one you have, multiply the minutes that remain by the difference between the sine you kept and the sine opposite the number half a degree greater, and divide the product by the 30 minutes by which the numbers in the two columns of arcs increase. Add the minutes and seconds that result from the division to the sine you kept if it is the smaller, and subtract them from it if it is the greater; what you obtain after the addition or the subtraction is the sine of the degrees and minutes that you have.[33]

Or, if you wish, find what part of 30 minutes the minutes left over are: if they are a half, or a third, or less or more than that, take the same part of the difference of the sines and proceed with it in the same way, adding or subtracting; the result is the sine of the arc you wanted.

If you wish to find arcs from these sines, look for the sine in the table of sines; where you find it, or the nearest value smaller than it, take what stands opposite it in the first of the two columns of numbers: that is the arc you want, and keep it. Then subtract the sine you found in the tables from the sine you have, multiply the remainder by 30 minutes, and divide the product by the difference between the sine you found and the one that follows it. Add the minutes and seconds that result to the arc you kept; the arc you then have is the arc of the sine you want. Or, if you wish, see what part the minutes and seconds left over are of the difference between the sine you found and the one that follows it, take the same part of 30 minutes and add it to the arc you kept, as before; it comes to the same. This procedure is called taking the arc of the sines.[34]

If you wish to find the versed sines from the arcs: if the number whose versed sine you want is less than 90 degrees, subtract it from 90, find the sine of the remainder by the rule given above, and subtract it from 60 degrees, which is the radius; what remains is the versed sine of that arc. If the number is more than 90, find by how much it exceeds 90, find the sine of the excess, and add it to 60 degrees; the sum is the versed sine of the arc you wanted.[35]

Ar. p. 17

If you wish to find the arcs from these versed sines: if the versed sine you have is less than 60 degrees, subtract it from 60, find the arc of the remainder by that rule, and subtract the arc from 90; what remains is the arc of the versed sine. If the versed sine is more than 60, take 60 from it, find the arc of the remainder, and add it to 90 degrees; the sum is the arc of the versed sine.

You need no more for finding arcs and sines than what I have set out for you. For these sines it is enough to know the sines from 1 degree to 90 degrees, because the sine of whatever goes beyond 90, up to 180, is like the sine of the degrees up to 90 taken in reverse order. Likewise for the full chords you need no more than the chords of the semicircle, from 1 degree to 180, because the chords of the other half are like those of the 180 degrees in reverse order.

As for finding the full chords from the arcs, and the arcs from these chords: if you wish to find the full chord of any number of degrees, take half those degrees, find its sine from the table, and double it; the result is the full chord of the degrees you wanted. If you wish to find the arcs of the full chords with the tables as well, take half the chord, find its arc from the table in the way described above, and double the arc; the result is the arc of the full chord that you wanted.

Whenever one of these sines is multiplied by itself and subtracted from the radius multiplied by itself, the root of the remainder is the sine of what remains of that arc to complete a quarter of the circle. And when the sine of any degree is subtracted from the radius, the remainder is multiplied by 30 parts and the root of the product is taken, the result is the sine of half of what remains of that arc to complete a quarter of the circle, if God wills.[36]

[33] The sines are given in degrees, minutes and seconds of a radius of 60 degrees.

[34] «Taking the arc» is *taqwīs*, Nallino's *arcuatio*: finding the arc that belongs to a given chord or sine.

[35] The versed sine is *al-watar al-rāji*ʿ, literally «the returning chord». In modern terms the versed sine of an arc a is $60(1 - \cos a)$; the two rules of the text are the cases $a < 90°$ and $a > 90°$.

[36] In modern terms, writing Sin a = 60 sin a for al-Battānī's sine of an arc a: $\text{Sin}(90° - a) = \sqrt{(60^2 - (\text{Sin } a)^2)}$, and $\text{Sin } ½(90° - a) = \sqrt{(30\ (60 - \text{Sin } a))}$, because $60^2 \sin^2 ½(90° - a) = 1800\ (1 - \cos(90° - a)) = 30\ (60 - \text{Sin } a)$.

Chapter 4. On finding the amount of the inclination of the ecliptic to the equator, the division of this inclination, its directions, and its ranks in its ascent and descent; this is the declination of the sun from the right sphere

Ar. p. 17
Ar. p. 18

Al-Battānī said: The ecliptic is defined by the path on which the sun is seen to move; the equator is the circle along which the greatest sphere turns about its two poles. The inclination of the ecliptic to the equator is found only by observing the sun and following its passage through the two solstitial points on the meridian circle. This is the circle of the middle of the sky; it passes through the two poles of the equator and the zenith, and it cuts the horizon circle.

Hipparchus stated, and Ptolemy's book reports, that the arc of the meridian circle between the winter and the summer solstice is 47° 42′, and that the inclination is half of that, 23° 51′. We ourselves observed it many times in our own day with the long alidade and with the brick, whose making and setting up are described in the Almagest, after dividing [their scales] precisely and setting up the instrument as exactly as could be done. We found the least distance of the sun from the zenith on the meridian circle, in the city of al-Raqqa, to be 12° 26′, and its greatest distance 59° 36′. From this it became clear to us that the arc between the two solstices is in truth 47° 10′, and that the inclination of the ecliptic to the equator is half of these degrees, 23° 35′; this is the distance between the poles of the two circles. We work with this value in this book, since we have seen it with our own eyes, while the first is known by report.[37,38]

From this we also learned that the distance of the city of al-Raqqa, where the observations were made, from the equator on the meridian circle is 36°. This is the altitude of the north pole of the equator above the horizon there, and it is also the distance of the equator from the zenith towards the south.[39]

If you wish to compute this inclination, so as to find the part of it that belongs to each degree you want, up to the full 90 degrees that complete the inclination, which is 23° 35′: take the sine of one degree, or two degrees, or more, up to the full 90 degrees, which run from the beginning of Aries to the end of Gemini. When you know the sine of the degrees you wanted, multiply it by the sine of the whole inclination, divide the product by the radius, which is 60, and find the arc of the quotient. The arc you obtain is the declination of the degree you wanted from the equator, on the meridian circle.[40]

Ar. p. 19

If you wish to enter this in a table degree by degree, find the declination of each degree you want up to 90 degrees, and enter under each degree what belongs to it. When you have done this, you know the declination of all the parts of the ecliptic. For the declination of what goes beyond 90, up to 180, is like the declination of the 90 [degrees] entered, taken in reverse order; the declination of what goes beyond 180, up to 270, is like the declination of the 90 in the same order; and the declination of what goes beyond 270, up to 360, is like the declination of the 90 in reverse order. We have entered this in the table at intervals of one degree, with four columns of numbers. In the first column we have entered the numbers of the ecliptic from 1 degree to 90; in the second, what the numbers of the first column fall short of 180; in the third, the numbers of the first column added to 180; and in the fourth, what the numbers of the first column fall short

[37] Ptolemy (*Almagest* I 12) found the arc between the solstices to be more than 47 2/3° and less than 47 3/4°, nearly the ratio of 11 to 83 parts of the meridian that Ptolemy ascribes to Eratosthenes and says Hipparchus also used; Ptolemy's table of declinations (*Almagest* I 15) uses an inclination of 23° 51′ 20″.

[38] The long alidade (*al-ʿiḍāda al-ṭawīla*) is Ptolemy's parallactic instrument, the triquetrum (*Almagest* V 12); the brick (*al-libna*) is Ptolemy's plinth, a quadrant set up in the plane of the meridian (*Almagest* I 12). Al-Battānī describes both in chapter 57 (Nallino).

[39] The two observations give 36° 1′, as Delambre noted, since the equator lies midway between the two solstitial points: (12° 26′ + 59° 36′)/2 = 36° 1′. Nallino suggests that al-Battānī dropped the minute to keep the tables simple, 36° being also the latitude of Rhodes, for which Ptolemy computed several tables.

[40] In modern terms, $\sin \delta = \sin \lambda \cdot \sin \varepsilon$, where λ is the distance of the degree from the beginning of Aries, ε the inclination and δ the declination.

of 360. Thus, if the number falls in the first or the second column, we know that the declination is towards the north of the equator, and if it falls in the other two columns, we know that it is towards the south.

If you wish to find the declination of the sun, or of any other degree of the signs, take [the distance] from the beginning of Aries to the degree of the sun, or to whatever other degree whose declination you wish to find; the result is the argument of the declination. Look for the same number in the four columns of numbers entered in the tables of declination, and take the degrees, minutes and seconds entered opposite it: that is the declination of the degrees you wanted. If there are minutes with the degrees, take for them their share of the difference, in the way I showed you for the differences of the sines. See what part the minutes are of the 60 minutes by which the numbers increase, and take the same part of the difference between the declination of the whole degrees and the declination of the degree one greater. Then look: if the declination of the degree you have is the smaller, add what you obtained to it; if it is the greater, subtract it from it. The declination you obtain after the addition or the subtraction is the declination of the degrees and minutes you wanted from the equator.[41]

If the argument is from 0 to 90, the declination is increasing and the sun is ascending in the north; if it is from 90 to 180, the declination is decreasing and the sun is descending from the north; if from 180 to 270, the declination is increasing and the sun is descending towards the south; and if from 270 to 360, the declination is decreasing and the sun is ascending in the south. In short, when the argument of the declination is from 0 to 180, the declination is northern, and when it is from 180 to 360, it is southern. By this computation you find the declination of the sun, its direction, and its ascent and descent.[42]

They have divided the declination into six ranks of ascent and descent: they made every 15 degrees of the sun's course in each of these quarters one of the ranks of ascent and descent, up to the full 90 degrees that complete the six ranks. When the sun is in the first 15 degrees of one of the quarters, they say that it is in the first rank; when it is in the second 15 degrees, they say that it is in the second rank; and so on until the sixth rank is reached.[43]

Chapter 5. On finding the ascensions of the signs in the right sphere[44]

Ar. p. 20

Al-Battānī said: Suppose you wish to know how many of the 360 times of the equator rise together with given parts of the ecliptic. These are the ascensions of the signs at the place of the line of equality. This is the place that has no latitude, above which the equator turns; there night and day are always equal, on all the days of the year. In every locality the signs cross the middle of the sky with the same amount [of the equator] with which they rise on this line, and there they also cross the middle of the sky with this amount. This is why these are called the ascensions of the signs in the right sphere. Every three signs rise in the right sphere together with 90 times of the equator.[45]

If you wish to compute the ascension in the right sphere of any degree of the signs you like, take the whole inclination, which is 23° 35′, and find its sine: this is the sine of the whole inclination. Then subtract the whole inclination from 90 and find the sine of the remainder: this is the sine of the complement of the whole inclination. Then take [the distance] from the beginning of Aries

[41] «The argument of the declination» is *ḥiṣṣat al-mayl*, literally «the share of the declination»: the number with which the table is entered (Nallino's *argumentum declinationis*).

[42] The text writes these numbers in abjad numerals, with the letters of the alphabet, and 0 with the zero sign of the codex.

[43] Theon of Alexandria describes the same ranks (Greek *bathmoi*) of 15° as a usage of the astrologers; al-Battānī gives a table of them at the end of the table of the declination of the sun (Nallino).

[44] The translation reads «تلك», «that», for the misprint «تلك» (p. 20, line 14), which the corrigenda do not list.

[45] A time (*zamān*) is a degree of the equator, the measure of the daily turning of the sphere. The three signs are those of a quarter of the ecliptic that begins at an equinoctial or a solstitial point.

to the degree you want, find the declination of that degree, and find its sine: this is the sine of the declination of the degree. Then subtract the declination of the degree from 90 and find the sine of the remainder: this is the sine of the complement of the declination of the degree. Then multiply the sine of the declination of the degree by the sine of the complement of the whole inclination, divide the product by the sine of the whole inclination, multiply the quotient by the radius, which is 60, divide the product by the sine of the complement of the declination of the degree, and find the arc of the quotient. The arc you obtain is the amount of the equator that rises from the beginning of Aries to the degree you wanted.[46]

If you computed for 30 degrees, the result is the ascension of the whole sign of Aries; if you computed for 60, it is the ascension of Aries and Taurus together: subtract from it the ascension of Aries, and the ascension of Taurus remains. Then subtract the ascension of Aries and Taurus together from 90; what remains is the ascension of Gemini. When you know the ascension of Aries, the ascensions of Virgo, Pisces and Libra are equal to it; the ascensions of Leo, Aquarius and Scorpio are equal to that of Taurus; and the ascensions of Sagittarius, Capricorn and Cancer are equal to that of Gemini.

Ar. p. 21

By this rule you derive the ascensions degree by degree and enter them in the tables. Begin from the beginning of Capricorn, so that from it you know the ascensions of the signs in the middle of the sky for every locality, and so that the number by which one finds what culminates and what parts rise in every locality is one and the same number. We shall explain how the ascensions are put into tables when we come to the ascensions of the signs in the climes, so as not to repeat ourselves.[47]

Chapter 6. On the properties of the parallel lines that run parallel to the equator, on the places of the inhabited earth that are known in longitude and latitude, and on what follows from this[48]

Ar. p. 21

Al-Battānī said: We should begin with the equator, and then speak of the other circles that decline from it towards the north, and of the places of the earth that lie beneath these circles.

We say: The line of the earth that lies beneath the equator is the line called the line of equality. It has no latitude; the equator turns upon it and above it, from east to west, and there day and night are always equal, on all the days of the year, as we said at the beginning. When the sun passes over this line, and only then, day and night are balanced and perceptibly equal over the whole earth. The sun is then at the point common to the ecliptic and the equator, for this is where the two circles intersect: the point of the beginning [of Aries and the beginning] of Libra. Only then does the sun stand at noon above the heads of those who live on this line, so that upright objects there cast no shadow. When the sun runs in the northern half of the ecliptic, the shadows of upright objects there fall towards the south at noon; when it runs in the southern half of the ecliptic, the shadows then fall towards the north at noon. This line alone bounds the whole inhabited quarter [of the earth] on the south. Also, all the stars rise and set there, because the two poles of the sphere lie there on the horizon circle itself, and the turning of the sphere

[46] In modern terms, $\sin \alpha = \tan \delta \cdot \cot \varepsilon$, where α is the ascension of the degree in the right sphere, δ its declination and ε the inclination.

[47] Counted from the beginning of Capricorn, the ascension in the right sphere of the culminating degree is equal to the ascension at the locality of the rising degree, counted from the beginning of Aries; one number therefore gives both (Schiaparelli, in Nallino's commentary). Al-Battānī's table of ascensions in the right sphere is counted in this way. The ascensions in the climes are the subject of chapter 13.

[48] The translation reads «الشمس», «the sun», for «اشمس» (p. 23, line 18) and «تنتهي» for «ننتهي» (p. 24, line 22), misprints that the corrigenda do not list. It follows the emendanda printed in Part II in reading «الأندلس» for «الأندلس» (p. 26, line 18) and «اوقيانس» for «ارقيانس» (p. 28, line 12).

there is like that of a water-wheel, the wheel of a well.[49,50]

Ar. p. 22

It is not known for certain that this line of the earth is inhabited, for we have seen no one who claims to have reached it in our time, and Ptolemy's book does not mention it. But people of understanding know that the clime of this line is temperate, because the sun never goes very far from it and does not stay long over its zenith, since at that time it passes quickly through the declination. So summer and winter there are both mild. Something like what we have described is seen in places near it, such as Ṣanʿāʾ, Aden and the other places of Yemen that are close to it.[51]

As for the other lines that decline from this line towards the north, which are the lines parallel to it: on any one of them, the stars that lie within the circle drawn about the north pole of the equator with a radius equal to the altitude of the pole above the horizon on that line never set on that line. Of the stars outside this circle, those that are near it may be seen twice in one night, once at the beginning of the night and again at its end, and they set in between. The stars at the zenith of one of these lines are those that cut off, on the circle through the two poles of the equator, an arc between the star and the equator equal to [the arc] between the line and the equator. The stars that are always hidden are those within the circle drawn about the south pole of the equator with a radius equal to the depression of that pole below the horizon. All the other stars, which are not of this description, rise and set.

Therefore, if one observes one of the stars within the circle drawn about the north pole of the equator with a radius equal to the altitude of the pole above the horizon, and takes its altitude at its highest, when it crosses the line of the middle of the sky above the pole, between the zenith and the pole; if one then waits until it is on the line of the middle of the sky below the pole, between the pole and the horizon, where it is lowest, and takes its altitude then; and if one finds the difference between the two altitudes and adds half of it to the smaller altitude: the result is the altitude of the north pole above the horizon there. Likewise, if the two altitudes are added together and half the sum is taken, this is the altitude of the pole, and it is the latitude of that place to the north.

Ar. p. 23

On every one of these lines whose distance from the equator is less than the inclination, the sun passes over the zenith twice a year. This is known from the table of declination, and so is the part of the ecliptic where it happens, I mean the degree in which the sun is on that day. For when the sun is at the beginning of Aries or of Libra, it passes at noon over the zenith on the line of equality, as has also been said before; and there this happens only once a year. When it is north of these two points, it reaches the zenith of those who live beneath its path in declination, that is, where the altitude of the pole equals the declination of the degree in which the sun is on that day, the declination being northern. It is known that the distance of the equator from the zenith is then equal to the declination, and that on that day upright objects there cast no shadow at noon. When the sun moves away from them, the shadows of upright objects at noon fall towards the south, until it returns to them and stands over their heads a second time. Then again upright objects have no shadow, until it moves away from them, and the shadows of upright objects fall towards the north.[52]

On the other lines, whose distance from the equator is greater than the inclination, the sun never reaches the zenith of their inhabitants, and the shadows of upright objects there never fall towards the south at noon. On them the difference between night and day in length keeps

[49] The words in brackets are supplied by Nallino; the codex lacks them.

[50] The print has «السَّنْويّ», «annual», which gives no sense here; Nallino's emendanda, printed in Part II, read perhaps «السّانويّ», from *sāniya*, the wheel that lifts water from a well. The sphere of the equator turns like a wheel standing upright, with its axis lying in the horizon.

[51] *Almagest* II 6 (Nallino).

[52] Once a year at each of the two points (Nallino); Plato of Tivoli has «twice», perhaps the translator's own conjecture, since the codex has «once».

growing, up to the line whose distance from the equator is 66° 25′, which is what the whole inclination falls short of 90. On this line alone, when the sun reaches the summer solstitial point, which is called the beginning of Cancer, the day is longer by 12 hours, so that day and night together become one day, all of it daylight; and the night becomes the same when the sun reaches the winter solstitial point, which is called the beginning of Capricorn. This line alone is the first of the lines on which the shadows of upright objects fall towards all the directions of the horizon, because beyond this line, towards the north, the middle of the day is not bounded. On this line alone the ecliptic coincides with the horizon itself when the spring equinoctial point rises; for the beginning of Cancer then rises at the north point, and at the same time the beginning of Aries is on the eastern horizon, rising at the equinoctial rising point. Therefore, when the sun passes the summer solstitial point, it does not set for a day and a night: it travels around the horizon at varying distances from it until it returns to the north point, so that this day has no night at all.

Ar. p. 24

Al-Battānī said: On the other lines that decline from this line towards the north, the shadows of upright objects go round them, on every one of these lines, towards all the directions of the horizon, and the length of the day on each of them is known from the table of declination. For when the declination of the degrees at which the sun, on these lines, is distant from the solstitial point is subtracted from 90, the remainder is the distance of the parallel line from the equator, I mean the altitude of the pole on that line. The degrees that the sun traverses on the two sides of the solstitial point are either always visible or always hidden. So on some of these lines the day lasts a month, or two months, or three, or less or more, and the night lasts as long at the opposite season. This goes on up to the line whose distance from the equator is all the degrees of the quarter, where the altitude of the pole is 90 degrees. There the day, with the shadow of upright objects going round them towards all the directions of the horizon, lasts nearly six months. For there the northern half of the ecliptic, from the beginning of Aries to the end of Virgo, is never hidden below the earth, and its other, southern half never appears above the earth; so the whole year is a single day, half of it daylight and half of it night. There alone the north pole is at the zenith, and the equator is at once always visible and always hidden, for it lies in the very place of the horizon there. Clearly the turning of the sphere there is like that of a millstone. Between the line of equality and this line, the turnings vary between that of the water-wheel and that of the millstone: the turning inclines with the inclination of the place from the line of equality, according to its nearness to each of the two lines and its distance from it. God knows best.[53]

We give an example of some lengths of the day on some of these lines, to serve as a model. We take it on the line whose distance from the equator is 69° 44′, which is the altitude of the pole on this line. Subtracting this from 90 leaves 20° 16′. We find that the sun reaches this amount of northern declination when it is 30 degrees from the summer solstitial point on either side; that is, from the time it is at the beginning of Gemini it remains visible above the earth, going round the horizon, until it reaches the beginning of Leo. So on this line it does not set at all while it is in these 60 degrees on the two sides of the solstitial point, and the day, with the shadow of upright objects going round them towards all the directions of the horizon, lasts until the sun has crossed these degrees, which takes about two months. When its whole distance from the winter solstitial point lies between the two degrees opposite these two degrees, it does not appear above the earth, that is, from the time it reaches the beginning of Sagittarius until it reaches the beginning of Aquarius; so the night too lasts about two months.

Ar. p. 25

As for the line whose distance from the equator is 78° 28′: there the sun does not set below the earth when it reaches a northern declination equal to what these degrees fall short of 90, and does not appear above the earth when it reaches a southern declination of the same amount. This amount is 11° 32′. We find that the sun reaches this declination when it comes to the beginning of Taurus and to the beginning of Virgo, where its distance from the summer solstitial point is

[53] The same comparison with the millstone ends chapter 7 of al-Farghānī's book, and Dante took it from there into the *Convivio* (Schiaparelli, in Nallino's note).

60 degrees on either side. So the day, with the shadows of upright objects going round them, lasts nearly four months. Likewise the sun stays below the earth while its course runs from the beginning of Scorpio to the beginning of Pisces, so that the night too lasts as long.[54]

As for the known places of the earth and the inhabited localities in longitude and latitude: we have shown, by the reasoning that Ptolemy set out and in which others of the ancients agreed with Ptolemy, that the earth is round, that its centre is in the middle of the sphere, that the air surrounds it on all sides, and that compared with the ecliptic it is as small as a point.[55]

As for its inhabited part, they took its limits from the inhabited islands called the Eternal Islands, in the western Ocean, which are six inhabited islands, to the farthest inhabited land of China, and they found this to be 12 hours. So they knew that when the sun sets at the farthest inhabited land of China, it begins to rise over the first of the inhabited islands said to be in the western Ocean, and when it sets at these islands, it begins to rise over the farthest inhabited land of China. That is half the circle of the earth, and it is the length of the inhabited land as far as it has been explored. In miles it is 13,500 miles, in the miles that they used in measuring the earth. Then they considered the latitude, and found that the inhabited land runs from the place of the line of equality towards the north as far as the island of Thule, which is in Britain, where the longest day is 20 hours.[56,57]

Ar. p. 26

They stated that on its course from east to west the line of equality on the earth is cut, between India and Ethiopia, at an island there on the south side of the equator; this island lies across it there and separates north from south. The line that cuts this line from north to south lies halfway between the islands said to be in the Ocean and the farthest inhabited land of China; this is the dome of the earth, known by what we have described, and its place is the place of the intersection. The latitude from the line of equality to the island of Thule is about 60 degrees, a sixth of the circle of the earth. If this sixth, the amount of the latitude, is multiplied by the half, the amount of the longitude, the inhabited land that appears in the north is half a sixth of the earth, that is, one part in twelve.[58,59,60]

They measured the Indian Sea. They said that its length, counted from west to east, from the farthest end of Ethiopia to the farthest end of India, is 8000 miles, and its breadth 2700 miles, of which it extends 1900 miles south of the island where night and day are equal. It has a gulf in the land of Ethiopia that reaches towards al-Barbar and is called the Berber Gulf; its length is 500 miles and the breadth of its channel 100 miles. Another gulf goes out towards the land of Ayla: this is the Sea of al-Qulzum. Its length is 1400 miles; the breadth of its channel, which is called the Green Sea, is 200 miles, and its breadth at its mouth 700 miles. Another gulf goes out towards the land of Persia; it is called the Persian Gulf, and it is the Sea of Basra. Its length is 1400 miles, its breadth at its mouth 500 miles, and the breadth of its channel 150 miles. Between these two gulfs, I mean the gulf of Ayla and the gulf of Persia, lie the lands of the Ḥijāz and Yemen; the distance between these two gulfs is 1500 miles. Another gulf also goes out from it, near its end,

[54] The Arabic writes 78° 28′ and 11° 32′ in abjad numerals; Nallino's Latin prints 78° 23′ in the first place, a misprint. Ptolemy (*Almagest* II 6) puts these two parallels at 69 1/2° and 78 1/3°, because Ptolemy's inclination is larger (Nallino).

[55] The rest of the chapter was edited and translated into French by Reinaud (1848); much of it recurs, nearly word for word, in al-Masʿūdī, Ibn Rusta and Qudāma (Nallino).

[56] The codex has «the empty islands» (*al-khāliyāt*); Nallino reads «the Eternal Islands» (*al-khālidāt*), as Plato of Tivoli and the Arabic geographers have it. They are the Fortunate Islands of the Greek geographers, the Canaries.

[57] 13,500 miles for 180° make 75 miles to the degree, a value that reached the Arabs through Syriac writers from Ptolemy (Nallino).

[58] Ethiopia (*al-Ḥabash*) is here, as in the Greek geographers, the whole south of Africa (Nallino).

[59] The dome of the earth (*qubbat al-arḍ*) goes back to the Indian prime meridian through Ujjain and Laṅkā, misplaced by the Arabs on an island on the equator; it is the «Arin» of the medieval Latin astronomers (Nallino).

[60] The computation is wrong twice over (Schiaparelli, in Nallino's commentary). The area of a zone of the sphere is not the product of its extent in latitude and its extent in longitude. And even on that rule, 60° is a third of the 180° from pole to pole, which would give 1/6, not 1/12. In fact the half of the zone between the equator and latitude 60° is (sin 60°)/4 ≈ 0.2165 of the sphere.

towards the farthest land of India; it is called the Green Gulf, and its length is 1500 miles.[61]

In this whole sea, I mean the Sea of India and China, there are 1370 islands, inhabited and uninhabited. Among them is an island at its far end, near the land of China, called Taprobane, which is Sarandīb; it is 3000 miles round. It faces India on the east. It has great mountains and many rivers, from which come rubies and sapphires. Around it are 59 inhabited islands, with many towns and villages.[62,63]

As for the western Ocean, which is called the Encircling [Sea], only its western and northern part is known, from the farthest land of Ethiopia to Britain; it is a sea on which ships do not sail. The six islands in it, facing the land of Ethiopia, are the inhabited islands, which are also called the Islands of the Blessed. Another island, facing al-Andalus and called Gadira, lies at the strait. This strait goes out from the Ocean; it is 7 miles wide where it goes out, it lies between al-Andalus and Tangier, it is called Sabṭā, and it goes out into the Sea of the Rūm. In the Ocean, on the north side, are also the islands of Britain, which are twelve islands. Beyond them it goes far away from the inhabited land, and no one knows what it is like or what it holds.[64]

Ar. p. 27

The Sea of the Rūm and of Egypt begins at the strait that goes out from the western Ocean near the island called Gadira, facing al-Andalus, and runs east to Tyre and Sidon. Its length is 5000 miles; its breadth is 600 miles in one place, 700 miles in another and 800 miles in another. It has one gulf that goes out towards the north near Rome, 500 miles long, called Adris, and another gulf that goes out towards the land of Narbonne, 200 miles long. In this whole sea there are 162 inhabited islands, five of them large: the island of Corsica, 200 miles round; Sardinia, 300 miles round; Cyprus, 350 miles round; Sicily, 500 miles round; and Crete, 300 miles round.[65]

The Sea of Pontus extends from Lādhiqa to Constantinople the Great; its length is 1060 miles and its breadth 300 miles. The river called Tanais flows into it; it comes from the north, from the lake called Maeotis, which is a large sea although it is called a lake: its length from east to west is 300 miles and its breadth 100 miles. At Constantinople a channel bursts out of the Pontus, flowing like a river, and pours into the Sea of Egypt; at Constantinople it is about 3 miles wide, and Constantinople lies on it.[66]

The Sea of Jurjān, which is the Sea of al-Bāb, is 800 miles long from west to east and 600 miles wide. In it, facing Jurjān, are two islands that were inhabited in the past. These are the inhabited places in the known seas of the earth; God knows best.[67]

The earth has been divided into three parts. The first of them is [bounded] by the Green Sea on the north side, by the channel that goes out from the Pontus into the Greatest Sea, and by what lies between the lake Maeotis and the Pontus. So the boundaries of this region are, on the west and the north, the western sea, which is the Ocean; on the south, the Sea of Egypt and of the

[61] The measures of the seas go back, through a Syriac source also used by Jacob of Edessa, to Ptolemy's map: at 75 miles to the degree they agree with it (Nallino). Al-Barbar is the country of Berbera, on the coast of Somalia. The Sea of al-Qulzum is the Red Sea: al-Qulzum is the Greek Clysma, near Suez, and Ayla is the present al-ʿAqaba. Nallino takes the Green Gulf to be Ptolemy's Prasōdēs Sea, the «leek-green sea» (*Geography* VII 2, 1).

[62] Taprobane and Sarandīb are names of Sri Lanka. «Rubies and sapphires» is literally «red *yāqūt* and the colour of the sky»: *yāqūt* is corundum, red in the ruby and blue in the sapphire.

[63] Jacob of Edessa, Ibn Rusta and al-Kharaqī give 19 islands, the number that Ptolemy lists around Taprobane (*Geography* VII 4, 11–13); Nallino concludes that al-Battānī's source had 19, written in letters (يط), which al-Battānī read as 59 (نط).

[64] Gadira is Cadiz, and Sabṭā is Ceuta; the strait is the Strait of Gibraltar. The Sea of the Rūm (the Byzantines) is the Mediterranean.

[65] Adris is the Adriatic. Corsica is called by its Greek name, Kyrnos (*Qurnus*).

[66] The Pontus is the Black Sea, the Tanais the Don and the Maeotis the Sea of Azov; the channel is the Bosporus. Lādhiqa, also written Lāziqa, is a city or region of the Caucasus (Nallino). For the length of the Pontus Nallino prefers 1300 miles, the figure of Jacob of Edessa, Ibn Rusta and others.

[67] The Caspian Sea; al-Bāb is Derbent. For its length Nallino prefers 1800 miles, the figure of Ibn Rusta and Jacob of Edessa.

Rūm; and on the east, the Tanais and the lake Maeotis. This land is like an island; they called it Europe.[68]

The second part lies to the south, from the Sea of Egypt to the Sea of Ethiopia. The boundaries of this region are, on the west, the Green Sea; on the north, the Sea of Egypt and of the Rūm; on the east, al-ʿArīsh; and on the south, the Sea of Ethiopia. This part is called Libya.

Ar. p. 28

The third part is all the rest of the inhabited earth, to its farthest end. Its boundaries are, on the west, the Tanais, the river, the channel, al-ʿArīsh and Ayla; on the south, the Sea of Yemen and of India; and on the east, the farthest inhabited land of China towards the east, and China itself. This part is called Greater Asia. These three parts take in the climes, the districts and all the inhabited regions.[69]

What is not known to be either inhabited or desolate is 11 parts out of 12. The part that holds the known inhabited land, from the place of the line of equality, also holds the seas and the deserts. If someone asks whether there are plants, animals and habitation in these eleven parts, the answer can only come from inference by analogy and from opinion. The inhabited earth on our side does not go beyond the limits and boundaries we have mentioned, and no one has brought us word of what lies beyond them. But opinion and conjecture, reasoning by analogy, arrive at what no one of understanding will deny. The sun, the moon and the stars move with us, and from their motion, their nearness and their distance come summer and winter, plants, animals and habitation, and all that everyone knows. If the sun and the stars rise over every place of the rest of the circle of the earth as they do with us, then there can be plants, animals, seas and mountains there as with us; and so it should be. One degree comes to about 65 of the miles mentioned above, which is about two days' journey; God knows best.[70]

As for the longitudes and latitudes of the cities as they are set down in the *Book of the Image of the Earth*: their positions in longitude, which is the distance between west and east, were counted from the inhabited islands in the western Ocean towards the east. This was done according to what they found of the times of eclipses, those of the moon in particular, which occur earlier in some localities than in others. From this they learned that noon in each locality precedes noon in another locality to the west of it by as many times of the equator as lie between [the times of] the eclipse in the two localities. Some of it they took, approximately, from the reports of travellers.[71]

The latitudes of the cities they took from measuring the sun at noon in the localities. They found its distance from the zenith, as we have explained earlier in this book, and so learned the distance of each locality from the line of equality, which is the distance between south and north. Under each city they set down, approximately, its distance from the Eternal Islands in longitude and from the line of equality in latitude. We have entered these according to the description that we found in the well-known *Book of the Image of the Earth*, and we have also listed separately the middles of the known regions and districts, as Ptolemy did; they are 94 regions. There are errors in the longitudes and latitudes in that book; we shall come back to what is needed of this in the later parts of our book.[72]

[68] The Green Sea is here the Atlantic, as often in Arabic authors, and the Greatest Sea the Mediterranean, the «Great Sea» of Orosius (Nallino, after Reinaud).

[69] The river is the channel at Constantinople that flows like a river; the channel is the Sea of the Rūm, which reaches Tyre and Sidon (Nallino).

[70] The 13,500 miles of the half circumference give 75 miles to the degree. Nallino takes 65 for a slip for 75: the Arabic words for sixty and seventy are easily confused when their dots are left out. Plato of Tivoli has 85.

[71] The *Book of the Image of the Earth* (*Kitāb ṣūrat al-arḍ*) is not al-Khwārizmī's book of that title: Nallino shows that its author used both Ptolemy's *Geography* and al-Khwārizmī's book, and suggests that it was the Arabic recension of the *Geography* made by Thābit ibn Qurra. Plato of Tivoli's Latin adds «which is called Geography».

[72] Nallino could not find such a list in Ptolemy: the *Geography* gives no coordinates for the middles of its provinces.

Chapter 7. On finding the winter and summer risings and settings on the horizon circles of the localities, from the excess of the longest day or from the altitude of the pole, whichever of the two is known

Ar. p. 29

Al-Battānī said: Suppose you wish to find the amounts of the arcs of the horizon circle that lie between the equator and the ecliptic at the horizon in any locality; this is the azimuth of the rising and of the setting of any part of the ecliptic you want. Take the given excess of the longest day and find its amount in degrees, by multiplying each hour of it by 15 degrees. Take half the result and add it to 90; the sum is half the arc of the longest day. Then take the whole inclination, which is the declination of the point of the beginning of Cancer, and subtract it from 90. Find the sine of the remainder: this is the sine of the complement of the declination of Cancer. Multiply it by the sine of half the arc of the longest day, divide the product by the radius, and find the arc of the quotient. Subtract this arc from 90; the remainder is the amount [of the arc] on the horizon circle between the rising and the setting of the beginning of Cancer and the equator, to the north of the equator.[73]

Likewise, if you work with half the arc of the shortest day, which is the day of the beginning of Capricorn, the amount comes out the same, and it is known that the beginning of Capricorn rises and sets to the south of the equator. Clearly the azimuth of the beginning of Cancer in the north is equal to the azimuth of the beginning of Capricorn in the south. These are the summer and winter risings and settings: those on the north side are called the summer ones, and those in the south the winter ones.

Ar. p. 30

If you wish to find the azimuth of the rising and setting of points of the ecliptic other than these two, take the declination of any degree you like, subtract it from 90, and find the sine of the remainder. Then find half the arc of the day of that degree, or take it to be whatever you like; find its sine and multiply it by the sine of the complement of the declination of the degree. Divide the product by the radius, find the arc of the quotient, and subtract it from 90; the remainder is the azimuth of the rising and setting of that degree on the horizon circle. If the declination is northern, it lies to the north of the equator; if it is southern, to the south.[74]

If the latitude of the locality is given and you wish to find from it the azimuth of the rising and setting of any degree you like, subtract the latitude of the locality from 90; the remainder is the altitude of the beginning of Aries there. Find its sine. Then take the declination of the degree you want and find its sine; multiply it by the radius and divide the product by the sine of the altitude of the beginning of Aries. Find the arc of the quotient: this arc is the distance of the rising and setting of that degree from the rising and setting of the beginning of Aries, on the horizon circle, towards the side of the declination. This is the azimuth, if God wills.[75]

Chapter 8. On finding the altitude of the pole from the excess of the longest day

Ar. p. 30

Al-Battānī said: Suppose you wish to find the altitude of the north pole of the equator above the horizon, which is the latitude of the locality, from the excess of the longest day over the equinoctial day, or from the shortfall of the shortest day. Take half the excess of the longest day, the day of the first degree of Cancer, in degrees, and add it to 90; the sum is half the arc of the longest day. Or, if you wish, subtract it from 90; the remainder is half the arc of the shortest day. Whichever of the two you work with, it comes to the same. Then subtract the whole inclination from 90 and find the sine of the remainder: this is the sine of the complement of the whole

[73] The azimuth of a rising (*samt al-maṭlaʿ*) is measured on the horizon from the point where the equator rises; in modern terms it is the amplitude of the rising. The excess of the longest day is its excess over 12 hours. In modern terms the rule is $\cos A = \cos \delta \cdot \sin H$, where A is the amplitude, δ the declination and H half the arc of the day.

[74] «Half» is supplied by Nallino; the codex and Plato of Tivoli have «the arc of the day».

[75] In modern terms, $\sin A = \sin \delta / \cos \varphi$, where φ is the latitude; $90^\circ - \varphi$ is the altitude of the beginning of Aries when it culminates.

inclination. Multiply the sine of half the arc of the day by the sine of the complement of the whole inclination, divide the product by the radius, and find the arc of the quotient. The arc you obtain is the distance of the rising of the beginning of Cancer from the north point. Subtract it from 90; the remainder is the distance of the rising of the beginning of Cancer from the equinoctial rising point, as we have explained in the preceding chapter. Then multiply the sine of half the excess of the longest day by the sine of the distance of the rising of the beginning of Cancer from the north point, and divide the product by the sine of the distance of the rising of the beginning of Cancer from the rising of the beginning of Aries. Multiply the quotient by the radius, divide the result by the sine of half the arc of the longest day, and find the arc of the quotient. The arc you obtain is the altitude of the pole where the excess of the longest day is the given amount with which you worked.[76,77]

Chapter 9. On finding the excess of the longest day, and the lesser excesses of the day, from the altitude of the pole

Ar. p. 31

Al-Battānī said: Suppose you wish to find the amount of the excess of the longest day, and of the shortfall of the shortest day, with respect to the equinoctial day, from the altitude of the pole when it is given. Take the latitude of the locality and find its sine. Then subtract the latitude of the locality from 90 and find the sine of the remainder: this is the sine of the complement of the latitude of the locality. Then find the sine of the whole inclination, and the sine of what the whole inclination falls short of 90. Multiply the sine of the latitude of the locality by the sine of the whole inclination, divide the product by the sine of the complement of the whole inclination, multiply the quotient by the radius, divide the result by the sine of the complement of the latitude of the locality, and find the arc of the quotient. The arc you obtain is half the excess of the longest day, and half the shortfall of the shortest day is the same. Double it: the result is the whole excess of the longest day and the whole shortfall of the shortest day. Every 15 degrees of it make one equal hour. Add the hours you obtain to the 12 hours that are the length of the equinoctial day; the sum is the hours of the longest day. Subtract the same excess from 12; the remainder is the hours of the shortest day.[78]

If you wish to know the excess of the day at degrees of the ecliptic other than these two, take the declination of any degree of the signs you like and work with it in place of the whole inclination. What you obtain at the end of the work, done in the same way, is the difference of the day at that degree: if the declination of the degree is northern, it is an excess of the day; if it is southern, it is a shortfall at that degree.

Chapter 10. On finding the altitude and the shadow, each from the other, by computation or from the table

Ar. p. 31
Ar. p. 32

Al-Battānī said: If you wish to find the shadow from the altitude, find the sine of the altitude and the sine of what the altitude falls short of 90. Then divide the gnomon into as many parts as you like, multiply the sine of the complement of the altitude by the number of parts of the gnomon, and divide the product by the sine of the altitude. The quotient is the amount by which the shadow extends and stretches over the level ground, in the measure in which the gnomon has that number of parts. What the calculators have worked with, and what we have worked with

[76] The equinoctial day (*al-nahār al-muʿtadil*) is the day of 12 hours. In modern terms the rule is $\sin \varphi = \sin e \cdot \cos A / (\sin A \cdot \sin H)$, where φ is the latitude, e half the excess of the longest day, $H = 90° + e$ half the arc of the longest day, and A the amplitude of the rising of the beginning of Cancer. The rule is exact, since $\sin e = \tan \varphi \cdot \tan \varepsilon$, $\sin A = \sin \varepsilon / \cos \varphi$ and $\cos A = \cos \varepsilon \cdot \sin H$.

[77] Here the codex writes 90 in Indian figures, «٩٠» (Nallino: «so the codex itself»); elsewhere the text writes numbers in words or in abjad letters.

[78] In modern terms, $\sin e = \tan \varphi \cdot \tan \varepsilon$, where e is half the excess of the longest day, φ the latitude and ε the inclination.

in this book for the amounts of the shadow, is that the gnomon has 12 parts. It may be divided into fewer or more, as the person computing wishes, because the parts of the shadow are related only to the parts of the gnomon: one says that the shadow is so many parts long, in the measure in which the gnomon was made so many.[79]

If you wish to find the altitude from the horizontal shadow that we have described, multiply the whole [shadow] by itself, and add to the product the parts of the gnomon multiplied by themselves, which, on the basis we have laid down for the computation, is 144, the gnomon having 12 parts. Take the root of the sum: it is the hypotenuse of the shadow triangle. Keep it. Then multiply the parts of the gnomon by the radius; on the basis we have laid down, this always comes to 720. Divide these 720 by the hypotenuse of the shadow triangle that you kept, and find the arc of the quotient; the arc you obtain is the amount of the altitude. If you wish to compute it another way, multiply the shadow by the radius, divide the product by the hypotenuse of the shadow triangle, and find the arc of the quotient. The arc you obtain is the distance of the degree of the sun, or of another degree, from the zenith on the circle of altitude; subtract it from 90, and the remainder is the altitude.[80]

As for the erect shadow, I mean the vertical shadow, it is the reverse of the horizontal one: it is longest at noon and shortest at sunrise. If you wish to find this shadow from the altitude, multiply the sine of the altitude by the number of parts of the gnomon, and divide the product by the sine of what the altitude falls short of 90; the quotient is the amount of the shadow in parts of the gnomon.

If you wish to find the altitude from this vertical shadow, multiply the shadow by itself, add to it the product of the parts of the gnomon by themselves, and take the root of the sum: this is the hypotenuse of the shadow triangle. Then, if you wish, multiply the parts of the gnomon by the radius, divide the product by the hypotenuse of the shadow triangle, and find the arc of the quotient. The result is the amount between the degree of the sun and the zenith on the circle of altitude; subtract it from 90, and the remainder is the altitude. Or, if you wish, multiply the shadow by the radius, divide it by the hypotenuse of the shadow triangle, and find the arc of the quotient: the arc you obtain is the altitude.

Ar. p. 33

If you wish to find either of the two shadows from the altitude with the table, and you want the horizontal shadow, look in the table of the altitude and the shadow, in the column of the altitude, for the altitude you have, and take what stands opposite it in the column of the shadow: that is the amount of the shadow of that altitude. If you wish to find the altitude from this shadow, look for the shadow you want in the column of the digits of the shadow; where you find it, take the degrees of altitude entered opposite it in the column of the altitude: that is the amount of the altitude for that shadow.[81]

If there are minutes with the degrees of the altitude, or minutes with the digits of the shadow, find the value by interpolation, as I described to you in the chapter on the declination. That is: if there are minutes with the altitude, see what part of 60 they are, and take the same part of the difference between [the shadows of] the whole degrees and of the degree one greater. Always subtract it from the digits of the shadow of the whole degrees, since every greater altitude has a smaller shadow than a lesser one; the remainder is the shadow of that altitude. If there are minutes with the shadow whose altitude you wish to find, look at the shadow that you find in the table and subtract it from the shadow you have. Find what part the remainder is of the difference between that shadow and the one that belongs to the degree of altitude one less, and

[79] In modern terms the horizontal shadow is g · cot h, where g is the gnomon and h the altitude, and the vertical shadow, described below, is g · tan h.

[80] «The whole» (*al-kull*) is the whole length of the shadow; Nallino translates «the square of the shadow». The hypotenuse of the shadow triangle is literally «the diameter of the triangle of the shadow» (*quṭr muthallathat al-ẓill*): the line from the tip of the gnomon to the tip of the shadow.

[81] The digit (*iṣbaʿ*, literally «finger») is a twelfth of the gnomon.

take the same part of the 60 minutes by which the column of the altitude increases. Subtract the minutes you obtain from the altitude that you found opposite the shadow you took in the table, the one nearest to your shadow among those smaller than it; the remainder is the altitude.

If you wish to find the erect shadow, which is the vertical shadow, from the altitude with the table, subtract the altitude from 90 and take the shadow opposite the remainder, interpolating in the same way; the result is the vertical shadow. If you wish to find the altitude from this shadow, look for the shadow you want in the table, take what stands opposite it in the column of the altitude, interpolating, and subtract the result from 90; the remainder is the altitude. The shadow has been entered in this table on the basis that the gnomon is 12 parts, so whatever you work out with it of the shadow is on the basis that the gnomon is 12 digits.[82]

Chapter 11. On finding the azimuth of the altitude and of the shadow on the horizon circle, in any locality you want, at all times

Ar. p. 33
Ar. p. 34

Al-Battānī said: If you wish to find the azimuth of the altitude and of the shadow at any degree of all the signs, in any locality you want, take the declination of that degree and find its sine, and the direction of the declination. Then subtract this declination from 90 and find the sine of the remainder: this is the sine of the complement of the declination of the degree. Then find the sine of the latitude of the locality and the sine of what the latitude of the locality falls short of 90. Then take the altitude at whatever time of the day you like, and find its sine and the sine of what the altitude falls short of 90. Then multiply the sine of the declination of the degree by the radius and divide the product by the sine of the complement of the latitude of the locality: the result is the sine of the amplitude of the rising. Keep it, and note its direction, which is the direction of the declination. Then multiply the sine of the altitude by the sine of the latitude of the locality and divide the product by the sine of the complement of the latitude of the locality: the result is the sine of the difference of the horizon, which is always southern. If the sine of the amplitude of the rising and the sine of the difference of the horizon are in the same direction, add them; if they are in different directions, subtract the smaller from the greater and note the direction of the remainder. Multiply what you obtain from the addition or the subtraction by the radius, divide it by the sine of the complement of the altitude, and find the arc of the quotient: the result is the azimuth of the altitude.[83]

The shadow is then at the degree for which you computed. If at that time the degree is between the ascendant and the middle of the sky, this azimuth is counted on the horizon circle from the rising point of the beginning of Aries and of Libra towards the direction that you obtained.[84]

The azimuth can also be found by another method, with the angles that are used in finding the parallax, which we shall explain later in this book.

[82] The vertical shadow of an altitude is the horizontal shadow of its complement: $g \cdot \tan h = g \cdot \cot(90^\circ - h)$.

[83] In modern terms, $\sin Z = (\sin \delta / \cos \varphi - \sin h \cdot \tan \varphi) / \cos h$, where Z is the azimuth counted from the east or west point, positive towards the north, δ the declination, φ the latitude and h the altitude. $\sin \delta / \cos \varphi$ is the sine of the amplitude of the rising, and $\sin h \cdot \tan \varphi$, always southern, is what al-Battānī calls the sine of the difference of the horizon.

[84] The codex gives only the case of the eastern half of the sky. Plato of Tivoli's Latin shows that words are missing after «direction»; Nallino restores them in Arabic in the apparatus, and the Latin translation includes them: «[the direction] in which you found the two sines, or the greater of them if they differ; and if the degree is between the middle of the sky and the setting point, this azimuth is counted from the setting point of the beginning of Aries and of Libra on the horizon circle, towards that direction».

Chapter 12. On finding the meridian line, which is the direction of the south

Ar. p. 34
Ar. p. 35

Al-Battānī said: Suppose you wish to find the direction of the south, which is the meridian line, in any locality you want and at any time of the year you like, and the place of the sun is not known to you. Go to a place with an open horizon and a smooth, level surface that does not slope, and draw on it a circle of any size you like. Fix at the centre of the circle a thin rod with a pointed tip, straight and without any bend; its best length is a quarter of the diameter of the circle. Measure [the distance] from four sides of the circle to the tip of the rod, so that it stands truly upright on the centre. Then watch the shadow at the beginning of the day, when it is long. It keeps getting shorter; when it reaches the circumference of the circle and is about to enter it, mark its place on the circumference with a point, as a sign of the tip of the shadow. Then wait until noon has passed and the shadow begins to grow; when it reaches the circumference of the circle and is about to leave it, mark the place of its tip on the circumference with a second point, as [a sign of the tip of the shadow].[85]


Then divide the arc between the two points into halves, mark the place of the half of the arc with a point, and from this point draw a straight line through the centre of the circle to the other side of the circumference, extending it as far as you like. To do this, lay the edge of the ruler on the point at the half of the arc and on the centre, and draw a line through both the point and the centre to the circumference on the other side. This line is always the meridian line: whenever the shadow of the rod at the centre falls on this line, it is noon, whether the shadow is long or short. This line is the direction between south and north. Then quarter the circle with another line through the centre of the circle at right angles; the circle is divided by these two lines into four equal quarters, and this line is the direction between east and west. Then write at the ends of the lines the directions of the horizon, that is, east, west, north and south.[86]

The nearer the sun is to one of the two solstitial points, the more accurate the observation, because the sun moves slowly in declination between the two observations, I mean the two observations of the shadow. It is known that the moment of noon cannot be fixed exactly, because the sun passes quickly in declination through the meridian circle; but the moment of noon, or the moment nearest to it, is found. This is a diagram of the circle described, if God, the Exalted, wills.[87]

[85] The words in brackets at the end are Nallino's conjecture.

[86] «Half», in «the half of the arc», is lacking in the codex and supplied by Nallino.

[87] «In declination», in the second sentence, is Nallino's conjecture (in the emendanda printed in Part II).



[88]

Ar. p. 36

Al-Battānī said: Draw a circle about the centre H, and fix the indicating rod at the place of point H. Mark point A at the place of the tip of the shadow before noon, and the sign B at the place of its tip after noon. Divide the arc AB into halves at the sign G, and draw the line from G to the sign D. The line GHD is the meridian line; point D is the direction of the south, and point G the direction of the north. Then divide the arc GAD into halves at point Ṭ, and draw through the points Ṭ and H a line that goes out to point Z. Point Z is the direction of the east, and point Ṭ the direction of the west. Whenever the shadow of the indicating rod falls on the line HG, it is always noon.[89]

If the place of the sun is known to you, find the azimuth of any altitude you like at some time of the day, and watch for the given altitude. When the altitude becomes equal to it, mark on the circumference of the circle, at the shadow of the indicator, a sign that stands in the middle of the breadth of the shadow of the indicating rod. Then divide the quarter of the circle in which this point falls into 90 parts, and count from that point, towards the side opposite to the direction of the azimuth of that altitude, as many parts as the azimuth of the altitude. The division at which you arrive is the east point or the west point, according to the time of the altitude with which you worked, before noon or after it. From this sign draw a line through the centre of the circle, and quarter the circle with another line through the centre at right angles. Then you know the meridian line by this line, and the line of east and west by the line before it.

Likewise, if the horizon is in view from this circle at sunrise or sunset, the east point or the west point is known from the azimuth of the rising or setting of the degree of the sun on the horizon circle, which we have drawn as ABGD.

Ar. p. 37

If you wish to find the line between east and west in another way, and through it the line between north and south, this is done by finding the altitude whose azimuth has no inclination from the equinoctial rising or setting point. This is possible only when the sun is in the northern signs, from the beginning of Aries to the end of Virgo. This altitude is found as follows. Find the place of the sun in the ecliptic on the day you want, and its altitude at noon on the day for which you work. Then find the sine of this altitude and the sine of what it falls short of 90. Then find the azimuth of the rising or setting of the sun, at its place in the ecliptic at the noon for which you work; by the condition we have laid down it is always northern. Then take the sine

[88] As in the print, the south (D) is at the top, so that the east (Z) is on the left and the west (Ṭ) on the right. The letters of the figures are transliterated: ا A, ب B, ج G, د D, ه H, و W, ز Z, ح Ḥ, ط Ṭ, ك K, ل L, م M.

[89] The indicating rod (*al-ʿamūd al-mūrī*, «the rod that shows») is the rod set up at the centre.

of this azimuth and multiply it by the sine of the altitude, divide the product by the sine of the azimuth and the sine of the complement of the altitude added together, and find the arc of the quotient. The arc you obtain is the altitude whose azimuth has no inclination. When you know this altitude, watch the sun; when its altitude becomes equal to this altitude, mark a point on the circumference of the circle in the middle of the shadow of the indicator. It is the east point or the west point, according to the time at which you measure, that is, the equinoctial rising or setting point. Quarter the circle at this point with two lines that intersect at the centre at right angles, and with them mark the directions of the horizon.[90]

We give an example of this, and place it in the fourth clime, where the altitude of the pole is 36° 22′. We take the place of the sun at the beginning of Cancer. The altitude of the sun at noon is then 77° 13′, and its altitude at midnight, from the northern horizon, 30° 3′; it is known that this is equal to the altitude above the earth, on the line of the middle of the sky, of the degree opposite to it, which is 30° 3′. We also find this in another way, by doubling the altitude of the beginning of Aries in the said clime and subtracting from the result the altitude of the beginning of Cancer in the middle of the sky. Clearly the altitude of the beginning of Aries in the middle of the sky in this clime is 53° 38′, and its double 107° 16′; when 77° 13′ is subtracted from this, there remains its altitude in the middle of the sky below the earth, 30° 3′. We shall show that the azimuth of the beginning of Cancer at its rising in this clime lies 30° 0′ to the north of the rising of Aries.[91]

Since this is as we have described, we draw a circle of the middle of the sky, ABL, about its centre H, with the diameter LB. Let the diameter LB be half the horizon, and let point A be the place of the zenith. We join point A to point H, so that the arc BA is the quarter of the circle between the zenith and the horizon. Point H is the place of the rising of the beginning of Aries, and point G the place of the rising of the beginning of Cancer: for HB is the southern half of the horizon, the line HL the northern half of the horizon, and the line HA the line of the quarter circle that passes through the zenith and the rising point of the beginning of Aries. We mark at the point of the beginning of Cancer on the circle of the middle of the sky the point Z. The arc BZ is the altitude of the sun at noon, and the arc ZA its distance from the zenith, which is the complement of the altitude to a quarter of the circle. We mark at the altitude of the sun at midnight the point Ṭ, so that the arc ṬL is the arc of the altitude at midnight below the earth, and we draw the line ṬZ, which passes through the point G at which the beginning of Cancer rises. The point common to the line ṬZ and the line HA is the place at which the sun, when it rises to it, is on the azimuth of H, from which the beginning of Aries rises; it then has no inclination from the azimuth of the equinoctial risings, since the line from the zenith passes through the place of the sun and through point H of the horizon. We mark the place of the sun on the line HA with the sign M.[92]

Ar. p. 38


It is clear in this figure that the line HG is the line of the azimuth of the rising of the beginning of Cancer, and it is the sine of the azimuth. Further, we draw from point Z a perpendicular to the line HB, parallel to the line HA: this is the perpendicular ZK, which is the sine of the altitude at noon, so that the line KH that remains is the sine of the arc ZA, which is the complement of the altitude. We want to find the line HM, which is the sine of the altitude whose azimuth has no inclination; for the line HM is equal to the perpendicular DḤ, which is clearly the sine of the arc BD, the amount of the altitude that we seek, since the circle ABL passes through the zenith and the point of the beginning of Cancer. Now the right-angled triangle ZKG has known sides, and it is similar to the small triangle MHG, since the angle MHG is equal to the angle ZKH, the angle

[90] The altitude whose azimuth has no inclination is the altitude of the sun when it stands due east or due west; al-Battānī uses it again for the sundial in chapter 56 (Nallino). In modern terms the rule is $\sin h = \sin A \cdot \sin H / (\sin A + \cos H)$, where A is the amplitude of the rising and H the altitude at noon; it is exact, and equal to $\sin \delta / \sin \varphi$.

[91] For 30° 0′ the codex has 30° 3′; Nallino reads 30° 0′ with Plato of Tivoli, the value used at the end of the chapter, where the sine of this azimuth is taken as 30 parts.

[92] The figure is the meridian circle, with the horizon, the vertical through the east point and the day circle of the sun seen edge on as the straight lines LB, HA and ṬZ. Here and below Nallino corrects several letters of the figure where the codex has others; the translation follows Nallino's text.

GMH is equal to the angle KZG, and the angle KGZ is common to the two triangles. Therefore the ratio of the line ZK to the line KG is as that of the line MH to the line HG. Further, the ratio of the line HG to the line GK is as that of HM to KZ, and this is also the ratio of the line GM to the line GZ. If we take of the line KZ the part given by the ratio [of the line GM to the line GZ], there remains for us the ratio of the line HM to the line KZ; and it is the same if we take of the line KZ the part that the line GH is of the line GK: we obtain the ratio of HM to KZ.[93]



The computation of this: multiply the line HG, which has been shown to be 30 parts, by the line KZ, which is 58 parts 31 minutes and is the sine of the arc BZ; the result is 1755 parts and half a part. The line KH, which is the sine of the complement of the altitude, is 13 parts 17 minutes, so the lines HG and HK together are 43 parts 17 minutes, which is the whole line KG. When we divide that by the line KG, the result is 40 parts 33 minutes, which is the amount of the line HM that we seek, and the line DḤ is equal to it. Therefore the arc DB is 42° 32′, and this is the altitude whose azimuth has no inclination. This is what we wished to show, if God wills.[94,95]

Chapter 13. On finding the ascensions of the signs in every locality in two ways, by computation and from the table, and on the procedures with them that follow from this, if God wills

Ar. p. 39

Al-Battānī said: The ascensions of the signs at the place of the equator we have described above: there the signs cross the middle of the sky and the horizon with the same amount of times of the equator, and with this amount they also cross the middle of the sky in every locality. At the other places, those that decline from it towards the north, in all the localities, their ascensions differ from horizon to horizon. For when a locality has a latitude, that is, when it declines from the equator, the ascensions of the signs vary there, being greater or smaller than their ascensions in the middle of the sky, which are their ascensions in the right sphere. Every sign that rises

[93] The print names the small triangle «م ه ح», MHḤ; the angles that follow show that it is MHG, as in Nallino's translation. The words in brackets are Nallino's; the codex has «the line KG to the ratio of the line GM».

[94] «And five», in 1755, is supplied by Nallino; the codex has 1750. The quotient 1755;30 / 43;17 is 40;33,29 (Nallino).

[95] At latitude 36° 22′ the sine of the amplitude of the beginning of Cancer, HG, is 29;49 parts, not 30, and the rule then gives 42° 26′, the exact altitude of the sun on the prime vertical (sin h = sin δ / sin φ). The 42° 32′ of the text comes from taking HG as 30.

in a locality with more than it rises with in the right sphere has a counterpart that rises in that locality with less than it rises with in the right sphere, by the amount of that excess; and in every locality each sign sets with as much as its counterpart rises with there.[96]

Ar. p. 40

If you wish to know the amount of the equator that rises together with given parts of the ecliptic in any locality you want, take [the arc] from the beginning of Aries to the degree of the ecliptic you want, in ascensions of the right sphere. Find its sine, multiply it by the sine of half the excess of the longest day in that locality, divide the product by the radius, and find the arc of the quotient. The arc you obtain is the share of the difference of the day, in the quarter of the circle, that belongs to [the arc] from the first degree of Aries to that degree. Keep it. If you wish to find it another way, multiply the sine of the latitude of the locality by the sine of the declination of the degree, divide the product by the sine of what the latitude of the locality falls short of 90, multiply the quotient by the radius, divide it by the sine of what the declination of the degree falls short of 90, and find the arc of the quotient. The arc you obtain is the difference of the day in the quarter of the circle of the sphere. When you have found this share in either of the two ways, look: if the declination of the degree is northern, subtract the share you obtained from the times of the ascensions in the right sphere between the beginning of Aries and that degree; if the declination of the degree is southern, add the share to those ascensions. The ascensions you obtain after the addition or the subtraction are the ascensions from the beginning of Aries to that degree in that locality.[97]

Know that the ascension of Pisces is equal to that of Aries, the ascension of Virgo to that of Libra, the ascension of Aquarius to that of Taurus, the ascension of Capricorn to that of Gemini, the ascension of Sagittarius to that of Cancer, and the ascension of Leo to that of Scorpio. So for finding the ascensions it is enough to know the shares between the beginning of Aries and the beginning of Cancer, that is, from 1 degree to 90 degrees.

If you wish to tabulate the ascensions degree by degree, or at larger intervals, find the share of the difference of the day for one degree, for two degrees, three and four, up to the full 90 that complete the difference of the whole quarter of the circle. When you have done this, take the ascension in the right sphere of the first degree of Aries and put it in two places. Then subtract the share of the degree from one of the two places and add it to the other. The one subtracted from is the ascension of the first degree of Aries, and the one added to is the ascension of the first degree of Libra. Add the latter to 180: the sum is the ascension from the beginning of Aries to the first degree of Libra. Subtract it from 180: the remainder is the ascension from the beginning of Aries to 29 degrees of Virgo. Also subtract the ascension of the degree of Aries from 360: the remainder is the ascension from the beginning of Aries to 29 degrees of Pisces. Do the same with the share of two degrees, three and four, up to the full 90, until you have divided [the ascensions] over the whole sphere at whatever interval of the parts you want, if God wills.[98]

We have entered the ascensions of the signs for the city of al-Raqqa in full, degree by degree, and for the other climes at intervals of 10 degrees, because the ascensions differ little within an interval of this size. In the ascensions entered in the tables we have made the excess of the day increase by a quarter of an equal hour [from one table to the next], so that they are more accurate for the work with the ascensions that is needed, and more exact than ascensions computed at intervals of half an hour.

Ar. p. 41

If you wish to find the ascension of any degree you like from the table, look for the degrees whose ascension you wish to know, of whatever sign you like, in the common column of numbers in the table of the ascensions of the signs for the given clime, or in the ascensions of the right sphere,

[96] The counterpart (*naẓīr*) of a sign or a degree is the sign or degree opposite to it on the ecliptic.

[97] In modern terms the share is the ascensional difference Δ: $\sin \Delta = \sin \alpha \cdot \sin e = \tan \varphi \cdot \tan \delta$, where α is the ascension in the right sphere, e half the excess of the longest day, φ the latitude and δ the declination. The ascension at the locality is $\alpha - \Delta$ for a northern declination and $\alpha + \Delta$ for a southern one.

[98] «Subtract it from 180»: the codex has «from 360»; Nallino corrects it.

whichever you want, and take the times of ascension that stand opposite them in the column of the sign to which that number belongs. If you are working with the ascensions of the climes, this is the ascension from the beginning of Aries to that degree; if you are working with the ascensions of the right sphere, it is the ascension from the beginning of Capricorn to that degree. If there are minutes with the degrees, find what part of 60 they are, when the numbers increase by one degree, and take the same part of the difference between those ascensions and the ascensions that follow them, one degree further. Add the result to the ascensions you obtained opposite the whole degrees; the sum is the ascension of the degree and minute that you wanted. If the numbers increase by 10 degrees, see what part of the 10 degrees are the degrees and minutes that you have left over beyond what you find in the table, and take the same part of the differences of the ascensions in the table, I mean of the ascensions you found and those 10 degrees further on in the numbers. Add the result to the ascensions under the tens; the sum is the ascension of that degree.

If you wish to find the degrees of the signs from the ascensions, which is called taking the arc of the ascensions and converting them into degrees of equality, that is, degrees of the signs: look for the number of times of ascension that you have in the table of the ascensions of the right sphere or of the clime, whichever you want. Where you find it, or the nearest value smaller than it, take the degree of the signs entered opposite it in the common column of numbers: that is the degree you want of the sign in which you found the number of times. Then subtract [the times found in the table from] the times you have, and look at the remainder: if the numbers increase by one degree, multiply it by 60 minutes; if they increase by 10 degrees, multiply it by 600 minutes. Divide the product by the difference of the ascensions between that entry and the entry that follows it, and add the degrees and minutes that result from the division to the degrees you obtained first. The result is the amount of that sign that rises, or that culminates, according to which [table] you worked with. Or, if you wish, see what part of the difference of the ascensions the remainder is, and take the same part of the interval of the numbers; add the result to the degrees you had obtained.[99]

Ar. p. 42

If you wish to find the arc of the day and of the night from the table, that is, the amount of the equator that rises from sunrise to sunset, or from sunset to sunrise the next day: find the degree in which the sun is on the day you want, and take the times of ascension opposite it in the given clime whose latitude is equal to that of the city, or nearer to it than the other climes. Subtract them from the ascensions opposite the degree opposite to the degree of the sun in that clime; the remainder is the amount of the arc of the day. If the ascensions of the degree of the sun are greater than those of the degree opposite to it, which is the counterpart of the degree of the sun, add a revolution to the ascensions of the counterpart of the degree of the sun and subtract from the sum the ascensions of the degree of the sun: the remainder is the arc of the day. When you know the arc of the day, subtract it from a revolution: the remainder is the arc of the night.

If you want the arc of the day in another way, take the times of ascension opposite the degree of the sun in the clime, and also the times of ascension opposite the degree of the sun in the right sphere, and subtract 90 from the latter, so that they are counted from the beginning of Aries. When you have done this, take the difference between them and the ascensions that you obtained from the climes. Then look: if the times of the ascensions of the climes are the greater, subtract this difference from 90; if they are the smaller, add this difference to 90. The 90 after the addition or subtraction is the amount of half the arc of the day; double it, and you have the whole arc of the day. Know that this difference between the ascensions is the share of the degree of the sun in the difference, I mean the difference of the day. When you know it, look at the degree of the sun: if it is in the northern signs, add the difference to 90; if it is in the southern ones, subtract it from 90. The result is half the arc of the day, which is the part of the equator from the

[99] Degrees of equality (*daraj al-sawā'*) are degrees of the ecliptic, as against the times of the equator that rise or culminate with them; the Alfonsine Tables call them «equal degrees» (Nallino).

rising of the sun to its culmination at noon, and its double is the whole arc of the day; the two procedures come to the same.

If you wish to know the number of the equal hours of the day and of the night, divide the arc of the day or the arc of the night by 15; the result is the hours of whichever of the two you computed. When you know the hours of one of them, subtract them from 24; the remainder is the hours of the other.

If you wish to find the times of the seasonal hours of the day and of the night, of which there are always 12 in the day and as many in the night, and which are called the crooked hours, divide the arc of whichever you like, the day or the night, by 12; the result is the times of its hours. Subtract the times of the hours of whichever you computed from 30; there remain the times of the hours of the other. For these 30 are the times of two equal hours, and what the times of an hour of the night or of the day lack is added to the other.[100]

Ar. p. 43

If you wish to find the times of the hours in another way, take a sixth of the difference of the day mentioned earlier in this chapter. If the sun, or the degree you want, is in the northern half of the sphere, add this sixth to 15; if it is in the southern half, subtract it from 15. The result after the addition or subtraction is the times of the hours of the day. If you wish to find the times of the hours of the day from the table, enter the degree of the sun, or any other degree of the signs, in the common column of numbers of the table of the ascensions of the clime that is given for that city, and take the times of the hours entered opposite it in the column of the sign to which that number belongs; the result is the times of the hours of the day. If you wish to know the times of the hours of the night, enter in those ascensions the counterpart of the degree of the sun, which is opposite to it, or the counterpart of the degree you want, and take the times of the hours opposite it in the same way; the result is the times of the hours of the night. Either can also be found from the other, by subtracting one of them from 30 degrees: there remain the times of the other.[101]

If you wish to find the arc of the day from the times of the hours, or the arc of the night from them, whichever you like, multiply the times of whichever you want by 6; the result is the arc of half the day or of half the night, whichever you computed. Then double it; the result is its whole arc. If you multiply the parts of the times by 12, the result is the amount of the arc of the day or of the night for the degree for which you computed.

If you wish to convert equinoctial hours into seasonal ones, multiply the equal hours by 15 and divide by the times of the hours of the day or of the night, whichever you like; the result is seasonal hours of the night or of the day, according to what those equal hours were. If you wish to convert seasonal hours into equal ones, multiply the hours of the day by the times of the hours of the day, and the hours of the night by the times of the hours of the night, and divide the product by 15; the result is equal hours, with their fractions if a fraction remains, if God wills.

Chapter 14. On finding the latitudes of localities by observation

Ar. p. 43
Ar. p. 44

Al-Battānī said: If you wish to find the latitude of any locality you like, which is the altitude of the north pole there and also its distance from the equator, find the altitude of the sun at noon, in whichever way you like, when the sun passes the meridian line: with the quadrant or by finding the shadow. When you know the altitude, in either of the two ways, find the declination of the degree of the sun at that time. If it is northern, subtract it from the altitude; if it is southern, add it to it. The altitude after the addition or subtraction is the altitude of the beginning of Aries or

[100] The times of a seasonal hour are its length in degrees of the equator; an equal hour is 15 times. The translation follows Nallino's emendanda (Part II, p. XXX) in reading «المُعْوَجَّة», «the crooked», at p. 42, line 15.

[101] The 12 seasonal hours of the day take $180° + 2\Delta$ of the equator, where Δ is the difference of the day; one of them is therefore $15 + \Delta/6$ times.

of the beginning of Libra in that locality; subtract it from 90, and the remainder is the latitude of that locality. If you take the latitude of the locality from the table of the latitudes of the cities, it is approximate, and not as accurate as one found by observation.

Chapter 15. On finding the altitude of the sun at noon on any day you want

Ar. p. 44

Al-Battānī said: If you wish to find the altitude of the sun at noon on any day you want, find the declination of the degree in which the sun is. If it is northern, subtract it from the latitude of the locality; if it is southern, add it to it. Subtract the latitude of the locality, after the addition or the subtraction, from 90; the remainder is the altitude of the sun at noon. If the declination is greater than the latitude of the locality, you know that the sun is to the north of the zenith: add 90 to the latitude of the locality and subtract the declination of the degree; the remainder is equal to the altitude above the northern horizon.

If you wish to find the altitude of the sun at noon in another way, subtract the latitude of the locality from 90; the remainder is the altitude of the beginning of Aries. If the declination is northern, add it to the altitude [of the beginning of Aries]; if it is southern, subtract it from it. The altitude of the beginning of Aries after the addition or the subtraction is the altitude of the sun at noon. If it exceeds 90, subtract it from 180; the remainder is the altitude above the northern horizon.[102]

Chapter 16. On finding how many hours of the day have passed, by measuring the sun, and on finding the ascendant

Ar. p. 44
Ar. p. 45

Al-Battānī said: If you wish to know how many hours of the day have passed, by measuring the sun, find the altitude of the sun at noon on that day, and then half the arc of the day on that day. Then measure the altitude of the sun with a quadrant or by the shadow. When you know the altitude, at whatever time of the day you like, find the versed sine of half the arc of the day, in the way set out at the beginning of the book, in the chapter on finding the versed sines from the arcs. Then take the sine of the altitude of the sun at the time of the measurement, multiply it by the versed sine of half the arc of the day, and divide the product by the sine of the altitude at noon. Subtract the quotient from the versed sine of half the arc of the day, and find the arc of the remainder as a versed sine, as I described for taking the arc of the versed sines; keep the arc you obtain. If the measurement was made before noon, subtract this arc from half the arc of the day; if it was made after noon, add it to half the arc of the day. Half the arc of the day, after the addition or the subtraction, is the amount of the sphere that has turned from sunrise to the time of the measurement. Divide it by the times of the hours of the day, I mean of that day, found from the degree of the sun; the result is the number of seasonal hours of the day that have passed. If you divide it by 15, they are equal hours.[103]

If you wish to find the ascendant from the amount of the sphere that has turned, add the amount of the sphere that has turned to the times of ascension opposite the degree of the sun in the clime; from the sum you find the ascendant, in the way that we have explained earlier in the book. If you wish, take the arc that you obtained as a versed sine: it is the distance of the sun from the line of the middle of the sky. Divide it by the times of the hours of the day, and subtract the result from 6 hours if the measurement was made before noon, or add it to 6 hours if the measurement was made after noon; the result is the number of seasonal hours of the day that have passed, which you can convert into equinoctial hours if you wish. If you wish to find the ascendant from this arc, subtract it from the ascension of the degree of the sun in the right sphere if the

[102] The words in brackets are supplied by Nallino; the codex lacks them.

[103] In modern terms vers t = vers H · (1 − sin h / sin h_0), where t is the distance of the sun from the meridian in times (the hour angle), H half the arc of the day, h the altitude and h_0 the altitude at noon. The rule is exact.

measurement was made before noon, and add it to the ascension if the measurement was made after noon. With the ascension you obtain you find the ascendant and the middle of the sky, by taking the arc of these ascensions in the clime and in the right sphere and finding the degrees of the signs that correspond to them, in the way described in the chapter on finding the degrees of the signs from the times of ascension.[104]

Chapter 17. On finding the altitude from the hours

Ar. p. 46

Al-Battānī said: If you wish to find the altitude from the hours of the day that have passed, take the hours from sunrise to the given hour. If they are equinoctial hours, multiply them by 15; if they are seasonal, multiply them by the times of the hours of that day. Look at what you obtain in either way: if it is less than half the arc of the day, subtract it from half the arc of the day; if it is more, take half the arc of the day from it. The result is the distance of the sun from the middle of the sky. Find its versed sine and subtract it from the versed sine of half the arc of the day. Multiply the remainder by the sine of the altitude of the sun at noon on that day, divide the product by the versed sine of half the arc of the day, and find the arc of the quotient, as I described to you for taking the arc of the sines. The arc you obtain is the amount of the altitude above the horizon at the given hour. [If the hour is] before noon, the altitude is on the east side; if it is after noon, it is on the west side.[105]

Chapter 18. On finding the distances of the stars from the equator, and the parts of the signs that culminate with them[106]

Ar. p. 46
Ar. p. 47

Al-Battānī said: Suppose you wish to find the distances of the stars from the equator, and the part of the signs that culminates [with them], from their positions in longitude and latitude. Every star that is on the circle of the signs, that is, that has no latitude, behaves like the sun in its declination from the equator, which is its distance from it. But for a star that has a latitude on one side or the other, its distance from the equator falls short of its latitude and the declination of the part in which it is, when the two are added together or one is subtracted from the other, as the case requires. For the latitude of a star is measured on an arc that passes through the poles of the ecliptic and the position of the star in longitude and latitude, while its distance from the equator is measured on an arc that passes through the poles of the equator and the position of the star. Therefore a star that has a latitude culminates with a part of the signs other than its own, except one that in its course coincides with the point of the beginning of Cancer or of the beginning of Capricorn. Only then do its distance from the equator and its latitude lie on one arc, so that its distance is equal to the declination with the latitude of the star added to it or subtracted from it; and so it culminates with that one of the two points in which it is. Of the stars that have latitude, one between the beginning of Cancer and the end of Sagittarius culminates after the culmination of the degree in which it is, if its latitude is to the north of the belt of the signs, and before the culmination of the degree in which it is, if its latitude is to the south. One between the beginning of Capricorn and the end of Gemini culminates, if its latitude is to the north, with parts that precede the part in which it is, I mean before the culmination of the part in which it is; and if its latitude is to the south, with parts that follow the part in which it is, I mean after the culmination of the part of the signs in which it is.[107]

[104] The ascension in the right sphere is counted from the beginning of Capricorn (chapter 5): taken in the table of the clime, it gives the ascendant; taken in the table of the right sphere, the degree in the middle of the sky.

[105] In modern terms $\sin h = \sin h_0 \cdot (\text{vers } H - \text{vers } t) / \text{vers } H$, with the letters of the note to chapter 16: the same relation, solved for the altitude.

[106] The translation reads «تجوز» for «نجوز» (p. 47, line 3), a misprint that the corrigenda do not list.

[107] Schiaparelli, in Nallino's commentary, found the second sentence obscure. With «the declination of the part» understood as its second declination (see the next note), it is a correct statement: the declination δ of a star is never greater than its latitude β and the second declination β' of its degree taken together, since $\sin \delta = \sin(\beta \pm \beta') \cdot \cos \varepsilon$

If you wish to find the distance from the equator of one of the stars that have latitude, and the parts of the signs with which it culminates, find the latitude of the star and its direction, and the declination of the part in which it falls. If the latitude and the declination are in the same direction, add them together; if they are in different directions, subtract the smaller from the greater. The result is the adjusted latitude; note the direction in which it falls. Then take the sine of this adjusted latitude, multiply it by the sine of what the whole inclination falls short of 90, divide the product by the sine of what the part falls short of 90, that is, of the complement of its declination, and find the arc of the quotient. The arc you obtain is the distance of the star from the equator, in the direction of the adjusted latitude. Keep it.[108]

Ar. p. 48

Then take the distance of the degree in which the star is from the beginning of Cancer or the beginning of Capricorn, whichever the degree is nearer to, before it or behind it. That is: take the times of ascension in the right sphere opposite the part in which the star is. If they are less than 90, take them as they are; if they are more than 270, subtract them from 360. What you obtain in either case is the distance of the star from the beginning of Capricorn. If they are more than 90, up to 180, subtract them from 180 and take the remainder; if they are more than 180, up to the full 270, take 180 from them. What you obtain in either case is the distance of the degree from the beginning of Cancer. Keep whichever it is, and find its sine as well. Then take the sine of the latitude of the star, multiply it by the sine of the whole inclination, and divide the product by the sine of the complement of the distance of the star from the equator. Multiply the quotient by the sine of the distance of the degree in which the star is from the beginning of Cancer or of Capricorn in the right sphere, which you have kept, divide the product by the radius, and find the arc of the quotient. The arc you obtain is the difference of the passage of the star through the middle of the sky.[109]

If the star is between the beginning of Cancer and the end of Sagittarius and its latitude is northern, add the difference of its passage through the middle of the sky to the times of ascension in the right sphere opposite the part in which the star is; if its latitude is southern, subtract the difference of its passage from these times, and proceed as before. If the star is between the beginning of Capricorn and the end of Gemini and its latitude is northern, subtract the difference of its passage from these times; if its latitude is southern, add the difference of its passage to the times. Then take the degree of the signs that stands opposite the times of ascension of the star's degree in the right sphere, after the addition or the subtraction, in the ascensions of the right sphere: that is the part of the signs that culminates with the star, I mean [a degree] of the sign in which you found the number of times, if God wills.

/ cos β' and cos $\beta' \geq \cos \varepsilon$; it is equal to them only when $\beta' = \varepsilon$, at the beginnings of Cancer and Capricorn, as the following sentences say.

[108] The «declination» of the part here must be its second declination: the arc of the circle through the poles of the ecliptic between the degree of the star and the equator. With it the rule is exact, $\sin \delta = \sin(\beta \pm \beta') \cdot \cos \varepsilon / \cos \beta'$ (Nallino, after Schiaparelli, who derives it from Menelaus' theorem). Al-Battānī calls both declinations by the same name, and does not say here how the second is found.

[109] The translation keeps the reading of the codex and of Plato of Tivoli, «by the radius». Nallino, following Schiaparelli, prints in its place «by the sine of what the declination of the degree in which the star is falls short of 90», holding the rule to be false otherwise. The emendation is not needed. The distance of the star's degree from the solstitial point is taken here in the right sphere, as an arc of the equator, and the sine of that distance is cos α, where α is the right ascension of the degree; with it the rule of the codex is exact: $\sin \Delta = \sin \beta \cdot \sin \varepsilon \cdot \cos \alpha / \cos \delta$, where Δ is the difference of the passage. Schiaparelli's own derivation, $\sin \Delta = \sin \beta \cdot \sin \varepsilon \cdot \cos L / (\cos D \cdot \cos \delta)$, with L the longitude and D the declination of the degree, is the same rule, since $\cos L = \cos \alpha \cdot \cos D$; Schiaparelli's objection takes the distance to be measured on the ecliptic. With the emendation the result is too large by the factor 1/cos D: for a star at longitude 60° and latitude 10° north, the codex's rule gives 2.45°, the true value, and the emended one 2.61°.

Chapter 19. On finding the arc of the day of a star, and the times of its hours, in every locality

Ar. p. 48
Ar. p. 49

Al-Battānī said: Suppose you wish to find the arc of the day of any star you like, that is, its stay above the earth from the time it rises until it sets, which is the part of the equator that rises from the rising of the star to its setting. Multiply the sine of the distance of the star from the equator by the sine of the latitude of the locality, and divide the product by the sine of what the latitude of the locality falls short of 90. Multiply the quotient by the radius, divide the product by the sine of what the distance of the star from the equator falls short of 90, and find the arc of the result. The arc you obtain is the difference of the quarter of the circle of the star. If the distance of the star from the equator is northern, add the difference of the quarter of its circle to 90; if it is southern, subtract it from 90. The result after the addition or the subtraction is half the arc of the day of the star; keep it. Then take a sixth of it: the result is the times of its hours above the earth. Then double half the arc of its day: the result is the whole arc of the day of the star above the earth. Subtract it from 360: the remainder is the whole arc of its night below the earth. Likewise subtract the times of its hours of the day from 30: the remainder is the times of its hours of the night, which are below the earth. As for a star that has no latitude, its arc of the day is the arc of the day of the degree in which it is, without any difference, because it runs exactly the same course as the sun.[110]

Chapter 20. On finding the degree of the ecliptic with which a star rises and the one with which it sets, in every locality[111]

Ar. p. 49

Al-Battānī said: If you wish to find the degree of the signs with which a star rises and the one with which it sets, take half the arc of the day of the star and half the arc of the day of the degree that culminates with it, and find the difference between them: this is half the difference of the two days; keep it. Then look: if half the arc of the day of the star is greater than half the arc of the day of the degree that culminates with it, subtract half the difference of the two days from the times of ascension opposite the part that culminates with the star in the given clime; if half the arc of the day of the star is the smaller, add half the difference of the two days to those times. The times of the part that culminates with the star in the clime, after the addition or the subtraction, are the times of ascension of the degree with which the star rises in that locality. Find the degree of the signs opposite them in the ascensions of the clime: it is the part with which the star rises in that locality, of the sign in which the number of times fell.

Ar. p. 50

If you wish to find the degree with which that star sets, take the times opposite the degree that is the counterpart of the degree culminating with the star, in that clime. Then look: if half the arc of the day of the star is greater than half the arc of the day of the degree that culminates with it, add half the difference of the two days to those times; if half the arc of the day of the star is the smaller, subtract half the difference of the two days from those times. The times after the addition or the subtraction are the times of ascension of the degree opposite to the degree with which the star sets. Take the degree of the signs that stands opposite them in the ascensions of the clime: it is the degree opposite to the degree with which the star sets. Find the counterpart of that degree: it is the degree of the ecliptic that sets with the setting of the star. It is known that if the star has no latitude, its passage through the middle of the sky does not differ [from that of its degree], and it rises and sets with the part of the ecliptic in which it is.

Or, if you wish, add the whole arc of the day of the star to the times of ascension, in the clime, of the degree with which it rises; the sum is the ascension of the degree that is the counterpart

[110] The difference of the quarter of the circle of the star is its ascensional difference, the share of chapter 13: $\sin \Delta = \tan \varphi \cdot \tan \delta$, where δ is here the distance of the star from the equator.

[111] The print has «الّني» for «الّتي» four times on p. 50 (lines 1, 6, 10 and 12), a dot missing.

of the degree with which it sets. Find the degree of the signs that corresponds to it: the star sets with the counterpart of that degree. You can also find the degree with which the star rises and the one with which it sets in another way. Take the times of ascension in the right sphere of the part that culminates with the star, and both add half the arc of the day of the star to them and subtract half its arc of the day from them. The one added to is the ascension of the counterpart of the degree with which it sets, and the one subtracted from is the ascension of the degree with which it rises, in the clime. Take the degrees of the signs opposite them according to the rule.[112]

Chapter 21. On finding how many hours of the night have passed, by measuring a star, and on finding the ascendant[113]

Ar. p. 50
Ar. p. 51

Al-Battānī said: If you wish to know how many hours of the night have passed, by measuring a star, find the degree that culminates with the star, half the arc of the day of the star, and the degree with which the star rises, as has been explained to you before this chapter. Find also the altitude of the star in the middle of the sky. That is: take the distance of the star from the equator; if it is northern, add it to the altitude of the beginning of Aries in that locality, and if it is southern, subtract it from it. The altitude of Aries after the addition or the subtraction is the altitude of that star in the middle of the sky. Whenever it comes out greater than 90, subtract it from 180: the remainder is its altitude above the northern horizon, and the star is then on the north side of the zenith. Then find the versed sine of half the arc of the day of the star, multiply it by the sine of the altitude of the star at the time of the measurement, and divide the product by the sine of the altitude of the star in the middle of the sky. Subtract the quotient from the versed sine of [half] the arc of the day of the star, and find the arc of the remainder as a versed sine; keep the arc you obtain. If at the time of the measurement the star is on the east side of the middle of the sky, subtract this arc from half the arc of the day of the star; if the star is on the west side, add it to it. Half the arc of the day of the star, after the addition or the subtraction, is the amount of the sphere that has turned from the rising of the star to the hour of the measurement; keep it.[114]

Then look: if the part with which the star rises is between the degree of the sun and the degree of its counterpart, the star rose by day; if it is between the counterpart of the degree of the sun and the degree of the sun, it rose by night. If it rose by day, take the times of ascension in the given clime of the degree with which the star rose, and subtract them from the times of ascension opposite the counterpart of the degree of the sun, which is opposite to it, in that clime. Subtract the remainder from the amount of the sphere that has turned since the rising of the star, which you have kept; the remainder is the amount of the sphere that has turned from sunset to the hour of the measurement. Divide it by the times of the hours of the night; the result is the number of seasonal hours of the night that have passed. If the star rose by night, subtract the times of ascension opposite the counterpart of the degree of the sun from the times opposite the part with which the star rose in that clime, and add the remainder to the amount of the sphere that has turned since the rising of the star; the sum is the amount of the sphere that has turned from sunset to the hour of the measurement. Divide it by the times of the hours of the night, in the same way; the result is the number of seasonal hours of the night that have passed. If you divide the amount of the sphere that has turned since sunset by 15, the result is the number of equal hours of the night that have passed.

Ar. p. 52

If you wish to find the ascendant from the amount of the sphere that has turned since the rising of the star, add the amount of the sphere that has turned since the rising of the star to the times

[112] The ascensions in the right sphere are counted from the beginning of Capricorn (chapter 5), so that they can be entered directly in the table of the clime.

[113] The print has «الّني» for «الّتي» on p. 52, line 1, a dot missing.

[114] This is the rule of chapter 16, applied to a star. «Half» is lacking in the Arabic at its second occurrence; Nallino's translation supplies it.

of ascension opposite the part with which the star rises in the clime, and with the sum find the ascendant and the middle of the sky by the rule given before. If you wish to find the ascendant in another way, take the arc that you obtained as a versed sine and subtract it from the times of ascension, in the right sphere, of [the part] that culminates with the star, if the star is on the east side, and add it to these ascensions if it is on the west side. With the times you obtain after the addition or the subtraction you find the ascendant in the same way, and the middle of the sky as well.

If you measure with the moon in particular, you need to know its parallax, so that you have its visible position correct, I mean the position in which it is seen, in longitude and latitude. From it you then find its visible distance from the equator, the visible part that culminates with it, half the arc of the day of its visible position on the ecliptic, half the arc of the day of the visible part that culminates with it, and the visible degree with which it rises. When you know all this, take the altitude of the moon and work with it, after finding the altitude of the moon in the middle of the sky from its visible distance from the equator.

Chapter 22. On finding the altitude of the stars from the hours of the night, in every locality[115]

Ar. p. 52

Al-Battānī said: If you wish to find the altitude of any star you like from the hours, take the degree that is in the middle of the sky at that time, and the rising and the setting degree. Then find the distance of the star you want from the line of the middle of the sky at that time. That is: take the times between the part of the middle of the sky and the part that culminates with the star, in the right sphere. If the degree that culminates with the star is to the east of the degree of the middle of the sky, subtract the times of ascension of the degree of the middle of the sky from the times of ascension of the degree that culminates with the star; if it is to the west, subtract the times of ascension of that degree from the times of ascension of the degree of the middle of the sky. The result after the addition or the subtraction is the distance of the degree that culminates with the star from the line of the middle of the sky.

Ar. p. 53

If you wish to find this in another way, take the times opposite the part with which the star rises in the clime, and take the times opposite the counterpart of the part with which the star sets. If the part that culminates with the star is to the east of the middle of the sky, subtract the times opposite the degree with which the star rises from the times opposite the rising part; if the degree is to the west of the middle of the sky, subtract the times opposite the rising part from the times opposite the counterpart of the part with which the star sets. What you obtain in either case is its distance from the horizon. Subtract it from half the arc of the day of the star; the remainder is the distance of the star from the line of the middle of the sky.

When you know the distance of the star from the line of the middle of the sky, on whichever side it is, find the versed sine of this distance and subtract it from the versed sine of half the arc of the day. Multiply the remainder by the sine of the altitude of the star in the middle of the sky, divide the product by the versed sine of half the arc of the day of the star, and find the arc of the quotient as a direct sine, as you take the arc of the sines; the arc you obtain is the altitude of the star at that hour. It is known that if the part with which the star rises follows the part that is rising at that time, the star has not yet risen; if it precedes the rising part, the star has risen and is above the earth. If the part with which the star sets follows the setting part, the star has not yet set and is above the earth; if it precedes it, the star has set. For a star does not rise until the part with which it rises has risen, and does not set until the part with which it sets has set. As for the moon, you find its visible altitude from its distance from the equator, if God wills.[116]

[115] The print has «الّني» for «الّتي» on p. 52, line 15, a dot missing.

[116] This is the rule of chapter 17, applied to a star: $\sin h = \sin h_0 \cdot (\text{vers } H - \text{vers } t) / \text{vers } H$, where h_0 is the altitude of the star in the middle of the sky.

Chapter 23. On finding the azimuth of any star from its altitude and its place in the sphere

Ar. p. 53
Ar. p. 54

Al-Battānī said: If you wish to find the azimuth of any star you like on the horizon circle, find the altitude of the star at that time, the distance of the star from the equator and the latitude of the locality. Then proceed with them in the way that I described to you in the chapter on finding the azimuth of the altitude and of the shadow, leaving out nothing, except that you use the distance of the star from the equator in place of the declination of the degree of the sun. If you wish to find the azimuth of the moon, do this with its visible distance from the equator, so that you have the azimuth of the moon on the circle of altitude correct; and likewise for every star whose azimuth on the horizon circle you wish to find, if God wills.

Chapter 24. On finding the distance of a star from the equator, and the part that culminates with it, from the parts of the signs that rise or set [with it] and from the amplitude of its rising and setting on the horizon circle

Ar. p. 54

Al-Battānī said: Suppose you wish to find which degree of the signs culminates with a star, and the distance of the star from the equator, from the azimuth of its rising or setting and the part of the ecliptic that rises or sets with it, when these are known from some measurements. Multiply the sine of the altitude of the beginning of Aries in that locality by the sine of the azimuth of the rising or setting of the star, divide the product by the radius, and find the arc of the quotient. The arc you obtain is the distance of the star from the equator, on the side of the azimuth.[117]

With it find half the arc of its day, in the way described for finding half the arc of the day of a star from its distance from the equator. Then look: if the star is on the eastern horizon, add half the arc of its day to the times of ascension, in the clime, of the degree that rises with it; if it is on the western horizon, subtract half the arc of its day from the ascensions of the part with which it itself sets. Enter what you obtain, in either case, in the ascensions of the right sphere and take the degree of the signs opposite it: that is the part that culminates with the star.[118]

Chapter 25. On finding the part in which a star is, and the latitude of the star, from its distance from the equator and the degree of the signs that culminates with it

Ar. p. 54
Ar. p. 55

Al-Battānī said: Suppose you wish to find the part in which a star is, and the latitude of the star, from its distance from the equator and what culminates with it, when these are known from measuring the altitude of the star in the middle of the sky and the degree that culminates with it, or from measuring it at the horizon. When the altitude of a star in the middle of the sky has been taken and the difference between it and the altitude of the beginning of Aries in that locality is known, this is its distance from the equator, on the side on which it falls: if the altitude is greater than the altitude of the beginning of Aries, the distance is to the north, and if it is less than the altitude of the beginning of Aries, the distance is to the south. The part that culminates with it at that time is found from the part of the signs that culminates at that hour, by measuring another star whose position is known, or by other measurements with which the part of the middle of the sky can be found. If it can be known only from the rising or setting of the star on the horizon circle and the part that rises or sets with it, [it is found] as we have explained in the preceding

[117] In modern terms $\sin \delta = \cos \varphi \cdot \sin A$, where A is the amplitude; this is the rule of chapter 7 solved for the declination.

[118] The rule for the eastern horizon is exact, with the ascensions in the right sphere counted from the beginning of Capricorn (Nallino). The rule for the western horizon is wrong as it stands: the ascension to be taken is that of the counterpart of the part that sets with the star, as in chapter 20, since that counterpart rises when the star sets. With the setting part itself the result is wrong by 180° plus twice the ascensional difference of that part. Nallino's commentary states the rule as printed, without remark.

chapter, from whatever allows the rising or setting part of the ecliptic and its azimuth on the horizon to be known.

Ar. p. 56

When you know this, in whichever way you found it, take the declination of the part that culminates with the star and the distance of the star from the equator. If both are on the same side, subtract the smaller from the greater; the remainder is the adjusted distance. Keep it, and find its sine and the sine of what this distance falls short of 90. Then find the sine of the whole inclination and the sine of what the whole inclination falls short of 90. Then subtract the sine of the complement of the whole inclination from 120; the remainder is the longest chord. Then subtract the declination of the part that culminates with the star from 90, find the sine of the remainder, and subtract that too from 120; the remainder is the exceeding chord. Keep all these by their names. Then multiply the sine of the whole inclination by the radius, and divide the product by the sine of what the declination of the part that culminates with the star falls short of 90: the result is the sine of the adjusted inclination; keep it with its name and its direction. Then find its arc, subtract the arc from 90 and find the sine of the remainder: this is the sine of the complement of the adjusted inclination. Then multiply the sine of the adjusted inclination that you kept by the sine of the adjusted distance mentioned earlier in this chapter, and divide the product by the sine of the complement of the adjusted distance. Multiply the quotient by the exceeding chord and divide the result by the longest chord. Multiply the quotient by the sine of the complement of the whole inclination and divide it by the sine of the complement of the adjusted inclination. Multiply the quotient by the sine of the distance of the degree that culminates with the star from the beginning of Cancer or the beginning of Capricorn, whichever it is nearer to on either side, I mean behind it or in front of it, in ascensions of the right sphere. Divide the result by the radius and find the arc of the quotient: the arc you obtain is the variation of the star. Keep it.

Then look: if the part that culminates with the star is between the beginning of Cancer and the end of Sagittarius, and the distance of the star from the equator is northern, subtract the variation of the star from the times of ascension in the right sphere of the part that culminates with the star; if it is southern, add it to them. If the star is between the beginning of Capricorn and the end of Gemini, and its distance from the equator is northern, reverse this and add the variation of the star to those times; if it is southern, subtract it from them. Find the degree of the signs opposite the times obtained after the addition or the subtraction, in the ascensions of the right sphere: the result is the degree and minute of the signs in which the star is, if God wills.

If the distance of the star from the equator and the declination of the part that culminates with the star are on different sides, the way to work is to add them together: the sum is the adjusted distance. Multiply the sine of the whole inclination by the sine of the distance of the star from the equator, divide the product by the sine of what the adjusted distance falls short of 90, multiply the quotient by the sine of what the declination of the part that culminates with the star falls short of 90, and divide the product by the radius: the result is the sine of the adjusted inclination. Multiply it by the sine of the distance of the star from the equator as well, divide the product by the sine of the complement of the distance of the star from the equator, multiply the quotient by the exceeding chord, and divide the result by the longest chord: the result is the dividend; keep it with its name. Then find the arc of the sine of the adjusted inclination that you obtained, subtract the arc from 90, take the sine of the remainder and multiply it by the dividend that you kept. Divide the product by the sine of the complement of the whole inclination, and multiply the quotient by the sine of the distance of the part that culminates with the star from the beginning of Cancer or the beginning of Capricorn, whichever it is nearer to in front of it or behind it, in the right sphere. Divide the product by the radius and find the arc of the quotient: the arc you obtain is the variation of the star. Follow the first rule with it, until you know the part of the ecliptic in which the star is.[119]

Ar. p. 57

[119] Schiaparelli, in Nallino's commentary, judges these rules for the longitude false. Schiaparelli suggests that they are not al-Battānī's, but were written to fill a leaf lost from the exemplar from which the Escorial codex and Plato

If you wish to find the latitude of the star and the direction of its latitude, multiply the sine of the distance of the star from the equator by the sine of what the declination of the degree in which you have found the star falls short of 90, divide the product by the sine of what the whole inclination falls short of 90, and find the arc of the quotient. Then look: if the arc is greater than the declination of the degree in which you found the star, subtract the declination of that degree from it; if the arc is the smaller, subtract it from the declination of that degree. The result after the addition or the subtraction is the latitude of the star. If you wish to know the direction of the latitude, look: if the arc is greater than the declination of the degree in which the star is, the latitude is on the side of that declination; if it is less, the latitude is on the side opposite to the declination of the degree of the star.[120]

Chapter 26. On finding the distances between the stars according to their configuration in the sphere and the positions of one relative to another; by it the true distance of the moon from the sun is found, according to the latitude of the moon[121]

Ar. p. 57

Al-Battānī said: We wish to show how the amounts of the distances between the stars are found on the greatest circle, the one that lies between the two poles of the ecliptic, which is the circle of the signs. It has been shown by proof that in every quadrilateral inscribed in a circle, the products of each two opposite sides, one by the other, added together, are equal to the product of one of its diagonals by the other. In every quadrilateral inscribed in a circle in which two of the sides are parallel, the two remaining sides are opposite and, for the reason given above, equal; when they are produced they meet in a point. Its diagonals too are equal, and the product of one of them by the other is equal to the product of one of the parallel sides by the other together with the product of one of the opposite sides by the other.[122]

Ar. p. 58

Since this is so, we draw a line for a piece of the ecliptic and mark its ends A and B, and from the points A and B we draw two lines that meet at Z; let the point Z be one of the poles of the ecliptic, whichever it is. Each of the lines AZ and BZ is then the line of a quarter of the circle that passes through the poles of the ecliptic and the positions of the two stars. We put one of the two stars at the point A of the ecliptic, and the other inclined from the ecliptic in latitude, at the point Ṭ; its position on the ecliptic is known to be the point B. The arc BṬ is the latitude of the star, and we draw the line AṬ, which is the amount of the distance between the two stars. The line AṬ and the arc AṬ are found by drawing from the point Ṭ a line parallel to the line BA, the line ṬH, and from the point Z, the pole, a line to the middle of the line BA, the line ZG, and by marking the sign M at the place where it cuts the line ṬH. The quadrilateral ṬBAH is then a figure of four sides, of which the sides BA and ṬH are parallel, and ṬB and HA equal and opposite; produced, they meet at the point Z. It is clear on the sphere that each of the arcs ZA, ZB and ZG is a quarter of a circle; therefore the arcs ZṬ, ZM and ZH are equal, and so each of the arcs ṬB, MG and HA is equal. By what has been said before, the line ṬM has also been shown to be half the line ṬH. Since the right-angled triangle BGZ is similar to the small right-angled triangle ṬMZ, the line ṬM is known in amount from the line BG, which is already known; and since they are in one triangle, the ratio of ṬM to BG is as the ratio of ZṬ to ZB, and also as the ratio of ZM to ZG.

---

of Tivoli's version both derive; al-Battānī could have found the longitude by inverting the rules of chapter 18. A numerical check bears out the judgement. When the star and its culminating degree are on the same side of the equator, the first rule comes close to the true variation without being exact: for a star at longitude 60° and latitude 10° north it gives 2.48°, against the true 2.45°, and for one at 150° and 25° north 10.63°, against 10.47°. When they are on opposite sides, the second rule is far off: for a star at longitude 200° and latitude 12° north it gives 0.07°, against the true 4.53°.


[120] The «declination» of the degree is here again its second declination β' (chapter 18). With it the rule is exact (Nallino, after Schiaparelli): $\sin x = \sin \delta \cdot \cos \beta' / \cos \varepsilon$, and the latitude is the difference between x and β'.

[121] The translation follows Nallino's corrigenda in reading «ضرب», «product», for «صرب» (p. 57, line 16).

[122] The first theorem is Ptolemy's theorem on the quadrilateral inscribed in a circle (*Almagest* I 10). For «inscribed in a circle», in the second sentence, the codex has «on a sphere or on a plane»; the reading is Nallino's.

When the line ṬM is known, the whole line ṬH is known, since it is twice ṬM.[123]

Let the arc AB between the two stars in longitude be 60 parts, so that the arc BG is half of that, 30 parts. We take the latitude of the star whose position in longitude is the point B to be 30 parts: this is the arc BṬ. Then by what has been said about the sphere the arc MG is also 30 parts, and so the arc MZ that remains is 60 parts; its sine, which is the line MZ, is [51 parts] 57 minutes 42 seconds, approximately. The arc BG has been shown to be 30, and its sine, the line BG, is also 30 parts. The whole arc ZG is a quarter of a circle, and the line ZG is its sine, which is 60 parts, the radius. So if we take of the line BG the part given by the ratio of the line ZM to ZG, there remains the ratio of the line ṬM to the line BG; this is what we wished to show.[124]



Ar. p. 59

Al-Battānī said: The computation of this is to multiply ZM by BG, which gives 1558 parts 51 minutes, approximately. When this is divided by the line ZG, the result is 25 parts 58 minutes 51 seconds, approximately, which is the amount of the line ṬM. So the arc ṬM is 25° 39½′, and the whole arc ṬH is twice that, 51° 19′. The quadrilateral BṬHA is then known in its sides, and the diagonal ṬA is known too, by what has been said before about finding the full chords that fall in these sides. Since the sine ṬM has been shown to be 25;58,51, the line ṬH, which is the full chord of ṬH, is twice that, 51 parts 57 minutes 42 seconds. The full chord of the arc BA is twice the sine BG, which is 60 parts. The full chord of the arc ṬB is 31 parts 3 minutes 30 seconds: this is the chord of the 30 parts that are the latitude of the star. The line ṬB is equal to it: it is the sine of 15 parts, doubled, and these 15 are half the arc ṬB. When the side BA is multiplied by the side ṬH parallel to it, the product is 3117 parts 42 minutes, and the product of ṬB by HA, which is equal to it, is 964 parts 37 minutes, approximately. Added together, they equal the product of ṬA by itself, since ṬA is equal to HB. So ṬA by itself is 4082 parts 19 minutes, and its root is 63 parts 54 minutes, approximately, which is the amount of the line ṬA. So the arc ṬA, the arc of the full chord, is 64° 19′, and this is the true distance between the two stars, whose difference in longitude was only 60 degrees.[125]

Further, if the two stars are both at the point B in longitude, and one of them at the point Ṭ in latitude, the distance between them is the amount of the latitude alone, the arc ṬB. If one of them is at the point Ṭ and the other at the point H, and they have equal latitudes in this figure, the distance between the two stars is the arc ṬH. Likewise, if one of them were at the point H and the other at D, the distance between them would be known, by drawing the line DK parallel to

[123] The sentence from «therefore the arcs ZṬ, ZM and ZH» to «is equal» is printed by Nallino in brackets as the addition of an unskilled reader. Its equalities hold if M lies on the circle of latitude through Ṭ and H; but the arc ṬH of the computation below is an arc of the great circle through Ṭ and H, whose middle is nearer to the pole. The computation does not depend on them: the ratio of ṬM to BG is that of ZṬ to ZB, and the sine of ZṬ is the 51;57,42 used below.

[124] «51 parts» is supplied by Nallino; the codex lacks it. Nallino takes the passage on the arcs MG and MZ to be corrupt, and reads «the arc ZṬ that remains is 60 parts, and its sine, the line ZṬ, 51;57,42»; and in the last sentence Nallino understands: if BG is reduced in the ratio of ZM to ZG, the result is ṬM.

[125] Nallino reads ZṬ and ZB for ZM and ZG in the first sentence, with the same numbers. For 51° 19′ the codex has 51° 59′. The true distance is 64° 20′, since cos d = cos 30° · cos 60°.

the line BA and to the line ṬH and finding the amount of DK in the way we have described: the quadrilateral DṬHK then becomes known in its sides, and so the line HD between the two stars, the diagonal of the quadrilateral, becomes known too. The distance of the star at the point D from the one at the point A is known from the quadrilateral DBAK.[126]

Ar. p. 60

Likewise, if you wish to know the distance between two stars, look. If one of them has no latitude, like the sun or another of the stars that are on the belt of the signs, and the other has a latitude on either side, take the amount of degrees of longitude between them: this is the first side. Then take half of it and find its sine, multiply it by the sine of what the latitude of the star falls short of 90, divide the product by the radius, and keep the result as it is. Then take its arc and double it: this is the second side. Then find the full chord of the latitude of the star by the rule given to you at the beginning of the book, which is to take the sine of half the latitude and double it: the result is the full chord of the latitude. Then find the full chord of the first side and the full chord of the second side as well; the fourth side is equal to the third, whose full chord is the chord of the latitude. When you have done this, multiply the full chord of the first side by the full chord of the second side, and add to it the full chord of the latitude multiplied by itself, which is the product of the third side by the fourth. Take the root of the sum and find its arc as you find the arcs of full chords, that is, take half of it, find its arc and double the arc: the result is the distance between the two stars.[127]

If both stars have latitude on the same side, and the two latitudes are equal, find the arc of the second side: it is the amount between them. If the latitudes on the same side are unequal, subtract the smaller from the greater: the remainder is the third side, and the fourth side is equal to it; keep it. Then subtract the latitude of each of them from 90, find the sine of the remainder, and multiply it by the sine of half the degrees of longitude between them. Divide what results for each of them by the radius, find the arc of the quotient and double it: the result is the amount of each of the two sides of longitude; the longer of them is the first side and the shorter the second. Find their full chords, which are twice what results from each of them by the division, multiply one of the two chords by the other, and add to the product the third side multiplied by itself. Take the root of the sum, take half the root, find its arc and double the arc: the result is the distance between the two stars.[128]

If the latitudes of the two stars are on different sides, add the two latitudes together: the sum is the third side, and the fourth side is equal to it. Then subtract each of the two latitudes from 90 and find the sine of each, which is the sine of what each of them falls short of 90. Multiply it by the sine of half the degrees of longitude between them and divide what results for each of them by the radius; double the quotient: what results for each of them is the full chord of the first side and of the second side. Multiply one of them by the other, and add to the product the full chord of the third side multiplied by itself. Take the root of the sum and take half of it; find the arc of the result and double the arc: the result is the distance between the two stars.[129]

Ar. p. 61

It is known that when the two stars are together in one degree, and only one of them has a latitude, or both have latitudes, on the same side or on different sides, the distance between them is only the amount of latitude between them; and when neither has a latitude, the distance between them is the amount of the degrees of longitude, whatever it is. This chapter is needed above all for working out the directions in nativities.[130]

[126] The codex has no figure with the points D and K; Nallino adds one to the Latin translation.

[127] In modern terms, with chords in a circle of radius 1: $\mathrm{crd}^2\, d = \mathrm{crd}\, \Delta\lambda \cdot \mathrm{crd}\, s + \mathrm{crd}^2\, \beta$, where $\Delta\lambda$ is the difference in longitude, β the latitude and s the second side, $\sin \tfrac{1}{2} s = \cos \beta \cdot \sin \tfrac{1}{2}\Delta\lambda$. The rule is exact: it amounts to $\cos d = \cos \beta \cdot \cos \Delta\lambda$.

[128] «The third side multiplied by itself» is its full chord multiplied by itself, as in the next paragraph.

[129] The rules of these two paragraphs are exact as well: they amount to $\cos d = \sin \beta_1 \cdot \sin \beta_2 + \cos \beta_1 \cdot \cos \beta_2 \cdot \cos \Delta\lambda$.

[130] The directions (*tasyīrāt*) are the astrological progressions of a nativity (Nallino's *profectiones*).

Chapter 27. On finding the length of the year and the motion of the sun in it

Ar. p. 61

Al-Battānī said: The ancients disagreed about the length of the year. Some of the ancient people of Egypt and Babylon said that it is 365 days, a quarter of a day and 1/120 of a day. Ptolemy says that they reckoned it from the sun's leaving one of the fixed stars until it returns to it, and finds fault with them for this and says that it is most absurd. For if this view were allowed, nothing at all would prevent us from saying that the year is the time from the sun's leaving Saturn, or another of the wandering stars, until it returns to it, and this view is very plainly false. The year is only the time from the sun's leaving an unmoving point of the sphere until it returns to it, either from one of the two equinoctial points to the same point, or from one of the two solstitial points to the same point; for no starting points on the ecliptic are more fitting than these points.[131]

Hipparchus worked with a year of 365 days and a quarter of a day only, although it had become clear to Hipparchus that it is less than that, as Ptolemy reports in collecting Hipparchus's views. For Hipparchus said that the year is in truth 365 days and less than a quarter of a day, having found that the summer solstice came before the time of the full quarter day in excess of 365 days. This made Hipparchus uncertain about the motion of the sun, to the point of imagining that it had another sphere, eccentric to the centres of the two spheres.[132]

Ar. p. 62

The ancients took this mostly from summer observations, made when the sun passes the summer solstitial point. These are not found to be as accurate as observations made when the sun passes one of the two equinoctial points, especially the autumnal equinoctial point, because the air is clearer and purer at that time than at the time of the spring equinox. For when the sun passes the solstitial point it moves slowly in declination, and when it passes the two equinoctial points its motion in declination is very fast. That is why Ptolemy relied only on the autumnal observations and based the reckoning on them. One of the observations of Hipparchus on which Ptolemy relied, and of whose truth there was no doubt, is the observation reported by Hipparchus, who found that the sun passed the autumnal equinoctial point in the year 178 after the death of Alexander, on the third of the five epagomenal days, at midnight at Alexandria, of the night whose morning was the fourth of the epagomenal days, and was sure of it.[133]

Ptolemy observed 285 Egyptian years later; this is the observation that Ptolemy's book says was verified and made exact with the greatest care. Ptolemy found that the sun passed the autumnal equinoctial point in the third year of the reign of Antoninus, which is the year 463 after the death of Alexander, on the ninth day of Athyr, one of the months of the Copts, about one hour after sunrise at Alexandria. Taking the time between the two observations, Ptolemy found it to be in truth 285 Egyptian years, 70 days and a quarter of a day and 1/20 of a day, in place of the 71 days and a quarter that should accumulate from the full quarters in these 285 years. The ratio of this one day less 1/20 of a day, by which the time of the observation came before the time of the quarter day in excess of 365 days, to the 285 years between the two observations is as the ratio of one day to 300 years. So the length of the year found from these two observations is 365 days and a quarter of a day less 1/300 of a day, which is one part and a fifth of a part out of 360 parts.

Ar. p. 63

Ptolemy also reports taking the ancient summer observations made before Hipparchus, namely the observation made in the time of Apseudes, king of Athens, in which the sun passed the summer solstitial point 108 Egyptian years before the death of Alexander, in the morning of the twenty-first of Pharmouthi, one of the months of the Copts, in that year; and observing the sun in person and finding that it passed the summer solstitial point in the year 463 after the

[131] 365 1/4 + 1/120 days is 365 days 6 hours 12 minutes, a year measured by the fixed stars (Nallino). Ptolemy discusses the length of the year in *Almagest* III 1.

[132] Hipparchus found 365 1/4 − 1/300 days, that is 365 days 5 hours 55 minutes 12 seconds (Nallino).

[133] Ptolemy does not say that Hipparchus made this observation at Alexandria; Hipparchus observed at Rhodes, which was taken to lie on the meridian of Alexandria (Nallino). The epagomenal days are the five days added after the twelve months of 30 days of the Egyptian year.

death of Alexander, on the eleventh of Mesori, one of the months of the Copts, about two hours after midnight of the night whose morning was the twelfth of that month. Between these two observations there were about 571 Egyptian years, 140 days and a half and a third of a day, in place of the 142 days and a half and a quarter of a day that would accumulate from the quarters of the said years if the quarters were full in the years. So Ptolemy found that the summer solstice came before the time of the full quarter by one day, two thirds and a quarter of a day, and the ratio of this one day, two thirds and a quarter of a day to the said 571 years is as the ratio of two full days to 600 years. This agreed with what Ptolemy had worked with, that the observation comes before the time of the full quarter day by one day in every 300 years, although these summer observations are not as reliable as the autumnal ones, for the reason we have given. It is clear that the observation made before Hipparchus was earlier than the observation of Hipparchus by about the time between the observation of Hipparchus and that of Ptolemy, for it was 286 years before Hipparchus.[134]

Ar. p. 64

Then we observed at the city of al-Raqqa. One of our autumnal observations, on which we rely and whose accuracy we trust as far as the instrument showed us, is the observation made 743 years after the autumnal observation of Ptolemy mentioned above. When we measured, we found that the sun passed the autumnal equinoctial point in the year 1194 of the years of Dhū l-Qarnayn, which is the year 1206 after the death of Alexander, about four hours and a half and a quarter of an hour before sunrise on the nineteenth day of Aylūl, one of the months of the Rūm, which is the eighth day of Pachon, one of the months of the Copts. Since the meridian circle of Alexandria comes before the meridian circle of al-Raqqa by about two thirds of an equal hour, there are between the two observations, I mean our observation and the autumnal observation of Ptolemy, 743 Egyptian years, 178 days and a half and a quarter, less about two fifths of an hour, in place of the 185 days and a half and a quarter of a day that should accumulate from the quarters in these years if the quarters were full between the two observations. When we divide these 7 days and two fifths of an hour, by which the time of the observation came before the time of the quarter day in excess of 365 days, by the 743 years between the two observations, the share of one year comes to 3 parts 24 minutes of the 360 parts that make up the revolution of a day and its night. When we subtract this from the time of the quarter day, which is 90 parts, there remains as the excess over the full 365 days 86 parts 36 minutes; so the true length of the year is 365 days, 14 minutes and 26 seconds [of a day], approximately.[135,136]

When we divide the 360 parts of the circle of the sphere by the length of the year that has been found, the mean motion of the sun in a day and its night comes to 0;59,8,20,46,56,14; in the 30 days that make the Egyptian month, 29;34,10,23,28,6,47; and in the 365 days that make the Egyptian year, 359 parts 45 minutes 46 seconds 25 thirds 32 fourths 2 fifths 31 sixths, approximately. We have compounded these motions and entered them in the tables for the collected years and the single years, the months, the days and the hours, in the era of the Arabs and the era of the Rūm, so that the position of the sun by its mean motion, which is called the mean of the sun, can easily be found at any time we want, in whichever of the two eras we like. It is clear that the length of the year that we obtained by observation is less than the length that Ptolemy gives by 2 parts and a fifth of a part, and so the motion of the sun that we found exceeds the motion that Ptolemy gives by 0;0,0,3,33,43,43 in a day, and in the Egyptian year by 0;0,21,40,10,53,56, approximately,

[134] The observation in the time of Apseudes, archon of Athens, is the summer solstice observed by Meton and Euctemon, 27 June 432 BC (Nallino). For 108 years the codex has 168.

[135] The years of Dhū l-Qarnayn are those of the Seleucid era, which al-Battānī begins on 1 September; the observation fell before sunrise on 19 September 882 (Nallino). Two thirds of an hour is 10° of longitude; al-Battānī's own table of cities gives al-Raqqa 73° 15′ and Alexandria 60° 30′, a difference of 12° 45′ (Nallino).

[136] The minutes and seconds of the year are sixtieths of a day: 365;14,26 days is 365 days 5 hours 46 minutes 24 seconds. Hipparchus' and Ptolemy's year is 365;14,48 days, 2;12 parts of a day of 360 parts longer.

if God wills.[137,138]

Chapter 28. On finding the anomaly of the motion of the sun, and what appears with it of the position of its farthest distance from the centre of the earth[139]

Ar. p. 64
Ar. p. 65

Al-Battānī said: Having finished with the length of the year and the mean motion of the sun, we try to explain the anomaly that appears in the course of the sun, and its greatest amount, and what appears with it of the position of the point of its farthest distance from the centre of the earth on the ecliptic. In this we follow the method that Ptolemy's book uses, from the sun's passage through the quarters of the ecliptic, by measurements that we made in successive years, renewing the observations as carefully as we could. We established that the sun passes from the autumnal equinoctial point to the spring equinoctial point in 178 days and about 14½ hours, and that it passes from the spring equinoctial point to the autumnal equinoctial point in a longer time: what we found by observation, as far as our diligence reached, is that its true course, which is seen by measurement, takes 186 days and about 14¾ equal hours. It became clear from what we have said that the point of its farthest distance is in this half.[140]

Then we observed and found that the sun passes from the beginning of Aries to the beginning of Cancer, that is, from the spring equinoctial point to the summer solstitial point, in 93 days and about 14 equal hours, a little less than that. It is also clear that its passage from the spring equinoctial point to the summer solstitial point takes a longer time than its passage from the summer solstitial point to the autumnal equinoctial point. So we knew that the point of the farthest distance, and the centre of the eccentric sphere on which the point of the farthest distance lies, fall, on the ecliptic, in this quarter, which takes longer than the remaining quarter. We found the mean motion of the sun in the 186 days 14¾ hours to be 183 parts 56 minutes 12 seconds, and in the 93 days 14 hours 92 parts 14 minutes 10 seconds, approximately.[141]

Since this is so, we draw a circle for the ecliptic, ABGD, about the centre H, with the diameters AG and BD at right angles. We take the point A as the spring equinoctial point; then the sign B is the summer solstitial point, the sign G the autumnal equinoctial point, and the point D the winter solstitial point. In the quarter of the circle on which AB lies, for the reason given above, we mark the sign Z and take it as the centre about which we draw the circle of the sun's eccentric sphere, inside the first circle. We write on it KLMN, on the diameters KM and LN, which intersect at the centre Z at right angles. We write the sign F where the lines BD and KM meet; the sign LA where the diameter AG cuts the circle KLMN on the side of [the point A]; and the sign Ḍ where the diameter BD cuts the circle KLMN on the side of [the point B]. We draw the perpendicular of the arc LA K from the point LA to the sign Y on the diameter KM, and also the perpendicular ḌḤ. We draw the line HZ, which passes through the two centres, and extend it to the ecliptic, which is the circle ABGD, and we write the sign Ṭ where it meets it, and the sign ʿ where it cuts the circle KLMN.[142]

Ar. p. 66

[137] Sexagesimal numbers with many places are written here in the usual notation: 0;59,8,20,46,56,14 is 0 degrees, 59 minutes, 8 seconds, 20 thirds, 46 fourths, 56 fifths and 14 sixths. Ptolemy's daily motion is 0;59,8,17,13,12,31 and the yearly motion 359;45,24,45,21,8,35; the two differences given here are exact. In the yearly difference the text has 50 fifths; the difference is 53, as Nallino's translation has it.

[138] The collected years are the periods of years used as arguments of the tables, the single years the years within a period. The era of the Arabs is that of the Hijra; the era of the Rūm is the Seleucid era of the Syrians.

[139] The heading prints «الثامن العشرون» without «و». The translation reads «مركوه» for «مركوه» (p. 68, line 2) and «التي» for «الني» (p. 70, line 20), misprints that the corrigenda do not list.

[140] Al-Battānī has not shown before why the farthest distance lies in the half that takes longer; Nallino, after Schiaparelli, suspects that something has fallen out. Ptolemy's method is that of *Almagest* III 4.

[141] Here and on p. 66 the text writes 183;56,2, but it gives 3;56,12 for the excess over 180 and 1;58,6 for its half; Nallino's translation has 183;56,12. With al-Battānī's daily motion the mean motion in 186 days 14¾ hours is 183;56,13. In 93 days 14 hours it is 92;14,26, as the tables give; Nallino keeps 92;14,10, which the computation below also uses, and takes the 16 seconds for the «little less» of the observed time.

[142] The words in brackets are supplied by Nallino. LA is the letter lām-alif, used here as a sign of the figure.


It is established that the arc AB is 90 parts, and that the arc KL of the eccentric circle is also 90 parts. The point LA of the eccentric circle is its point of the beginning of Aries, and the point Ḍ the place of the beginning of Cancer. So the arc LA K L Ḍ M S of the eccentric is the amount of the eccentric circle that the sun passes over by its mean motion between the beginning of Aries and the beginning of Libra, which, as was said before, is 183 parts 56 minutes 12 seconds. The arc K L Ḍ M is half the eccentric circle, 180 parts; so each of the two arcs KL and SM is half of the 3 parts 56 minutes 12 seconds by which the sun's mean motion exceeded 180, that is, 1 part 58 minutes 6 seconds: the arc LA K is this amount, and the arc MS is equal to it. It is known too that the arc LA K L Ḍ is what the sun passes over on the eccentric by its mean motion from the beginning of Aries to the beginning of Cancer, so that the arc LA L Ḍ of the eccentric circle is of the 92 parts 14 minutes 10 seconds; and since the arc LA K L of it is known from what was said before, 91 parts 58 minutes 6 seconds, the arc LḌ is 16 minutes 4 seconds. Clearly the perpendicular LA Y is half the chord of twice the arc LA K, and the perpendicular ḌḤ half the chord of twice the arc LḌ; so the perpendicular LA Y is about 2 parts 3 minutes 39 seconds and the perpendicular ḌḤ about 16 minutes 45 seconds, the sines of the arcs LA K and LḌ. Since the line KM is parallel to the line AG, the line HF is equal to the line LA Y; and since the line LN is parallel to the line BD, the line ZF is equal to the line ḌḤ. So the side HZ of the right-angled triangle HFZ is known. The line HF multiplied by itself is about 4 parts 14 minutes 48 seconds, and the line ZF multiplied by itself 4 minutes 41 seconds; and the line HZ, which subtends the right angle, multiplied by itself is equal to HF and ZF, each multiplied by itself, added together. So HZ multiplied by itself is 4 parts 19 minutes 29 seconds, and its root is 2 parts 4¾ minutes: this is the line HZ between the two centres. In the measure in which a quarter of the circle about the right-angled triangle HFZ is 90 parts and its radius 60 parts, the arc HZ is about 1 part 59 minutes; this is the whole anomaly of the motion of the sun that appeared from these observations.[143]

Ar. p. 67

Next we seek the amount of the arc BṬ of the ecliptic; when it is known, the remaining arc ṬA is known in amount. For the point ʿ is the point of the farthest distance of the sun's eccentric sphere: when we drew the line HZ through the two centres and extended it to the ecliptic, it cut the circle KLMN at the point ʿ and the ecliptic at the point Ṭ. So we wish to know the ratio of the line HZ to the line HṬ, which is the radius, and the amount of the arc BṬ of the ecliptic. It has been shown that the line HZ is 2 parts 4¾ minutes in the measure in which the radius is 60 parts; and in the measure in which the radius is 60 parts the line HṬ is that too, since it is equal to the line HB. So the line HṬ measures HZ about 28 5/6 times. Further, as was shown first, if the line HZ is made 60 parts, the line FZ is in that measure about 8 parts 4 minutes; for this is what results when it is multiplied 28 5/6 times. Or, if you wish, multiply the line FZ by the line HṬ, the radius of the sphere: by the order of the multiplication the product is 16 degrees 45 minutes. Divide this by the line HZ, which has been shown to be 2 parts 4¾ minutes; the result is 8 parts 4 minutes, which is the sine of the amount of the angle BHṬ. So the arc BṬ is about 7 parts 43 minutes. Clearly the point of the farthest distance of the eccentric sphere, which is the point ʿ, falls 7 parts 43 minutes from the summer solstitial point towards the preceding side of the ecliptic, that is, 82 parts 17 minutes from the beginning of Aries. This is what we wished to show.[144]

[143] «The two arcs KL and SM»: the arc meant is LA K, as the next words say and Nallino's translation has it. The greatest equation of the sun is 1;59,10 in al-Battānī's tables, and Ibn Yūnus gives the same value for al-Battānī (Nallino).

[144] The farthest distance (apogee) of the sun is thus at Gemini 22° 17′. Ptolemy (*Almagest* III 4) put it at Gemini 5° 30′.



The observation on which we based this measurement was in the year 1194 of the years of Dhū l-Qarnayn, when we observed the course of the sun from the beginning of Aries to the beginning of Cancer and to the beginning of Libra.[145]

Ar. p. 68

What remains for us is to distribute this anomaly over the degrees of the signs, to find its share degree by degree and to enter it in the tables, so that the equation of the motion of the sun is easily found when it is needed. Ptolemy has shown and made clear that the irregular motions are seen and supposed in two ways. One is to imagine that the star has a sphere whose centre is the centre of the ecliptic, and on this sphere another sphere attached to it, whose centre runs on the circle of the first sphere and turns on it. This second sphere is a small sphere that does not surround the earth, and the large sphere is the one that carries the centre of the small sphere in the order of the signs, by the amount of the motion in longitude that is known for the star in the order of the signs, in either of the two ways. The star itself moves on the epicycle, which is the small sphere, either towards the preceding side or towards the following side; or this small sphere carries the star to either side, whichever it is. This motion is the motion of the proper anomaly of the star. The second of the two ways is to imagine that the star has a sphere whose centre is the centre of the ecliptic, and another sphere of the same size, whose centre is not the centre of the first sphere but outside it, and whose circle cuts the circle of the first sphere in two places; the star is on this eccentric sphere, the sphere carrying the star or the star moving on it. Whichever of the two ways you imagine, it comes to the same for this anomaly and what appears from it. We begin with the first way and give an example of it.[146]

Ar. p. 69

We draw a figure for the circle of the signs, ABGD, about the centre H, and we take the centre of the epicycle to be at first at the point A. We draw about it a circle for the epicycle, ṬZ, and draw the diameter AG and extend it to the point Ṭ, which is the point of the farthest distance of the epicycle. We take the position of the sun on the epicycle to be the point Z, draw from it a perpendicular to the line AṬ, write M at its foot, and draw also the line AZ, which is equal to the line AṬ, since each of them is the radius of the circle of the epicycle. It has been made clear earlier in this chapter that the radius of the epicycle is the line HZ found in the first figure, which is 2 parts 4¾ minutes. Since what we have described is clear, consider the motion of the sun on the epicycle towards the opposite of the order of the signs, that is, towards the preceding side, or the epicycle carrying the sun to this side, every day by as much as the mean motion of the sun in a day, in the measure in which the circle of the epicycle is 360 parts. The mean motion of the sun

[145] That year began on 1 September 882 (Nallino).


[146] *Almagest* III 3. The «sphere» on which the epicycle is carried is the circle of the deferent.

that appears by measurement is the motion of the centre of the epicycle towards the following side, which is the motion we have posited, also in the measure in which the circle ABGD is 360 parts. Now we take the arc ṬZ, between the sun and the point of the farthest distance of the epicycle, to be 30 parts in the measure in which the epicycle is 360, draw the line HZ in this figure, and seek the arc of the line ZM, which is the anomaly of the motion of the sun there. It has been shown that the line HA is the radius of the parecliptic sphere, 60 parts by the measure on which we have based the computation, in which the diameter AG is 120; so the line HṬ, from the centre of the parecliptic sphere to the point of the farthest distance of the epicycle, from which the motion on the epicycle begins, is 62 parts 4 minutes 45 seconds. Since the triangle ZMA is right-angled, AZ multiplied by itself is equal to AM and ZM, each multiplied by itself, added together, and the angle MAZ is known; so the line ZM is known, and when ZM is known, the remaining side AM of the triangle is known, which is the sine of what the angle ZAṬ and the arc ZṬ fall short of a quarter of their circle. So the line HM is known in amount; and the triangle ZMH is right-angled, and its line HZ, which subtends the right angle, is known for this reason, so that the line ZM is known in amount in its measure, and the arc on it is the arc of the anomaly. If the arc ZṬ is 30 parts, as we took it, its sine is also 30 parts in the measure in which the line AZ, the radius, is 60 parts; but in the measure in which the line AZ is 2 parts 4¾ minutes, the line ZM is 1 part 2 minutes 22½ seconds, the remaining line AM 1 part 48 minutes 2 seconds, and the line HM 61 parts 48 minutes 2 seconds. Clearly then [the line HZ] is about 61 degrees 48 minutes 35 seconds. In the measure in which the line HZ is only 60 parts, the line ZM is 1 part 33 seconds, and the arc on it about 57 minutes 49 seconds; this is the amount of the arc ṬZ, which is the anomaly of the motion of the sun. So the arc ʿA of the ecliptic is 29 degrees 2 minutes 11 seconds, whereas it was 30 parts; for the centre of the epicycle has moved from the point ʿ to the point A as the sun has moved on the epicycle from the point Ṭ to the point Z.[147]

Ar. p. 70

Further, we take the centre of the epicycle at the point B and draw about it a circle for the epicycle, ḤYQ. We take the position of the sun on it to be the point Ḥ, and the arc QḤ that the sun has passed over from the point Q, the farthest distance, to be 150 parts; so the arc YḤ that remains, from the position of the sun to the point of the nearest distance, is also 30 parts. We draw the line HḤ and the perpendicular ḤK. Clearly again each of the triangles BKḤ and ḤKH is right-angled, and each of the two sides BḤ and BH is known: BḤ is the radius of the epicycle and BH the radius of the ecliptic. The angle ḤY and the arc ḤY are given, so the perpendicular ḤK is known as well. If the arc ḤY is 30 parts, as we took it, its sine is also 30 parts, and the arc on KB, which completes the quarter, is 60, whose sine is 51 parts 57 minutes 41 seconds. In the measure in which the line BḤ is 2 parts 4¾ minutes, the perpendicular KḤ is 1 part 2 minutes 22½ seconds, and the line BK that remains is, in that measure, 1 part 48 minutes 2 seconds; so the line HK is about 58 degrees 11 minutes 58 seconds.

[147] The parecliptic sphere (*al-falak al-mumaththal bi-falak al-burūj*, «the sphere made like the ecliptic») is the sphere concentric with the ecliptic, in the plane of which the deferent lies (Nallino). «The arc of the line ZM» is the arc of the circle about the right-angled triangle of which ZM is the sine. The words in brackets are supplied by Nallino.



148

The line HḤ therefore comes to about 58 parts 12 minutes 34 seconds. But in the measure in which the line HḤ is 60 parts, the perpendicular KḤ is 1 part 4 minutes 17 seconds, and the arc on it 1 part 1 minute 24 seconds, in the measure in which the circle about the right-angled triangle BKḤ is 360; this is the arc of the anomaly, which is the arc ḤY. So the arc NB of the ecliptic is 31 parts 1 minute 24 seconds. This is what we wished to show.[149]

Ar. p. 71

Al-Battānī said: We show it also in the second way, which is seen on the eccentric sphere. We draw a circle for the ecliptic, ABG, on the diameter AG about the centre H, and a circle for the eccentric sphere, ZMḤ, about its centre, the point Ṭ, so that the diameter AG passes through the two centres. The point Z is then the farthest distance from the parecliptic sphere, and the point Ḥ the nearest distance from it. We take the position of the sun on the eccentric sphere to be at first the point M, the arc ZM that the sun has moved on the eccentric being 30 parts; so the angle ZṬM is also 30 parts. It has been shown that the line HṬ between the two centres is 2 parts 4¾ minutes. Since this is as we have drawn, we draw the line ṬM, which is the radius of the eccentric sphere, and the line HM; we extend the line ṬM in a straight line to the point L, and draw from the point L a perpendicular to ML, the perpendicular LH. The triangle ṬLH is right-angled, and its angle LṬH is equal to the given angle ZṬM. The arc on HL of the circle about the triangle ṬLH, the circle being 360, is 30 parts, and its sine also 30 parts in the measure in which the line ṬH between the two centres is 60 parts; and the line LṬ that completes the quarter remains 51 degrees 57 minutes 41 seconds, since the arc LṬ completes the quarter, that is, is 60 parts. But in the measure in which the line ṬH between the two centres is 2 parts 4¾ minutes, the line HL is 1 part 2 minutes 22½ seconds, and the line LṬ that completes the quarter 1 part 48 minutes 2 seconds; so the whole line LM is 61 parts 48 minutes 2 seconds. The triangle MLH is right-angled, so its line HM, which subtends the right angle, is known: it is 61;48,35. But in the measure in which the line HM is 60 parts, HL is 1 part 33 seconds, and the arc on it 0;57,49, the circle about the triangle ṬLH being 360. So the arc AB of the ecliptic remains about 29;2,11.[150]

Ar. p. 72


Further, we put the sun at the point D of the sun's eccentric sphere and take the arc ZD to be 150; so the arc DḤ that remains, from the position of the sun to the nearest distance, is also 30 parts. We draw the two lines HK and ṬD, each of which is the radius of its sphere, and draw also

[148] In the figure the sun on the first epicycle is printed «ن», N; the text calls it Z (ز). The dashed line Nʿ is the diameter of the ecliptic parallel to the line of the farthest and the nearest distance; F is not named in the text.

[149] For the arc NB the codex has FB; the reading NB is Nallino's.

[150] The translation reads «33 seconds» with the codex. Nallino prints «33 minutes». The codex is right: HL is 1;2,22½ × 60 / 61;48,35 = 1;0,33 parts, the value found for the same line ZM in the first way, and only this gives the arc 0;57,49 that follows.

the perpendicular HS. Since the triangle ṬSH is right-angled, and its side HṬ between the two centres is known, and the side HS and the angle DṬḤ are known, the side ṬS and the remaining angle ṬHS are known; so the line DS that remains is known, and HD, which subtends the right angle of the right-angled triangle HSD, is known. Since the arc DḤ and the angle ḤṬD are known and given, 30 parts as has been shown, their sine is also 30 parts; likewise the arc HS of the circle about the right-angled triangle HSṬ is 30, if this circle is 360, and its sine, which is the perpendicular HS, is also 30 parts in the measure in which the line HṬ, the radius of this circle, is 60 parts. But in the measure in which the line ṬH is 2 parts 4¾ minutes, the perpendicular HS is 1 part 2 minutes 22½ seconds, and so the line SṬ that remains of the sides of the triangle is 1 part 48 minutes 2 seconds. The line ṬD, the radius of the eccentric sphere, is 60; when SṬ is taken from it, the line SD that remains is 58 parts 11 minutes 58 seconds, and the line HD, which subtends the right angle of the triangle HSD, is about 58 parts 12 minutes 34 seconds. In the measure in which the line HD is 60 parts, the perpendicular HS is 1 part 4 minutes 17 seconds, and the arc on it 1 part 1 minute 24 seconds; this is the amount of the anomaly. So the arc KG of the ecliptic is about 31 parts 1 minute 24 seconds. This is enough about this anomaly; it is what we wished to show.[151]



[152]

Ar. p. 73

Al-Battānī said: In this way we have computed it degree by degree and entered it in the tables, counted from the point of the farthest distance. In this way also the single equation of the moon is computed, and the mean equation of the planets, which is the radius of the epicycle of each of them, when its sine is taken and it is distributed in this way. Whenever you wish to compute this, look at the degrees that the star, or the sun, or the moon, has passed over on the epicycle from the point of the farthest distance, which is called the anomaly of the sun, the moon and the other stars. If this anomaly is less than 180, work with it; if it is more than 180, subtract it from 360 and work with the remainder. The procedure is to take the degrees that you obtain in either way. If they are less than 90, take their sine and the sine of what remains of them to 90, and multiply each of the two sines by the radius of the epicycle of the star, which is the sine of the whole equation. Divide each product by the radius. Add what results for the sine of the complement of the degrees to the 60 that are the radius, multiply the sum by itself, add to it what results for the sine of the degrees multiplied by itself, take the root of the sum and keep it. Then return to what resulted for those degrees, multiply it by the radius, and divide it by the root that you kept. If the degrees with which you work are more than 90, take 90 from them, take the sine of the remainder and the sine of what remains of it to 90, multiply each of the two sines by [the radius of] the epicycle, and divide each product by the radius. Subtract what results for the degrees from 60, multiply the remainder by itself, add to it what results for the complement

[151] The text has «1 part 4 minutes 24 seconds» for the arc of the anomaly; the arc whose sine is 1;4,17 is 1;1,24, as in the first way, and the 31;1,24 that follows requires it (so Nallino's translation).

[152] In the figure the point at the right end of the line of the centres is printed «ب», B, a second time; the text calls it G (ج).

of the degrees multiplied by itself, take the root of the sum and keep it. Then return again to what resulted for the complement of the degrees, multiply it by the radius and divide by the root that you kept. Find the arc of the quotient. The arc you obtain, in whichever of the two ways, I mean from the first way, which results from the division of the first quantity, or from the division of this second quantity, is the share of those degrees of the anomaly with which you worked, for whichever star you intended, in the anomaly of its motion: it is the equation of the star. The radius of the epicycle of the sun is 2;4,45, the radius of the epicycle of the moon 5;15, the radius of the epicycle of Saturn 6;29,50, the radius of the epicycle of Jupiter 11;30,0, the radius of the epicycle of Mars 39;27,22, the radius of the epicycle of Venus 43;9,0, and the radius of the epicycle of Mercury 22;30,30. This is what has been shown by the observations, and the computation agrees with it; it is the sine of the mean equation of all the stars, if God wills.[153,154]

Chapter 29. On finding the inequality of the days with their nights, and on converting the one kind into the other

Ar. p. 73
Ar. p. 74

Al-Battānī said: Many people, and the common folk, think that the days with their nights are equal in length, I mean that each day with its night is 24 hours for them; but in truth it is not so. One mean day with its night is the rising of all the 360 times of the equator from the horizon circle or the meridian circle, together with the further times of the equator that rise with the 59 minutes that the sun moves by its mean motion in a day and night. One irregular day with its night is the rising of all the 360 times of the equator together with what further rises with the irregular course of the sun in a day and night, which is necessarily either more or less than 59 minutes. A beginning taken from the horizon circle changes and differs in every place with the difference of the ascensions of the signs there, while the beginning from noon is fixed in one state, without change or difference, because the signs pass through the meridian circle alike in every locality. Therefore the beginning of the days in the reckoning of the stars and the computation of their positions is not taken from sunrise or sunset, but from noon or midnight. Further, all the motions of the stars set down in the tables are set down for mean days of equal length. If what accumulates of the difference between the irregular days with their nights and the mean days with their nights is neglected, in the course of the sun and of the other stars it does not amount to anything from which a perceptible error appears; but in the moon it is very evident, because of its speed.

For the greatest amount that accumulates between the irregular days and the mean days is about half an hour, and in this time the motion of the moon is at times 18 minutes; between the days that exceed the mean days and the days that fall short of them it is twice that. This anomaly is composed of two parts: one is the anomaly of the motion of the sun, which is the equation; the other is the anomaly of the passage of the signs through the middle of the sky, since they do not all rise there with the same amount. The greatest amount that accumulates from the anomaly of the motion of the sun is about 3 parts and a quarter and a tenth, and the greatest amount that then accumulates from the passage of the signs through the middle of the sky about 4 parts and a quarter and a fifth; so what accumulates from the two together is 7 parts 48 minutes, which is about half an hour and a fifth of a tenth of an equal hour. The place of the shortfall is from about two thirds of Aquarius to about the beginning of Scorpio, and the place of the excess from about

[153] «Anomaly» renders al-Battānī's *ḥāṣṣa*, the portion of motion that falls to the star on its epicycle; most other astronomers call it *al-khāṣṣa*, «the proper [motion]» (Nallino's glossary). In modern terms, with r the radius of the epicycle and a the anomaly, the rule is $\sin q = r \sin a / \sqrt{((60 + r \cos a)^2 + (r \sin a)^2)}$, the radius being 60; it is exact, and its second form, for $a > 90°$, is the same rule written with $a - 90°$. The single equation of the moon is its first anomaly; the mean equation of a planet is the equation produced by its epicycle at its mean distance.

[154] Nallino corrects the codex in four of the radii: the sun (codex 2;5,45), the moon (6;15), Mars (19;25,22) and Mercury (29;30,30). For Mars the printed text has 39;25,22; the translation follows Nallino's emendanda, printed in Part II, and the Latin translation, which read 39;27,22. Ptolemy's values, in the same parts, are: sun 2;30 (the eccentricity), moon 5;15, Saturn 6;30, Jupiter 11;30, Mars 39;30, Venus 43;10, Mercury 22;30.

the beginning of Scorpio to about two thirds of Aquarius.[155]

Ar. p. 75

In this book we have set out the mean motions in the tables on the basis that the assumed position of the sun is at 18 degrees 19 minutes [of Aquarius] by its mean motion, and at 20 parts of it by its true motion, in which it is seen; and with this day and its night you compare the other days of the year in this book.

Al-Battānī said: If you wish to convert irregular days into the mean days with which the mean motions are taken from the tables, take [the arc] between the first, assumed mean position of the sun and the second position to which it moves, also by its mean motion, and keep the number of degrees. Then take also [the arc] between its first true position, in which it was, and the second position to which it moves by its true motion, in times of the ascensions of the signs in the right sphere. If the number of these times is greater than the degrees of the mean motion that you kept, find what part of an equal hour the difference between them is, and add it to the given irregular days; if the number of times is smaller, subtract it from them. The days that you obtain after the addition or the subtraction are those converted from the irregular days into the mean days, in whichever of the two reckonings is used for the beginning of the days, I mean from noon or from midnight. If you wish to convert from the mean days obtained from the tables into the irregular days that are found, do the reverse: add the difference to the mean days when the number of times is smaller, and subtract it from them when the number of times is greater. The mean days after the addition or the subtraction are those converted from the mean days into the irregular days that are found.

On the basis that we have laid down in this book for the assumed position of the sun, the number of times is always the smaller, until a long period of time has passed in which the position of the farthest distance of the sun, as we found it on the ecliptic, has changed much, and so what arises from the anomaly of the motion of the sun has changed. Since this is as we have described, we have added 18 minutes to the mean position of the moon at the root of the computation. We have taken the share of each degree of the signs in the amount of the inequality of the days with their nights and entered it in the tables of the ascensions of the right sphere, in the column that follows the ascensions in each sign. When we take what stands opposite the true degree of the sun in that column, find its amount in equal hours and subtract it from the irregular days, what remains is the mean days with which the motions are found from the tables; and when it is added to the mean days, the result is the irregular days that are found by measurement.[156]

Chapter 30. On the description of the spheres of the moon, the anomaly of its motions, the increase and decrease of its light, the causes of the two eclipses, and the distances of the two luminaries from the centre of the earth, their diameters and the sizes of their bodies when they are compared with the earth[157]

Ar. p. 76

Al-Battānī said: When the motions of the moon were investigated, two anomalies were found in it. One of them is single by itself: it appears alone, only at the times of the conjunctions with the sun and the oppositions to it that take place by the mean course of the sun and the moon, and it depends on the position of the moon on its epicycle. The second anomaly appears through the moon's distances from the sun; it is compounded with the first anomaly, so that the two act together. This is grasped by demonstration with geometrical lines, by imagining that the moon has four spheres. The first is made like the ecliptic: it lies level beneath it, moves with its motion without deviating from it, and has its centre at the centre of the ecliptic. The second sphere is

[155] This is the inequality that is now called the equation of time. Al-Battānī counts it from its least value: 7;48 times of the equator are 31 minutes of an hour, close to the range of about 31 minutes over which the equation of time varies.

[156] The root of the computation is the epoch of the tables.

[157] The last words, «with the earth», are Nallino's conjecture: only the tops of the letters can be read in the codex.


inclined to it towards the north and the south; it is as large as this parecliptic sphere, and the two have one centre. Its greatest inclination to either side is about 5 parts, which is the amount of the moon's distance from the belt of the signs in latitude. The motion of this inclined sphere, against the order of the signs, is about 3 minutes a day. This is the motion of the two nodes. One of them is called the head: from it the moon passes in latitude towards the north. The other is called the tail: from it the moon passes towards the south. These two nodes are the places where the inclined sphere and the parecliptic sphere intersect.

Ar. p. 77

Inside this inclined sphere is a third sphere, whose centre lies outside the centre of the other two. It hangs from the inclined sphere and touches it at a point that is its highest place; that point is called the farthest distance from the earth. It moves within the inclined sphere against the order of the signs, about 11 parts 12 minutes a day. There is a fourth sphere, called the moon's own epicycle. Its centre is on the circle of the eccentric sphere, and this centre moves on the circle of the eccentric sphere in the order of the signs about 24 parts 23 minutes [a day]. It begins its motion from the point of the farthest distance of the eccentric sphere, which is taken together with the mean position of the sun. Therefore the centre of the epicycle falls on the point of the farthest distance twice in the lunar month, once at the mean conjunction and again at the opposition. The moon moves on the circle of the epicycle about 13 degrees 4 minutes a day, against the order of the signs on the epicycle, beginning from the point of the farthest distance that is seen from the centre of the eccentric sphere. Since the centre of the epicycle falls on the circle of the inclined sphere at these two times, as we have said, nothing prevents us from taking it, in this way, to move on the circle of the inclined sphere about 13 degrees 14 minutes a day; this is its motion in latitude. The node, at the intersection of the two spheres, carries it back against the order of the signs by the 3 minutes that we said are the motion of the inclined sphere, so that its motion in longitude, in the order of the signs, remains about 13 degrees 11 minutes a day. The motion of the moon on the epicycle is the first motion mentioned.[158]

It is clear from what we have described that nothing enters the motion of the moon from the eccentric sphere at these two times, since then the moon is not distant from the mean position of the sun or from the point opposite it. So nothing of the second anomaly is mixed with the single anomaly until the moon moves away from the sun; at those distances the second anomaly, which comes from the eccentric sphere, is compounded with it according to the moon's distances from the sun. This is the figure of the four spheres of the moon; the demonstration will be clear to you from the example of their drawing.

[158]The daily motions are Ptolemy's, rounded. The 24;23 is twice the daily excess of the moon's motion in longitude over the sun's, and the eccentric moves back by 24;23 − 13;14 + 0;3 = 11;12 (Nallino). The 13;4 is the daily motion in anomaly, 13;3,53,56,... in *Almagest* IV 3.



[159]

Al-Battānī said: I drew a circle for the parecliptic sphere, marked ABGD, with H at its centre, and a circle for the inclined sphere, also marked ABGD; let its centre also be the point H, as is the case on the globe, which turns on its two poles. We draw the diameter AS and mark on it the centre of the eccentric sphere at the point Z, between the centre of the two spheres and the sign A. About the centre Z we draw a circle for the eccentric sphere, marked AMF, with the radius AZ. We take the arc AM, as much as we wish, as the motion of the centre of the epicycle from the point A, which is the point of the farthest distance and the position of the sun, to the point M. We take the point M as the centre of the epicycle and draw about it a circle for the epicycle, marked ḤṬḌK. We draw the two lines HMṬ and ZMḤ. Then the point Ṭ of the epicycle is the position of the farthest distance that is seen from the centre, the point H, which is the centre of the earth and the centre of the ecliptic, and Ḥ is the position of the true farthest distance, which is seen from the centre Z, I mean from the centre of the eccentric sphere. So the arc ṬḤ is clearly the anomaly of the motion of the moon in its proper course on the epicycle; it is the anomaly set down in the third column of the tables of the equation of the moon. We take the motion of the moon on the epicycle to be from the point Ḥ to the point Ṭ, then to Ḍ, and make the position that it has reached on the epicycle the sign K. We draw the line HKN touching the epicycle, and draw the line MK, the radius of the epicycle as displaced by the distance of its centre from the point A of the eccentric sphere. Since the moon is on the line that touches the epicycle, the radius of the epicycle is the whole single anomaly together with what is compounded with it of the second anomaly, according to the distance of the moon from the sun, which is at the point A. It is clear in this figure that when the moon is in the first half of the epicycle, on which are ḤṬḌ, its true position on the ecliptic, which is seen from the centre H, is less than its mean position in longitude, which is the position of the centre of the epicycle; so the equation is subtracted from the mean position of the moon when the anomaly is less than 180 degrees. When it is in the second half, on which are ḌKḤ, its true position on the ecliptic is greater than its mean position; so when its anomaly is more than half the circle, the equation is added to the mean position of

[159] The dashed circle about Z, as large as the circle of the ecliptic, is not mentioned in the text; Schiaparelli found no use for it (Nallino's commentary). The point L and the lines ZL and LH belong to the computation on p. 80.

the moon, if God wills.[160,161]

Ar. p. 79

As for the single equation, which appears at the times of the conjunctions and the oppositions and is set down in this book of ours in the second column of the tables of the equation, we have shown how it is computed, in the way in which we worked in computing the equation of the sun and distributing it in the tables. The greatest amount that this single anomaly of the moon reaches is 5 parts 1 minute, and its sine, which is then the radius of the epicycle, is about 5¼ parts: this is the ratio of the 60 of the radius to the 5¼ parts. This is what Ptolemy stated and showed from the lunar eclipses, in which the true position of the moon must be opposite the true position of the sun, in which the sun is seen on the ecliptic. At those times [the arc] between the position of the moon by its mean course and the degree opposite the true degree of the sun is the single anomaly of the motion of the moon according to the position of the moon on the epicycle, and so the whole of this single anomaly becomes known. We too have observed many lunar eclipses, established their exact times and middles, and found the amount of this single anomaly to be as we have described.[162]

Ar. p. 80

As for the second anomaly, which is found from the distance of the moon from the sun, the greatest amount that they found reaches about 2⅔ parts. Compounded with the 5 parts 1 minute of the single anomaly, the two anomalies together come to about 7 parts 40 minutes. This happens when the centre of the epicycle is at the point F, at a distance of half the circle from the point A; the radius of the displaced epicycle is then about 8 parts, the sine of the 7⅔ parts. From what we have described it becomes clear that the line HZ between the two centres is 10 parts 19 minutes. The demonstration of this is as I shall describe. We again draw a circle for the epicycle, marked ṬḤ, about the point A, which is the farthest distance on the eccentric sphere, and draw the line HṬ touching the epicycle, and the line AṬ. Since the moon on the tangent line completes the whole single anomaly, which has been shown to be 5;1 in the measure in which the four right angles are 360, its sine is 5;15 in the measure in which the radius is 60 parts, the radius of the parecliptic, inclined, sphere in this figure. Again we take the centre of the epicycle at the sign F, which is the point of the nearest distance of the eccentric sphere, draw about it a circle for the epicycle, also marked ṬḤ, and draw the line HṬ touching the epicycle, and the line FṬ. Since the moon on the tangent line, I mean at the position Ṭ, completes the whole of the two anomalies, which is 7;40, its sine is about 8 in the measure in which the four right angles are 360 and the radius, the line HA, is 60. The line FṬ is equal to the line AṬ, and it was shown that the line AṬ is 5¼ parts in the measure in which the line HA is 60 parts. But since the centre of the epicycle has come to a place where the measure changes, because of its nearness to the point H, which is the centre of the earth and the true place of sight, [FṬ] appears in the measurement as about 8 parts, in the measure in which the line HA is 60. So in the measure in which the 8 parts are 60 parts, the 5¼ parts are 39 degrees 22 minutes, and that is the amount of the line HF, from the centre of the earth to the point of the nearest distance of the eccentric sphere. Likewise, by the inverse of this ratio, in the measure in which the 8 parts are 5¼ parts, the 60 parts are 39 parts 22 [minutes]. Since the amount of the line HF has become clear, 39 parts 22 minutes, when it is added to the line HA, which is 60, it comes to 99;22, which is the whole diameter of the eccentric

[160] In the printed figure the line from H through M ends at Ḥ, and Ṭ lies on the dashed line drawn through M from the point of the diameter that is as far from H as Z is, on the other side. The true farthest distance of the epicycle is seen from that point in Ptolemy's theory (*Almagest* V 5), and al-Battānī's own computation uses it on p. 82. The text, with the codex and Plato of Tivoli, draws HMṬ and ZMḤ instead and has the true farthest distance seen from the centre Z of the eccentric; Nallino's translation, following Schiaparelli, corrects the text to agree with the figure. The arc ṬḤ is the same in either reading.

[161] The «displaced» radius of the epicycle is its radius measured in parts of which the distance of its centre from the earth, HM, is 60; it grows as the centre moves from A towards F: 5;15 at A, 7;12 at the doubled distance of 120, about 8 at F, as is shown below.

[162] *Almagest* IV 6. The single equation is computed as the equation of the sun is in chapter 28.

sphere; and half of it, the radius of the eccentric sphere, is 49;41.[163,164]

Ar. p. 81

Since the radius of the epicycle according to its displacement from the sun is known, and the distance between the centres and the radius of the eccentric sphere are known, what remains to complete our knowledge of this is to explain how to compute the arc ṬḤ, which is set down in the third column, and to explain what is compounded of the single equation with the second between the two distances, in the way in which I have set it out in the tables and entered it in the fourth and fifth columns. In the fourth: if these 2 degrees 40 minutes, which are entered in the fifth, are taken as 60, how much is compounded of them, and what is its ratio to the 60. This is known as I shall describe. We extend the line MH to the sign L and join the point L to the point Z; then the ratios of the sides of the triangle MLZ are known, and its angles. We take the arc AM, as Ptolemy took it in this matter, as 120 parts; this is the doubled distance of the moon from the sun. Since we take the ratio of the sines to the radius, the angle LZH is 30 parts, and the angle ZHL, which completes the quarter, 60 parts, in the measure in which the circle that goes round the triangle ZHL is 360 parts. Also the sine of the angle LZH is 30 parts, and the sine of the angle ZHL about 51;58, in the measure in which the line HZ is 60; but in the measure in which the line HZ is 10;19, the line HL is about 5;10 and the line ZL 9;16. Again, when the line HKN in the figure touches the epicycle and the position of the moon on the epicycle is the point K, the first anomaly together with what is compounded with it of the second anomaly is greatest. Since the line MK is the radius of the epicycle and the line ZM the radius of the eccentric sphere, by which you know these amounts, the ratio of LM is known from the ratio of ZM and ZL, and so the whole line ML is 48;53. When the line HL, which has been shown to be 5;10, is taken from it, the line HM from the centre remains 43;43. The line MK, the radius of the epicycle, has been shown to be 5;15; but in the measure in which the line HM from the centre is 60, the line KM, the radius of the displaced epicycle, is about 7 parts 12 minutes, and the arc on it about 6 parts 54 minutes; that is the amount of the arc MK. When the 5 parts 1 minute, the amount of the whole single anomaly, are taken from it, what is compounded with it of the second anomaly remains, 1 part 53 minutes. If the 2⅔ degrees, approximately, are 60, this 1 degree 53 minutes is 42;38 of the 60; that is what is set down under 120 in the fourth column, and it results from the ratio of the minutes to the one part, which is the ratio of 0;42,38 to 60. When these 42 and 38 are extended and made 60, the 1 part 53 minutes become 2 parts 39 minutes, which is what is set down in the fifth under 120.[165,166,167]

We also find [the arc] between the true farthest distance and the mean distance, which is the arc ṬḤ, in the figure set out, by taking the doubled distance of the moon from the sun by their mean course as 90;30, as Ptolemy took it in the figure to which the demonstration led, as we have said, so that the motion of the moon on its epicycle from the point Ṭ is 333;12. We draw this circle as an example of it.[168]

[163] The greatest second anomaly is Ptolemy's (*Almagest* V 3), and so is the distance between the centres (V 4). The resulting extreme equations of the moon, 5;1 at the syzygies and 7;40 at the quadratures, compare with the modern 5;2 and 7;34 (Schiaparelli, in Nallino's commentary); the second anomaly is the inequality now called the evection.


[164] «Half» is supplied by Nallino. After «the point F» Plato of Tivoli has «which is the nearest distance of the eccentric sphere», words that Nallino takes to have fallen out of the codex. At the end of the paragraph Plato also has «so the distance between the two centres is 10;19 in the measure in which AH is 60 parts», that is, 60 − 49;41.

[165] The text prints LHZ for the angle of 30 parts, in this sentence and the next (the codex has AHM); the angle of 30 parts is the angle at Z, LZH, as in Nallino's translation. Ptolemy (*Almagest* V 7) makes the angle AHM, not the arc AM, 120 degrees, which is what gives the angle ZHL of 60 (Schiaparelli).

[166] On the base HZ = 10;19 the sine of 60 parts is 8;56 (10;19 × 51;58 / 60), and the line ML = 48;53 that follows agrees with it, not with the text's 9;16, which would give 48;49. Plato of Tivoli has 18;56.

[167] The 42;38 is reckoned with the greatest second anomaly 2;39, that is 7;40 − 5;1, rather than with the rounded 2⅔: 60 × 1;53 / 2;39 = 42;38, while 60 × 1;53 / 2;40 = 42;22,30. In al-Battānī's tables the 2;39 of the fifth column stands under 110, not 120 (Nallino). Schiaparelli, in Nallino's commentary, takes the last sentence for an interpolation by a reader who did not understand the computation.

[168] These are the values of Ptolemy's example in *Almagest* V 6.



Ar. p. 82

Al-Battānī said: This is the circle of the eccentric sphere, marked ABG, about the centre D, with the diameter AG, on which the centre of the ecliptic falls, at the sign H. The circle about the point B is the one called the epicycle, marked MḤṬ. We draw the line BM and the line HBḤ, extend the line BH to the point K, and join the point K to the point D. Then the angle KDH of the triangle is the half part by which [the doubled distance] exceeds 90, and the arc HK is half a part in the measure in which the circle that goes round the triangle DKH is 360 parts; its sine is 0;31,25 in the measure in which the line HD, the radius, is 60. The angle KHD remains 89;30, and so the arc KD is 89;30 and its sine about 60. But in the measure in which the line DH between the centres is 10;19, the line HK is about 5 minutes and the line KD about 10;19. Further, because of the difference of the centres that we have described, we make the line HZ equal to DH, the line HS equal to HK, and the line SZ equal to the line DK. The line DB, from the centre of the eccentric sphere to its circle, has been shown to be 49;41 in the measure in which the line MB, the radius of the epicycle, is 5;15. From what we have described, the whole line BK is 48;36. When HK, which has been shown to be 5 minutes, is taken from it, the line HB remains, in that measure, 48;31; and since the line HS is also 5 minutes, the line SB remains, in that measure, 48;26. From the ratio of SZ and SB you know the ratio of the line BZ, which is therefore about 49;31 in the measure in which the line SZ was about 10;19. When the line BZ is extended and made 60, the line SZ is in that measure about 12;32, and the arc on it about 12;1, in the measure in which one right angle is 90; that is the amount of the arc ṬḤ. So the true motion of the moon on the epicycle, which is seen from the centre of the sphere, counted from the point Ḥ, is 345 parts 13 minutes. Therefore, when the doubled distance is less than 180, the arc ṬḤ is added to the anomaly of the moon obtained from the table, and when it is more than 180, the arc ṬḤ is subtracted from that anomaly. For the centre of the epicycle is at first between the point A of the eccentric sphere and the point F, on the side of M; then it passes to its other half, between F and A, on the side of D. These 12 parts 1 minute are what is set down in the third column under 90½ parts.[169,170,171]

Ar. p. 83

Al-Battānī said: As for the motion of the moon in longitude, we find it as it stands in Ptolemy's book, after we add to it what we found in correcting the motion of the sun, and so we have entered it in the tables. Likewise its motion in anomaly is the motion set down in Ptolemy's book for the anomaly of the moon, with nothing added to it or taken from it. As for its motion in latitude, we found that it exceeds in Ptolemy's book by 27 minutes; so we distributed these minutes over the time between Ptolemy and us, subtracted them from the motion in latitude,

[169] Here Z is the point of the diameter that is as far from H as D is, on the other side; the true farthest distance Ṭ of the epicycle lies on the line from Z through B (Ptolemy, *Almagest* V 5).

[170] The line SZ is 10;19 × 60 / 49;31 = 12;30, as Plato of Tivoli has it, and its arc 12;1; the 12;32 of the text would give 12;3.

[171] The letters A, F, M and D of the last sentences are those of the first figure (Nallino).

and entered in the tables what remained. We have had no need to set down tables of the doubled distance between the sun and the moon, since we know the distance between the sun and the moon by their mean course at any time we wish; when we double it, that is what we use in place of what is obtained from the tables, without addition or subtraction. Likewise we found that the latitude of the moon reaches about 5 parts, which is set down in the seventh column of the tables of the equation, and we entered it as it was; except that its share exceeds, in our time and Ptolemy's, by a half and a quarter of a part, so we subtracted that from its proper course, and what remains is what you find there, if God Most High wills.[172,173]

As for the cause of the lunar eclipse, it is that the sun is greater than the earth and the earth greater than the moon. The rays of the sun go out along the sides of the earth until they end in the air on the other side in the shape of the head of a pine, and so the shadow of the earth is called the pine-shaped shadow; its end lies beyond the sphere of Mercury. When the passage of the moon is at one of the two nodes of its sphere at the times of its opposition to the sun, its centre comes to the centre [line] of the ecliptic: it falls on the belt of the signs, faces the sun across a diameter of the sphere, with no latitude by which it is inclined away from the sun, and is directly opposite it. Then the earth comes between the moon and the sun and screens it from it, so that the moon falls into the pine-shaped shadow of the earth that we have mentioned; its light is darkened, and it is eclipsed according to how far or near its path is to the belt of the signs, which is the middle of the shadow. If it has no latitude at all and is in the node itself, its passage at the middle of the eclipse is on the middle line of the shadow, and its eclipse is then the most complete of eclipses and the longest in duration. For this reason the moon never has its light complete: it receives all the light only when the sun falls on the half of its circle that faces it, and that happens only when it is on the diameter of the sun, with half the sphere between them, which it can reach only under the darkness, at the middle of the eclipse. If it is inclined from the path of the sun in latitude to the north or to the south, less than half the circle of the sphere lies between it and the sun, and its opposition to the sun is not along a straight diameter. So when it is opposite the sun while inclined from its path in latitude, its eclipse is according to the amount of its latitude, up to the greatest latitude at which its circle can touch the circle of the shadow.[174,175,176]

Ar. p. 84

It is clear from what we have said that none of the stars can be eclipsed at their opposition to the sun, since the shadow does not reach their centres; and Mercury does not move as far from the sun as opposition, to fall into the shadow then. But the moon may eclipse the other stars and hide them from sight when its visible path agrees [with theirs] in longitude and latitude, for then it falls on the line that goes out from the eye to the star in question. The stars also eclipse one another, when the lower of them passes under one of those above it and comes onto its course in longitude and latitude. If the sun were equal to the earth, the breadth of the shadow would be the same from its bottom to its top; it would have no end in the air, but would rise without end. The eclipse of the moon would then be of one and the same amount at the top of its epicycle and at the bottom, it would linger in the eclipse longer than it is found to linger, and all the stars would

[172] The correction of the motion of the sun is that of chapter 27; adding it to the moon as well keeps Ptolemy's mean distance of the moon from the sun. In 100 Roman years al-Battānī's mean motion of the moon in longitude exceeds whole revolutions by 307;57,46, Ptolemy's by 307;21,37; Hansen's tables of the nineteenth century give 307;53,40 (Schiaparelli, in Nallino's commentary).

[173] «Its share» (*ḥiṣṣa*) is the argument of latitude; Nallino reads it for the codex's *ḥāṣṣa*, «its anomaly». Schiaparelli explains the ¾ part as the correction of the motion in latitude accumulated over the roughly 1200 years from the epoch of the era of Dhū l-Qarnayn, at the rate of 27 minutes in the roughly 750 years between Ptolemy and al-Battānī (27′ × 1200 / 750 = 43′).

[174] The reading «head» (*jumjuma*) is uncertain (Nallino). *Ṣanawbarī*, «pine-shaped», is the Arabic word for conical.

[175] In this chapter (p. 92) the shadow reaches 254⅔ radii of the earth from the centre of the earth; in chapter 50 the distances of Mercury run from 64⅙ to 166 radii of the earth and those of Venus from 166 to 1070, so that the shadow passes the sphere of Mercury and enters that of Venus (Nallino).

[176] The translation follows Nallino's emendanda (Part II, p. XXX), «its centre becomes the centre of the ecliptic», for the printed «its centre comes to be in the ecliptic»; the codex has «it becomes the centre of the ecliptic».

be eclipsed at their opposition to the sun. If the sun were smaller than the earth, the top of the shadow would be broader than its bottom, and it would rise in the sky without end; the higher the breadth of the shadow rose, the more the moon and the stars would be eclipsed, lingering in the eclipse for days that differ according to their course compared with the course of the sun.[177]

As for the sun, the cause of its eclipse is the moon. When at the times of the conjunctions its centre happens to be seen on the belt of the signs, it comes between the eyes of those who look at the sun and the sun, since it falls on the line that goes out from the eye to the sun, being nearer to the earth than the sun is; just as a small thing can always be seen to hide a large thing when it is nearer to the eyes. The amounts of the eclipse are according to the latitude of the moon as it is seen, up to the limit at which its circle cannot hide anything of the circle of the sun. For this reason the eclipse of the sun has different amounts in places of different latitude, while the eclipse of the moon is seen of one amount in all places.

As for the distances of the sun and the moon, their diameters and the sizes of their bodies compared with the earth, to find them Ptolemy put forward two lunar eclipses as the basis of the measurement, and carried it out on the assumption that the moon hides the whole sun from sight when it is at its farthest distance from the earth at the times of the conjunctions and is seen on the belt of the signs, and gave the diameter of the sun no perceptible variation, relative to the moon, between its far and near distances from the earth, but made it the same as the moon's. Ptolemy mentioned no observations of solar eclipses in the book and did not use them, and we do not know what prevented Ptolemy. But in the amounts of the solar eclipses that we observed we did not see anything that requires the circle of the moon to cover the circle of the sun and hide it from sight in the ratio mentioned. On the contrary, we also found a clear and evident change in the diameter of the sun, relative to the moon, between its farthest and nearest distances, as geometrical measurement requires, although in itself it is small and imperceptible.[178,179]

Ar. p. 85

As our demonstration of what we have described we take two well-known solar eclipses that we observed in our time. In one of them the sun and the moon were in the region of their farthest distance; in the second the sun was in the region of its nearest distance and the moon near its mean distance. The middle of the first eclipse, as we found it by observation, was in the year 1202 of Dhū l-Qarnayn, which is the year 1214 from the death of Alexander, one seasonal hour after noon on the eighth day of Āb, in the city of al-Raqqa, and more than two thirds of the sun was eclipsed to the sight. By our computation the sun at the time of the conjunction was in Leo 20;54 by its mean course and in 19;14 of it by its true course. The moon by its mean course was in Leo 17;7, and in truth, necessarily, with the degree of the sun; so its proper course on the epicycle from the position of the true farthest distance was 333;13. Its mean motion in latitude was 174;43, and in truth 176;51. The visible conjunction, which is the middle of the eclipse, was about an eighth of an hour after the time of the true conjunction; so its motion in latitude at the middle of the eclipse was 176;55, its visible latitude 6 minutes to the south, and its true latitude about 16 minutes to the north. By Ptolemy's computation and on that ratio, the part of the sun eclipsed should have been more than a half and a quarter, and the middle of the eclipse should have been about an hour before the time at which it occurred by measurement.[180,181]

Ar. p. 86

[177] Mercury and Venus are never in opposition; Nallino suggests that «upper» has fallen out after «all the stars».

[178] *Almagest* V 14.

[179] The translation reads «منعه», «what prevented Ptolemy», with Plato of Tivoli and Nallino's translation, for the printed «صنعه», «what Ptolemy did» (p. 84, line 18). Bailly and Delambre, cited by Nallino, explain that Ptolemy did not rely on solar eclipses because Ptolemy's lunar theory put the distance of the moon, and with it its parallax and apparent diameter, far from the truth.

[180] 8 August 891 (Nallino). Nallino's translation has «apogee» for «nearest distance» in the description of the second eclipse; the Arabic is right: the sun, at Aquarius 8;35, was 46 degrees from its nearest distance at Sagittarius 22;17.

[181] The translation reads 333;13 for the printed 333;17 (p. 85, line 7), a misprint that the corrigenda do not list: Nallino's apparatus and translation have 13 minutes (the codex has 332;57), and Schiaparelli's recomputation of the eclipse from al-Battānī's tables, in Nallino's commentary, gives 333;12,57. It also confirms Nallino's 17;7 for the mean position of the moon (the codex has 14;7), and puts the true conjunction 1 hour after noon in true time, 47 minutes

The middle of the second eclipse, as we found it by observation in the city of Antioch in the year 1212 of the years of Dhū l-Qarnayn, which is 1224 from the death of Alexander, was about 3⅔ equal hours before noon on the 23rd day of Kānūn II, and the part of the sun eclipsed was a little more than half to the sight. The middle of the eclipse at al-Raqqa, as its time was taken for us, was 3 hours and less than half an equal hour before noon, and less than two thirds of the sun was eclipsed to the sight. By our computation the mean position of the sun at the time of the true conjunction was Aquarius 7;9, and in truth 8;35 of it. The moon by its mean course was in Aquarius 12;49, and in truth, necessarily, with the degree of the sun; so its course in anomaly from the point of the true distance on the epicycle was 126;37, its mean motion in latitude 173;25, and in truth 169;11. The middle of the eclipse to the sight was about a half and a third of an equal hour before the time of the conjunction; its visible latitude was about 10 minutes and its true latitude about a degree less a minute, but its motion in latitude at the middle of the eclipse was 168;45. By Ptolemy's computation and on those ratios the whole sun should have been eclipsed, and the middle of the eclipse should have been about two hours later than the time found. This is a defect of a kind that may not be tolerated in computation at all.[182,183,184]

We also mention two lunar eclipses of our time on which measurement can be based for what we intend in this kind [of inquiry]. The first of them was in the year 1194 of the years of Dhū l-Qarnayn, which is the year 1206 from the death of Alexander, on the 23rd day of Tammūz. We observed it, and the middle of the eclipse in the city of al-Raqqa was 8 equal hours and a little after noon of that day; a little more than a half and a third of the diameter of the moon was eclipsed. By our computation the sun was in Leo 5;21 by its mean course, and in truth in 4;2 of it; the mean position of the moon was Aquarius 8;45, and in truth, necessarily, opposite the degree of the sun. So its motion in anomaly from the point of the mean farthest distance on the epicycle was 113;0, and in truth 114;9; its mean motion in latitude was 190;49, and in truth 186;5, so that its latitude at the time of the opposition was about 32 minutes to the south. By Ptolemy's computation the part of the moon eclipsed should have been a half and a third and an eighth of its diameter, and the time of the middle of the eclipse should have preceded the time at which we found it by about a half and a quarter of an equal hour.[185,186,187]

Ar. p. 87

The second eclipse was in the year 1212 of the years of Dhū l-Qarnayn, which is the year 1224 from the death of Alexander. We observed it ourselves: the middle of the eclipse in the city of Antioch was about 15⅓ equal hours after noon of the second day of Āb, and at al-Raqqa about 15 hours and a third and a quarter of an hour after noon, which is the time of the opposition; a little less than the diameter of the moon was eclipsed. By our computation the sun was in Leo 14;10 by its mean course, and in truth in 14;36 of it; the mean position of the moon was in Aquarius 19;24, and in truth, necessarily, opposite the true degree of the sun. So its course in anomaly from the point of the mean farthest distance on the epicycle was 110;7, and in truth 111;5; its mean motion in latitude was 190;10, and in truth 185;21, so that its true latitude at the middle of the eclipse, which is the time of the opposition, was about 28 minutes. By Ptolemy's computation

after noon in mean time.

[182] 23 January 901, about 8:20 in the morning, true time (Nallino).

[183] Al-Battānī thus puts somewhat more than 10 minutes of time, 2½ degrees of longitude, between Antioch and al-Raqqa, and for the second lunar eclipse below about a quarter of an hour (Nallino); the difference of their longitudes is 2° 55′, 11⅔ minutes of time.

[184] Schiaparelli's recomputation from al-Battānī's tables (Nallino's commentary) confirms the numbers as Nallino prints them; the codex has 126;32, 199;11 and 198;45 for 126;37, 169;11 and 168;45.

[185] 23 July 883 (Nallino).

[186] 113;0: for the minutes the text prints a sign that Nallino's translation and Schiaparelli read as the zero of the codex; Nallino's apparatus suggests 113;8, Halley's reading. Schiaparelli, recomputing the eclipse from al-Battānī's tables, finds 113;13 for the mean anomaly and 114;13 or 114;14 for the true anomaly, for the 114;9 of the text; Nallino's translation has 113;13 and 114;14.

[187] Oppolzer's canon of eclipses gives this eclipse a magnitude of 11.2 digits, against the 10 digits, ⅝ of the diameter, observed by al-Battānī; for the next, 12.6 digits against nearly 12 (Schiaparelli, in Nallino's commentary).

and on those ratios only a half and a third of the diameter of the moon should have been eclipsed, and the time of the middle of the eclipse should have preceded the time at which it occurred by observation by about a half and a third of an equal hour.[188,189]

So the times and amounts of the eclipses and the positions of the two luminaries differed in everything that we have mentioned, and we found the like of that, and less and more, in many solar and lunar eclipses whose times we observed and whose amounts we established. We have contented ourselves with mentioning these two lunar eclipses. In both of them the sun was in the region of its farthest distance, and the moon in both was at one and the same place in its distance, about 1½ parts less than its mean distance; the latitude of the moon in both was on one side, and between its first latitude and its second there was 0;3,50. The difference between the two eclipses came to one part of 8 and a half and a quarter parts of the diameter of the moon. When that is multiplied by these minutes between the two latitudes, the whole diameter of the moon in these two eclipses comes out about 0;33,30. If the ratio of the diameter of the shadow to the diameter of the moon is the ratio that Ptolemy stated, which is about 2⅗ times the whole diameter of the moon, the radius of the shadow at the place of the moon's passage is about 0;43,30. In the measure in which the 36 minutes 10 seconds that the moon moves in an hour at the times of the conjunctions and oppositions, its greatest course at those times, are 35⅓ minutes, the amount of the diameter of the moon then, the 30 minutes 12 seconds that the moon moves in an hour at those times, its least course then, are about 29½ minutes; this happens when it is at its farthest distance, and that is then the diameter of the moon. Ptolemy, however, worked on the basis that it is 0;31,20, and carried out on that basis the computation and the derivation of the distances and the diameters.[190,191,192]

Ar. p. 88

Since what we wanted has become clear, and the diameter of the moon according to its passage at each of the two distances has become evident, and we have taken the ratio of the diameter of the shadow to the diameter of the moon to be the ratio mentioned, the radius of the shadow at the farthest passage of the moon is by it about 0;38,30 when the sun is at its farthest distance; when the sun is at its farthest distance and the moon at its nearest distance, the radius of the shadow is about 46 minutes. So it is clear that the radius of the shadow at the farthest passage of the moon is less than what Ptolemy worked with by about 2⅙ minutes, because of the excess that fell in the diameter of the moon in Ptolemy's computation. As for the radius of the shadow at the nearest passage, it is equal in amount in the two computations. It must also be that the radius of the shadow has, between the farthest and the nearest distance of the sun, a variation that measurement requires, of about 50 seconds: the radius of the shadow when the sun is at its nearest must be less by this amount than when it is at its farthest distance.[193]

[188] 2 August 901, 15⅓ hours after noon in true time at Antioch, that is, 3 August at about 3:20 in the morning (Nallino).

[189] The mean position of the sun must be Leo 16;10: with al-Battānī's equation of the sun this gives the true position 14;36 of the text, and al-Battānī's tables give 16;10 (Schiaparelli, in Nallino's commentary; Nallino's translation has 16;10). Schiaparelli also reads 110;11 for the mean anomaly (the text has 110;7, the codex 110;4) and 111;9 for the true anomaly (the text 111;5): in the Maghribi script of the codex the numerals 9 and 5 are easily confused.

[190] The anomalies of the sun in the two eclipses were 42 and 52 degrees. The distances of the moon, in parts of which its mean distance is 60, were 58.04 and 58.32, that is, 1.96 and 1.68 parts less than the mean. The difference of the latitudes, 4 minutes by the rounded values given above, is 0;3,49 by an exact computation: al-Battānī computed the eclipses more precisely than the text reports them (Schiaparelli, in Nallino's commentary).

[191] The magnitudes reported above, a little more than ⅚ of the diameter and a little less than the whole, differ by about ⅙, which would give 6 rather than 8¾, and a diameter of the moon of only 23 minutes. Schiaparelli, in Nallino's commentary, takes the passage as a check that the observations do not contradict a diameter of 33½ minutes, not as a measurement of it.

[192] Al-Battānī takes the apparent diameters of the moon to be in the ratio of its hourly motions. The hourly motions given here, 0;36,10 and 0;30,12, are not quite those of al-Battānī's tables, 0;36,4 and 0;30,18 (Schiaparelli). Ptolemy's 0;31,20 is in *Almagest* V 14.

[193] Ibn Yūnus objected that al-Battānī and al-Nayrīzī make the radius of the shadow vary by only about 7 minutes between the farthest and the nearest passage of the moon, much less than the geometry of the shadow requires; Ibn Yūnus agreed that the nearness of the sun changes it by no more than a minute (Nallino's commentary).

As for the solar eclipses, Ptolemy worked in them as we have mentioned, and made the diameter of the moon, when it is at its farthest distance, subtend an arc of the ecliptic of 0;31,20, and held that it then hides the whole sun at the times of the visible conjunctions, when it is on the belt of the signs to the sight. For this reason Ptolemy made the diameter of the sun equal to the diameter of the moon, so that, though the sun is many times greater, the moon hides it; and gave the diameter of the sun, relative to the moon, no change between its two distances, as Ptolemy did for the moon. But it had become clear to us by measurement that the diameter of the moon at its farthest passage subtends an arc of the sphere of 29½ minutes, and that it cannot hide the whole sun from sight when it is at its farthest distance, since the sun's diameter is greater than its own, subtending 0;31,20. That is when the sun is at its farthest distance, when its course in an hour is 0;2,23; when it is at its nearest distance, its course in an hour is 0;2,33. In the measure in which the 2 minutes and 23 seconds are 31⅓ minutes, the 2 minutes and 33 seconds are about 33⅔ minutes; so we find that the diameter of the sun, relative to the moon, changes between its two distances by 2⅓ minutes. By this the amounts of the solar eclipses came out right for us, and it became clear that the radius of the shadow at the farthest passage of the moon subtends an arc of the circle of the sphere of 0;38,30, and its radius at the nearest passage of the moon an arc of about 46 minutes.[194,195]

Let us try to show the distance of the sun and what appears with it. This cannot be done in the way close to the view on which Ptolemy worked, except by repeating the figure as it is and with the ratios given in Ptolemy's book, and then apportioning it according to what we found by our observations; for whenever we work with what we found by our observations, the ratios do not come out right and the distance is multiplied many monstrous times. So we draw this figure and then follow it with the explanation. Picture what is drawn for you in it, and picture how it is worked, and you will get it right, if God wills.[196]

Ar. p. 89

I began, with God's help, and drew three circles, their centres on a straight line, facing one another, some greater than others. On the greatest of them, which is the circle of the sun, I wrote ABG, and D at its centre; on the one next to it in size, which is the circle of the earth, KLM, and N on its centre; and on the smallest circle, in the middle, which is the third, the circle of the moon, HZḤ, and Ṭ on its centre. I placed it between the circle of the sun and that of the earth. I drew the two lines of the rays at the ends of the diameter of the sun, the signs A and G, touching the circle of the earth at the points K and M and meeting on the other side at the point S, so that the triangle ASG is the cone. The line DS divides it into two halves, so that it becomes two triangles, each of them right-angled. From the centre of the earth, the sign N, I also drew two lines that touch the circle of the moon at the signs Ḥ and H and pass through the signs A and G, touching the circle of the sun at them, because of the solar eclipses in which the moon hides the whole sun from the sign N. We draw the diameter AG, and the diameter HḤ, which we extend to the point Q; we draw also the diameter KM. We take the position of the moon when it is at its farthest distance from the earth at the times of the lunar eclipses to be the point F, and make the line ṬN equal to the line FN. Since the line DS passes through all the centres, it is clear in this figure that the line DA is the radius of the sun, the line ṬḤ the radius of the moon and the line MN the

[194]The translation follows the corrigenda in reading «تَغْيِيرًا», «change», for «تَعْيِيرًا» (p. 88, line 6).

[195]From these values al-Battānī concludes that the moon at its farthest distance cannot hide the whole sun, so that an eclipse of the sun can leave a ring of the sun visible, which Ptolemy's equal diameters exclude (Delambre, cited by Nallino). The eclipse of 8 August 891 described above was annular along a band across Asia Minor and Mesopotamia, not far from al-Raqqa (Oppolzer's canon, cited by Schiaparelli). Al-Battānī's diameters of the sun, 0;31,20 at its farthest and 0;33,40 at its nearest distance, compare with the modern 31′ 32″ and 32′ 36″, and al-Battānī's diameter of the moon at its farthest distance, 0;29,30, with the modern 29′ 26″ (Nallino's commentary).

[196]Ptolemy's figure and numbers, which follow, are those of *Almagest* V 15. The figure rests on the relation that the parallaxes of the sun and the moon together equal the apparent radii of the shadow and the sun together. With Ptolemy's values (radius of the shadow 0;40,40, of the sun 0;15,40, parallax of the moon at 64;10 radii of the earth about 53½ minutes) the parallax of the sun comes to about 2¾ minutes; with al-Battānī's radius of the shadow, 0;38,30, to about ⅗ of a minute, and the distance of the sun grows almost fivefold.

radius of the earth. We also draw the line ʿFḌ, which is the diameter of the shadow; so the line FḌ is the radius of the shadow.[197,198]

Ar. p. 90

What Ptolemy worked with, and on which the course of the computation rests, is that the line AS is 60 parts in the measure in which the diameter is 120 parts; the triangle ADS is right-angled and the distance is great, so the line DS is also about 60 parts in that measure. The angle ḤNṬ is 0;15,40 in the measure in which the four right angles of the circle that goes round the right-angled triangle ADS are 360, and the angle ḌNF is in this measure 0;40,40. The sine ṬḤ, which subtends the angle ḤNṬ, is 0;16,24, and that is the line ṬḤ; the sine of the angle ḌNF is 0;42,35, and that is the line FḌ, in the measure in which the line FN is 60 parts. But in the measure in which the line MN, the radius of the earth, was one part, and in which the line FN, the distance of the moon from the centre of the earth, was 64;10, the line ṬḤ is 0;17,33 and the line FḌ 0;45,38; so the ratio of FḌ to ṬḤ is the ratio of 2⅔ to one, approximately. The line ṬN is equal to the line FN, and therefore the line FḌ and the line ṬQ together are twice the line MN. When the line FḌ, which has been shown to be 0;45,38, and the line ṬḤ, which has been shown to be 0;17,33, are added together, the sum is 1 part 3 minutes 11 seconds of the double; when the line MN, which is the single one, is taken from it, the line ṬN remains, 3 minutes 11 seconds, and the line DL, which completes the double, is 56 minutes 49 seconds. Likewise the line ṬN is 0;3,11 and the line DṬ 0;56,49 when the whole line DN is made one part, and the line DN measures the line ṬN about 18⅘ times. Likewise the line DA measures the line ṬḤ also about 18⅘ times, which is the ratio of the line DN to the line ṬN. It has been shown that the line ṬN is 64;10 in the measure in which MN is a line of one part; so the line DN, the distance of the sun from the centre of the earth, is about 1210 times the line MN, the radius of the earth. The diameter of the sun is about 18⅘ times the diameter of the moon, but the diameter of the earth is about 3⅔ times the diameter of the moon; so the diameter of the sun is 5½ times the diameter of the earth.[199,200]

Ar. p. 91

The cube, which has length, breadth and depth, that results from multiplying one by itself and then by one is one: I mean the cube of the earth. The cube that results from multiplying 5½ by itself and then by 5½ is 166 and a quarter and an eighth. The cube that results from multiplying 18⅘ by itself and then by 18⅘ is 6644½. The cube that results from multiplying the diameter of the moon, which is the line HḤ, by itself and then by the diameter of the moon is one part of 39¼ of the cube of one. So the size of the sun is 166 and a quarter and an eighth times the size of the earth, and 6644½ times the size of the moon; and the size of the earth is 39¼ times the size of the moon.[201,202]

Further, if the line MN is one part, the line FḌ is 0;45,38, and the line FN in the same measure is 64;10. If the whole line SN is made one part, the line FS of it is 0;45,38 and the line FN 0;14,22, which remains to complete the one part. Since the line SF is [to the line FN] in the ratio of 45 minutes 38 seconds to 14 minutes 22 seconds, the line SF is 203 and a half and a third in the

[197] The text calls the greatest circle «the circle of the earth» as well; it is the circle of the sun.


[198] The lines from A and G touch the circles near the ends of the diameters drawn, not at them; the difference is imperceptible, and Ptolemy says that the lines through the points of contact are equal to the diameters to the senses (Nallino).

[199] Nallino takes «that the line AS is 60 parts … about 60 parts in that measure» and «of the circle that goes round the right-angled triangle ADS» for interpolations, found also in Plato of Tivoli: neither AS nor DS is 60 parts, as what follows shows. The angles are the apparent radii of the moon and of the shadow at the moon's farthest distance (*Almagest* V 14).

[200] «Twice» is supplied by Nallino. The line that completes the double, 2 − 1;3,11 = 0;56,49, is ḤQ; the text calls it DL. The words «the line ṬN remains, 3 minutes 11 seconds, and» anticipate the next sentence, where DN is taken as one part; Nallino's translation leaves them out and reads ḤQ (they are in the codex and in Plato of Tivoli). DN is to DṬ as MN is to ḤQ (Nallino). Ptolemy finds the same 1210 radii of the earth in *Almagest* V 15.

[201] The translation reads «والعُمْق», «and depth», for «والغَمْق» (p. 90, line 15), a misprint that the corrigenda do not list.

[202] Ptolemy (*Almagest* V 16) makes the sun about 170 times the size of the earth, the quotient of 6644½ by 39¼; al-Battānī cubes the rounded ratio 5½.



The line DN is not in the figure of the codex or in that of Plato of Tivoli; Nallino added it.

measure in which the line FN is 64⅙. When the line FN is added to the line SF, the line SN, from the end of the shadow to the centre of the earth, is about 268 times the radius of the earth; but [the line] from the centre of the sun to the end of the shadow, the line DS, is 1478 times the radius of the earth, the line MN. These are the ratios that Ptolemy derived, and the distances, on the basis of the size of the diameter of the shadow and the sizes of the diameters of the moon and the sun with which Ptolemy worked.[203]

Ar. p. 92

Since we have made clear the difference that appeared in this, that the diameter of the moon at its farthest passage is only 0;29,30, the radius of the shadow at the farthest passage of the moon 0;38,30, and the diameter of the sun, as has been said, 0;31,20, on this basis we find that the diameter of the moon falls short of the diameter of the sun by a minute and a half and a third. If we take its amount out of the 5 minutes and a half and a third by which the moon varies in its distance from the earth and its nearness to it, we find it to be about a third less a fifth of a tenth of that. When we take [that part] of the 10⅓ parts that are the whole diameter of the epicycle, by which the distance of the moon from the earth varies at the times of the conjunctions and oppositions, it comes to about 3⅕ parts. When we subtract that from the 64;10 that is the farthest distance of the moon from the earth, we find that the distance of the moon from the centre of the earth at the place where its diameter is 0;31,20, where it can hide the whole sun from sight, is about 60 and a half and a third and a tenth and a third of a tenth times [the radius of the earth]. When the diameter of the moon is 0;31,20, the radius of the shadow at the place of the moon's passage is about 0;40,40, which is close to the amount with which Ptolemy worked. When we multiply the 18⅘ by the 60 and a half and a third and a tenth and a third of a tenth, the distance of the sun from the centre of the earth when it is at its farthest distance is 1146 times the radius of the earth; and when we divide that by the 4½ parts that are, approximately, between the diameter of the earth and the diameter of the sun, [the line] from the centre of the earth to the end of the shadow is 254⅔ times the radius of the earth. Since the whole diameter of the epicycle of the sun, which is twice the distance between the centres, as appeared earlier in this book, is about 4⅙ parts, the variation of the distance of the sun from the centre of the earth is about 76 times the radius of the earth, and half of that, 38, is the share of the mean distance. So the nearest distance of the sun from the centre of the earth is 1070 times the radius of the earth, its mean distance 1108, and its farthest distance 1146, as has been shown; and the moon hides the sun from sight when there are about 1085 times the radius of the earth between it and the sun. This is the ratio that appeared to us from the solar eclipses.[204,205]

As for the moon's receiving light, it is from the sun, and the increase and decrease of its light are according to its distance from it and its nearness to it. For of every round body the eye falls only on the half that faces it. So the half of the globe of the moon that faces the earth is the half that faces the sun when we see the moon full of light, and that is at the times of the middle of the lunar month. When the half that faces the earth is other than the half that faces the sun, and the half that faces the sun is the remaining one, we see no light in it at all; that is the time of the dark of the moon. In between, we see the light in it according to how much of the light of the half that faces the sun falls in the half that faces the eyes. The farther it goes from the sun from the time of the dark of the moon, the more light there is in it, and it increases until the moon is opposite the sun, about a diameter of the sphere away, and is full of light. Then it begins to decrease, as it did in increasing, until it vanishes at the end of the month.

Ar. p. 93

We draw an example of this: a circle for the sphere of the moon about the centre Y, with the diameter ZN. We extend the diameter ZN to the point B, take the point B as centre and draw about it a circle for the sun, on the diameter AG. Let the point Y be the centre of the earth, and

[203] The words in brackets are supplied by Nallino. SN is to FS as MN is to FD. Ptolemy's values are in *Almagest* V 15.

[204] The distance is 60 29/30 radii of the earth; 18⅘ × 60 29/30 = 1146, and 1146 − 60 29/30 = 1085 (Nallino).

[205] Al-Battānī's distances of the sun, 1070 to 1146 radii of the earth, are like Ptolemy's 1210 about twenty times too small: the mean distance of the sun is about 23,500 radii of the earth.

the line BY represent the distance of the sun from the earth. We take the point N of the inclined lunar sphere as centre and draw about it a circle for the moon at the time of the conjunction, when the centre of its circle is under the centre of the circle of the sun in direction, I mean on the line that passes through the centre of the sun and of the earth. Then the centre of the circle of the moon moves away from the point N on its sphere according to its course in a day, or in more than a day or less, until it reaches the opposition, where the centre of its circle is the point Z. We mark the centres of the circles of the moon between the points Z and N, one after another, with the sign D. From the two ends of the diameter of the sun, the signs A and G, we draw lines to all the circles of the moon, so that two lines touch each of the circles at the two ends of a diameter of the circle of the moon; we mark on them in all the circles the signs K and Ṭ, and join the points K and Ṭ of each circle by a line passing through the centre D. Then we colour red the bright half of the circle of the moon, which faces the sun, and blot out the other half, which the sun does not see. Then we draw from the point Y, the centre of the earth, to each of the circles of the moon two lines touching the circle of the moon, mark the places of contact on each circle with the signs M and L, and join them by a line passing through the point D of each circle. So we find the half of that circle on which the eye falls, which is the half that faces the earth; and according to how much of the bright half that faces the sun falls in this half that faces the earth and on which the eye falls, is the amount of light seen in the moon. It is clear in this figure that the points M and L of the circle of the moon fall, at the dark of the moon, at the place of the points K and Ṭ. When the moon moves away from the sun, a small segment of the half of its circle that faces the sun falls in the half that faces the earth; the more its distance from the sun increases, the more the segment grows, until the quarter of the month is reached, when the [lit] half amounts to half of the half that faces the earth. Then the segment continues to grow beyond that amount until the moon is opposite the sun, when the whole half that faces the sun is the half that faces the earth, and the points M and L come to the places of K and Ṭ.[206]

We shall draw this figure and place ten circles of the moon in it; the distance of the moon from the sun in each of the nine circles after the circle of the conjunction is 20 parts of the parts of the half circle, and the shape of the light in the circle of the moon is according to the amounts of these distances from the direction of the position of the sun, which is the point B. Since this is so, the increase and decrease of the light of the moon has become clear in this figure, as you see it on the plane of the circle. In the round body, however, it is twice each segment, because its angle, in the spherical way, is unlike this figure; we shall represent it in what follows, if God Most High wills, and success is from God.[207]


Ar. p. 94

It has become clear from what has appeared that, in the measure in which the circle of the moon in which the light is seen complete is 15, each 12 parts of its distance from the sun are one part, up to the full 180, which make up the whole 15; and if the circle of the moon is 12 parts, each 15 parts of the distance are one of the parts of the light. On these ratios we have drawn the two circles and explained them, if God Most High wills.[208]

[206] In the printed figure the dark halves are hatched and the bright halves left white. Its letters are Nallino's: the figure of the codex and that of Plato of Tivoli have none. Nallino leaves out the lines from A and G that touch the circles of the moon at K and Ṭ, to keep the figure clear, and the lines from Y that touch them at M and L.

[207] That is, the circles stand 20 degrees apart: nine steps of 20 degrees lead from the conjunction to the opposition. For «what follows», Nallino suggests chapter 43.

[208] That is (Nallino): if the disc of the moon in the figure is made 15 degrees of its orbit, twelve discs fill the half orbit; if it is made 12 degrees, fifteen.




The words of the figure are «the sun», «dark» in the first circle, at the conjunction, «bright» in the last, at the opposition, «the earth», and, along the dashed arc on the right, «this half is like the other half»: the waning moon would repeat on the right the circles of the waxing moon.

Chapter 31. On the description of the spheres of the five stars and their states

Ar. p. 95

Al-Battānī said: As for the description of the spheres of the five stars and of their states, which have become known by way of demonstration from the anomaly of their course: each of them has four spheres, in the manner of the spheres of the moon. The first is made like the ecliptic: its centre is the centre of the ecliptic, it lies level beneath it, and its motion is like its motion. The second is the inclined sphere: its centre is the centre of the parecliptic sphere and its size the size of that sphere, and its greatest inclination from the circle of the parecliptic sphere, towards the north and the south, is the whole latitude of the star. Inside this sphere is another sphere, whose centre lies outside the centre of the two spheres; it hangs from it and touches it at a point, which is the point of the farthest distance. From the amount between the centres of the two spheres the equation of the anomaly and the centre of each of the stars is known, as was shown for the moon. The fourth sphere is the epicycle of the star. Its centre runs on this eccentric sphere from the point of the farthest distance in the order of the signs, by the amount of the mean motion of the star in longitude in a day; and the star moves on the epicycle, from the point of the distance that is seen from the centre of the ecliptic, also in the order of the signs, by the amount of the star's own motion in anomaly each day. The radius of each of the epicycles of the stars is the amount of [the sine of] its mean equation. It has a displacement in the lower and the upper part of the circle: it grows in the lower part, exceeding the mean, and shrinks in the upper part, falling short of the mean. This mean equation is what is set down in the sixth column of the tables of the equation of the star; the amounts of the shortfall are set down in the fifth column, and the amounts of the excess in the seventh. What is set down in the fourth column is the minutes in proportion to which [a part] of the excess and the shortfall is taken, in the way that I gave for the moon for the excess. What is set down in the third column is the equation of the anomaly and the centre, which results from the distance between the centres. These are the figures of the spheres that we said we would draw.[209]

Ar. p. 96



210

[209] The words in brackets, «the sine of», are added by Nallino's emendanda (Part II, p. XXXI). The «centre» is the distance of the centre of the epicycle from the farthest distance of the eccentric, counted at the centre of the eccentric; the «equation of the anomaly and the centre», which the eccentricity produces, is applied to both (Nallino).

[210] Nallino prints the figure as the codex gives it, «most ineptly» in Nallino's words. Schiaparelli, in the commentary, points out that the circle of the ecliptic and the inclined circle cannot be drawn in one plane as two circles about different centres, that the nodes B and D are put 90 degrees from the line of the apsides, which is true of no planet,

Al-Battānī said: The first thing I drew was the circle of the parecliptic sphere, marked ABGD, about the centre H; another circle, for the inclined sphere, marked ḤBZD, whose centre is also the point H, as it falls on the globe; and a third circle, for the eccentric sphere, marked ḤṬKL, with M at its centre. Clearly the point Ḥ is the farthest distance of the eccentric sphere and the point K its nearest distance. We take the point Ṭ of the eccentric sphere as the centre of the circle of the epicycle and draw about it the circle of the epicycle, marked FQS. We draw from it the line MṬQ and the line HṬF, take the position of the star on the epicycle to be the point ʿ, and draw the line HʿN, along which the motion of the star on the ecliptic is seen. Clearly the diameter AZ passes through the centres. Again we take the point L of the eccentric sphere as centre and draw about it a circle for the epicycle, marked Y LA Sh; we draw the two lines M L Y and H L LA, put the star at the position Sh of the epicycle, and draw the line H Sh Ḍ, along which it is seen on the ecliptic.[211]

Ar. p. 97

It is clear in these circles that, when the point A is the direction of the farthest distance on the ecliptic, the star is at the point ʿ of the epicycle whose centre is Ṭ, and the centre of the epicycle is at the point Ḥ, the line that goes out from the point H passes through the centre M and the points A and Ḥ, and we find the point of the farthest distance on the epicycle at the sign Q, on the line MṬQ. For the line MṬQ is then in the place of the line HMA, and the place of Q is then the place of A; so the mean and the true farthest distance are the same, without any difference, since the line HṬF, along which the true point of the farthest distance is seen, then also comes into the place of the line HA. But when the centre of the epicycle comes to the place Ṭ, between the points Ḥ and K of the eccentric sphere, which is less than half its circle, the place of the true distance on the epicycle is the point F and the place of the mean farthest distance the point Q; from Q the course of the star on its own epicycle is counted, which is the arc Qʿ, and so its course in anomaly is greater than the arc Qʿ by the arc QF, which is the difference. Likewise the position of the centre of the epicycle that is seen from the point H on the ecliptic is less than the one seen from the centre M, again by the arc QF, since the point F is nearer to the point M than the point Q is. Likewise, when we put the centre of the epicycle in the second half of the circle, at the point L, the position of the centre of the epicycle in which it is seen on the ecliptic from the centre H becomes greater than the position in which it is seen from the centre M, by the arc LA Y, and the true farthest distance, which is seen from the centre H, becomes less than the mean farthest distance, which is seen from the centre M, again by the arc LA Y. For the star is at the mark Sh of the epicycle; its mean motion on its own epicycle is from the point Y to the point LA and then to the point Sh, and its true motion is from the point LA, so that the arc LA Sh of the epicycle is smaller than the arc Y LA Sh by the arc Y LA. Therefore the equation of the anomaly and the centre is added to the centre when the motion of the centre of the epicycle is between the point of the farthest distance of the eccentric sphere and its point of the nearest distance on the side of the sign L, and it is subtracted from the anomaly; and when the centre of the epicycle is in the second half of the eccentric sphere, on the side of the sign Ṭ, the equation of the anomaly and the centre, which is the arc Y LA, is subtracted from the centre and added to the anomaly. When the true position of the centre on the ecliptic is known, it gives the shares of the difference, of the excess and the shortfall, that belong to the epicycle at its displacement, since it is on the eccentric sphere.[212]

Ar. p. 98

Further, when the star is at the position ʿ of the epicycle, its distance from the point Q is less than

and that the lines of sight need not touch the epicycles. Schiaparelli suspects that the circle drawn about M as large as the ecliptic was at first the equant of Ptolemy's theory, the circle about which the centre of the epicycle moves uniformly.

[211] The text has S for Sh, in the letters of the second epicycle (the codex has ʿ) and for the position of the star on it; the figure and what follows have Sh, as Nallino's translation reads.

[212] The text has the centre of the epicycle move uniformly about the centre M of the eccentric, and so counts the «centre» at M; in Ptolemy's theory the uniform motion is about the equant point, which lies as far from M as H does, on the other side (Schiaparelli, in Nallino's commentary). On the side of Ṭ the equation is the arc QF; the text names the arc Y LA of the other half (Nallino).

half the circle of the epicycle, so the position in which it is seen on the ecliptic is greater than the position of the centre Ṭ on the ecliptic by the arc on the perpendicular ʿṬ. When the star is at the position Sh, the arc LA Sh of the epicycle is more than half its circle, so the position in which it is seen on the ecliptic is less than the position in which the centre L is seen by the arc that falls on the perpendicular L Sh. Therefore the mean equation of the star, corrected for the displacement of the epicycle, is added to the corrected centre when the corrected anomaly of the star is less than 180, and is subtracted from it when the corrected anomaly is more than 180; what results after that addition or subtraction is the distance of the star on the ecliptic from the point of the farthest distance of the eccentric sphere, whose position on the ecliptic is determined.[213]

As for the cause of the retrogradation of the wandering stars, it is that the change of the equation of the star, in its increase and decrease in one day, is at some of its places on the epicycle greater than its mean course, which is the motion of the centre of the epicycle on the eccentric sphere in a day. When the true position of the star is computed for a day, and its course for another day is then added to its mean position, and from that is subtracted an equation that exceeds the first equation by more than its mean course in that day, or to it is added an equation that is less than the first equation by more than the mean course of the star in the day, the position of the star on the ecliptic is less than the position in which it was at first. This can happen only when the star is in the nearer half of its epicycle, which is necessarily smaller than the upper half, since the arc of the eccentric sphere bounds these two halves: the lower half is the arc Sh W, and the upper half the arc W LA Y Sh. So when the course of the star from the point of the farthest distance on the epicycle reaches the point W, it is there like one standing set up in the circle, for it then falls on the line that touches the epicycle and goes out from the point H. The decrease and increase of the change of its equation in a day are then equal to its mean course in a day, and no motion appears in it until it passes the point W and falls in the lower half. Then its motion on the ecliptic continues to be seen towards the preceding side of the signs until it reaches the sign Sh and falls on the tangent line a second time, when it is like one standing raised in the circle on that side. When it rises from the point Sh, its motion begins to be seen in the order of the signs, as long as it is in the upper half of the epicycle. Yet the star in itself has no retrogradation in its course; this befalls it only for us, because of the difference of the centres of its spheres and its state on the epicycle.[214,215]

As for the sun and the moon, this does not befall them for us, because the course of each of them in a day is many times greater than the change of its equation in a day. So the state of retrogradation is not evident in them, although they too must in themselves have a course in the nearer half of their epicycles; but it is not perceived in them.

Ar. p. 99

We have tested the motion of each of these five wandering stars many times at places on their epicycles: at one, when the star was at their point of the farthest distance; at a second, when it was at the point of the mean distance; at a third, when it was at the point of the nearest distance; and at other places of the centre of the epicycle on the eccentric sphere, farther from and nearer to its point of the farthest distance. So we established what appeared of their mean motions in longitude in excess of the motions set down in Ptolemy's book, and also what appeared of the anomaly of their motions and of the positions of their farthest distances on their spheres

[213] «The arc on the perpendicular ʿṬ» is the arc whose sine is the perpendicular from Ṭ to the line of sight Hʿ, that is, the angle at H between the centre of the epicycle and the star; in the figure the line of sight touches the epicycle at ʿ (Schiaparelli, in Nallino's commentary).

[214] In modern terms, the motion in longitude in a day is the mean motion together with the change of the equation; when the change is negative and greater than the mean motion, the star goes backwards. The sentence from «When the true position» restates this obscurely (Schiaparelli, in Nallino's commentary).

[215] Delambre, cited by Nallino, points out that at the point of contact the star moves along the line of sight, so that its motion on the epicycle adds nothing to the motion of the centre: the star is not stationary there, and the stations fall between the points of contact and the nearest point of the epicycle. The points of contact are not where the epicycle cuts the eccentric either, as the figure itself shows (Nallino).

eccentric to the ecliptic. We corrected it and entered it in the tables, after adding to their course in longitude the correction that we found in each of them. Their equations we found close to those in Ptolemy's book, and the positions of their distances likewise, and we entered them as they were, except the farthest distance of Jupiter: we measured it by the moon many times, according to the visible position of the moon at the times of the measurements, and found that it was less than the amount set down by about 8 parts.[216]

Since the motions of the upper stars on their epicycles are what remains of the mean course of the sun when the mean motion of the star in longitude is taken from it, and the mean course of Venus and Mercury is equal to the mean course of the sun, their anomaly is obtained from the tables. We found the anomaly of Venus greater than its anomaly as set down by about 4½ parts, and that of Mercury by about 2½ parts. We divided that over the time between us and Ptolemy, and added what fell to one day to the course in anomaly of each of them for a day. As far as we were able, we have left nothing from which we saw that a defect might arise without putting it right, although their motions cannot be grasped exactly, as the motions of the two luminaries can, since their observations were made only when they came close to some of the fixed stars. Since their farthest distances also move with the motion of the sphere of the fixed stars, we have had no need to set down tables of the motions for the anomaly of each of the upper stars and for the course of the two lower stars, or of the measurement of their distances from the Heart of the Lion or from other fixed stars. We have also left out the mention of the observations of them that we made at the places mentioned, for the sake of brevity and so as not to lengthen the discourse in the explanation that we are attempting for each of them.[217]

Ar. p. 100

As for the latitudes of the three upper stars, I mean Saturn, Jupiter and Mars, they come close to the amounts that we found in Ptolemy's book, and we kept them as they were for finding their latitudes. But in the latitudes of Venus and Mercury we found a great discrepancy, which arose, as we think, from the procedure used to find the latitude; so we changed the method of working that we found for them in Ptolemy's book to one that we saw comes close to and agrees with the latitudes that we find for them by observation. It may be that what happened in the procedure in Ptolemy's book came from the translator of Ptolemy's Greek words, or from a fault in the copy from which the book was translated; and God knows best.[218]

Chapter 32. On knowing the eras of the Arabs, the Romans, the Copts and the Persians, and on converting them into one another[219]

Ar. p. 100

Al-Battānī said: The names of the months of the Arabs are al-Muḥarram, Ṣafar, Rabīʿ I, Rabīʿ II, Jumādā I, Jumādā II, Rajab, Shaʿbān, Ramaḍān, Shawwāl, al-Qaʿda and al-Ḥijja. They are a month of 30 days and a month of 29 days, alternately, except Dhū l-Ḥijja, which has 29 days and a fifth and a sixth.[220]

[216] In the 740 years between the epochs of Ptolemy's tables (AD 137) and al-Battānī's (AD 880), al-Battānī's mean motions in longitude exceed Ptolemy's by 2° 54′ for Saturn, 3° 5′ for Jupiter and 4° 12′ for Mars, and are better than Ptolemy's (Nallino). Al-Battānī's farthest distances of Saturn and Mars are 20° 18′ greater than Ptolemy's (for Mars with Nallino's correction of the minutes), that of Jupiter only 12° 19′, the 8 degrees of the text. Al-Battānī had raised Ptolemy's longitudes of the fixed stars by 11° 10′; Nallino does not know why al-Battānī used 20° 18′ for the farthest distances, and supposes that the value rests on al-Battānī's own observations.

[217] Over the 740 years between the epochs of the two sets of tables, al-Battānī's anomalies exceed Ptolemy's by 4° 28′ for Venus and by 0° 57′ for Mercury; Nallino's translation therefore has 1 degree for Mercury, where the codex has 2½ and Plato of Tivoli 11½. Such tables, with the positions measured from the Heart of the Lion (Regulus), are in Theon's tables (Nallino).

[218] Al-Battānī's procedure for the latitudes of the five stars is in chapter 47.

[219] The translation reads «المستقبلة» for «المستقباة» (p. 105, line 4) and «بتأريخ» for «يتأريخ» (p. 105, line 9), misprints that the corrigenda do not list.

[220] A fifth and a sixth make 11/30 of a day: the lunar year has 354 11/30 days, which rest on the synodic month of 29;31,50 days (Nallino). Over thirty years Dhū l-Ḥijja gains 11 days, and the year in which it has 30 days is a leap year.

The names of the months of the Romans, with the beginning [of the year] of the Greeks and the people of Egypt: Aylūl, 30 days; Tishrīn I, 31 days; Tishrīn II, 30 days; Kānūn I, 31 days; Kānūn II, also 31 days; Subāṭ, 28 days and a quarter of a day: the quarter is added to the quarter for three successive years, and the year is intercalated in the fourth, Subāṭ then having 29 days; Ādhār, 31 days; Nīsān, 30 days; Ayyār, 31 days; Ḥazīrān, 30 days; Tammūz, 31 days; Āb, 31 days. So the days of the non-Arab year are 365 and a quarter of a day in all, and in the leap year 366; this is the year in which Subāṭ has 29 full days, if God wills.[221]

Ar. p. 101

The names of the months of the Persians: Farwardīn-māh [its first day is the Nayrūz], Ardibihisht-māh, Khurdādh-māh, Tīr-māh, Murdādh-māh, Shahrīwar-māh, Mihr-māh, Ābān-māh — the twenty-sixth day of Ābān-māh [begins] the Farwardajān, which is ten days: five of them are the rest of Ābān-māh, up to the thirty that are due to it, and five are days that are dropped and not counted among the months; the sixteenth day of Mihr-māh is the Mihrajān — Ādhar-māh, Day-māh, Bahman-māh and Isfandārmadh-māh. Each of these months has 30 days, and five days after Ābān-māh are a cast-off addition; so the days of the Persian year are 365 in all, without a fraction, if God wills.[222]

The names of the months of the Copts: Tūt, Bābah, Atūr, Kiyahk, Ṭūbah, Amshīr, Barmahāt, Barmūdhah, Bashans, Baʾūnah, Abīb and Misrā. Each of these months has 30 days, and five days, which are cast after the months, are called the added days; so the days of the Coptic year are 365 and a quarter of a day in all, and in the fourth year 366 days. The era of the Romans and the Copts is, for the people of Egypt, from the death of Alexander the Macedonian, and for the Romans from the years of Dhū l-Qarnayn Alexander; between the two there are twelve Egyptian years.[223]

If you wish to know, by the years of the Hijra, the beginning of any month of the years of the Arabs that you want, take the complete years of the Hijra and multiply them by 354 days and a fifth and a sixth of a day. Look at the result: if there is a fraction in it, and the fraction is less than half a day, drop it and do not count it; if it is more than half a day, count it as a day and add it to the sum of the days. The number of days that results is the number of days that have passed from the beginning of the Hijra to the end of that complete year; it is the root, so keep it. Then take this root, add 5 days to it, and cast out the sum seven by seven; what remains, less than seven or seven, is the sign of the coming year. Cast it from Sunday, and the reckoning brings you to the day on which al-Muḥarram begins in the year you are in, which is the incomplete year. If you want another of the months, add to the sign of the year, for the months of the complete year that have passed, two days for one month and one day for the next, which makes three days for every two full lunar months; if there is a single month, or a single month remains, take two days for it. Then cast that out seven by seven, and cast what remains, less than seven or seven, from Sunday; the reckoning stops at the day on which the month whose sign you sought begins. This is the reckoning on which the zījes and the chronologies are made; do not go past it to another, whether it gives more or less.[224]

Ar. p. 102

[221] These are the Syrian names of the Julian months, from September to August. Other Arabic writers begin the year with Tishrīn I, October, as was the custom of the Syrians; al-Battānī begins it with 1 September, as the Byzantine indiction did (Nallino).

[222] *Māh* is Persian for «month»; *Nayrūz*, «new day», is the Persian new year. The words in brackets stand after Ardibihisht-māh in the codex; Nallino moves them here. The five added days stood after Ābān-māh in al-Battānī's time; the Farwardajān is the festival of the last ten days of the year.

[223] The era of Dhū l-Qarnayn is the Seleucid era, which al-Battānī begins on Saturday 1 September 312 BC; the era from the death of Alexander is the era of Philip, which al-Battānī takes from Theon's tables (Nallino). The Coptic era of this chapter, as the rules below show, is the Alexandrian era of Augustus, whose first day al-Battānī puts on Friday 29 August 25 BC, 287 Julian years less 3 days after the era of Dhū l-Qarnayn (Nallino).

[224] To cast a number from Sunday is to count it off from Sunday: 1 is Sunday, 2 Monday, and 7 Saturday. With no complete years the sign is 5, a Thursday: the astronomers' first day of the Hijra, 15 July 622; in civil use the era began on Friday (Nallino). Months of 30 and 29 days leave 2 and 1 when the weeks are cast out.

If you wish to know the beginnings of the Roman months by the era of Dhū l-Qarnayn, with the beginning [of the year] of the Egyptians, take the complete years of Dhū l-Qarnayn and add to them a quarter of them. If there is a fraction in the result, do not count it, whether it is more than a half or less; then multiply the total by 365 days and cast out the result seven by seven. What remains, less than seven or seven, is the sign of the year; cast it in the first way, and you come to the first day of Aylūl of the coming year, the one you are in. If the fraction is exactly half, the year that is coming in on you, I mean the coming year, is a leap year; if it is more than half or less, it is not. If you want another month than Aylūl, add to the sign of the year, for the complete months of the year that have passed, two days for each month of 30 days and three days for each month of 31 days, and take nothing for Subāṭ unless the year is a leap year, when you take one day for it. Cast out the result seven by seven and proceed with it in the way of casting given before, and you come to the first day of the month that you want, if God wills.[225]

If you wish to know the beginnings of the Persian months by their known years, take the complete years of Yazdajird son of Shahriyār son of Kisrā, king of the Persians, always add three to them, and multiply them by 365. Cast out the result seven by seven, and cast what remains, less than seven or seven, from Sunday; the day at which the count stops is the first day of Farwardīn-māh, which is the day of the Nayrūz. If you want another of the Persian months, add to the sign of the year, by which you found the day of the Nayrūz, two days for each of the complete months of the year that have passed, except Ābān-māh, for which you take nothing. Then cast that out seven by seven, proceed in the way of casting it from Sunday, and take the day at which the count stops as the beginning of the month that you sought.[226]

Know that the Copts precede the Greeks of the people of Egypt at the entry of Aylūl by three days, and that they [the Greeks] outrun them in the era by one day every four years. If you wish to know the beginnings of the months of the Copts, take the complete years of Dhū l-Qarnayn, always add six to them, and multiply it by the days of the year. Cast out the result seven by seven and carry out what remains, less than seven or seven, in the way given before; where the count brings you is the first day of Aylūl, which is Tūt, of the coming year. If you want another of the months, add to the sign of the year two days for each complete month of the year that has passed; cast out the result seven by seven and cast what remains, less than seven or seven, from Sunday; the day to which the count brings you is the beginning of the month that you want. If all the months have run out, cast five more days after that, and then the coming year begins, because those days are the added days, which are not counted among the months, if God wills.[227]

Ar. p. 103

If you wish to know the era of the Romans by the era of the Hijra — this is the conversion — and so to know the day of the Roman months on which you are and how many years [have passed] of Dhū l-Qarnayn, take the Arab root that I told you to keep and add to it 317. Add to the result the Arab months and days of the year that have passed, and divide the total by 365 days and a quarter of a day. What comes out is complete years; always add 932 years to them, and the total is the complete years of Dhū l-Qarnayn, so keep them. From the days that remain short of a year cast off, for each month, the number of its days, beginning with Aylūl: what comes out is complete months, and what does not make up a month is the days that have passed of the month at which you stopped, which is the current month, the one you are in. If a fraction is left over,

[225] Since 365 is 52 weeks and 1 day, the multiplication by 365 does not change what remains when the sevens are cast out. As stated, the rule leaves out the leap day in the year after a leap year: for 1 Aylūl 1192 of Dhū l-Qarnayn, 1 September 880, a Thursday, it gives Wednesday. Counting a fraction of three quarters as a whole day gives the right day in every year.

[226] The era of Yazdajird began on Tuesday 16 June 632 (Nallino). Ābān-māh with the five added days has 35 days, a whole number of weeks (Nallino).

[227] In the year before a Roman leap year the Copts begin their year only two days before Aylūl: the Alexandrians put their extra day at the end of that year (Nallino, after a chronological fragment ascribed to Heraclius). The six makes the count begin on a Friday, the first day of the Coptic era as al-Battānī reckons it; the codex has 7, Plato of Tivoli 5 (Nallino).

do not count it; if the fraction is exactly a half, the year you are in, which is the coming year, not included in the number of years that you kept, is a leap year, so take 29 full days for Subāṭ in that year, if God wills.[228]

If you wish to know the era of the Copts exactly from the era of the Romans, take the years of Dhū l-Qarnayn together with the year that you are in, even if only one day of it has begun, and take 287 from them. Take a quarter of what remains: if there is a fraction in it, do not count it; if there is no fraction, the year that you are in is a leap year. When there is no fraction, take one day from what the quarters give you, unless Subāṭ has run out; once Subāṭ has run out, add that day to the quarters. Always add to the result the three days by which the Copts precede the Greeks at the entry of Aylūl, which is Tūt, and add to the result [the days] from the first of Aylūl to the day that you are in. If that is more than 365, cast off 365 from it, and add a complete year to the years of Dhū l-Qarnayn that you have. If the year is a leap year and Subāṭ has run out, take 29 days [for it] and cast off 366 days from the days that you have collected. The days that remain after that are the days that have passed of the Copts in the year of the Copts that you are in; cast off 30 days for each month, beginning with Tūt. What comes out is complete months, and what remains below 30 is the days that have passed of the month of the Copts that you are in. With this era the motions of the stars are found by Theon's canon, after 12 years have been added to the years, so that they run from the death of Alexander the Macedonian; and do not count the first month set down in the tables among the months.[229]

Ar. p. 104

If you wish to know the era of the Persians from the era of the Hijra by computation, take the Arab root that I told you to keep, and add to it, for the months of the year that have passed, 30 days for one month and 29 days for the next; add also the days that have passed of the Arab month that you are in. The result is the number of days that have passed from the beginning of the Hijra to the day that you want. Take from it 3624 days, the days between the Hijra and Yazdajird, and divide the remainder by 365: what comes out is complete years from the death of Yazdajird. From what remains below 365 take for each month the number of its days, beginning with Farwardīn-māh; the day at which you stop is the day that has passed of the current month of the Persians that you want. When you count Ābān-māh, reckon 35 days for it, for the five added days that go with it, I mean that are dropped after it and not counted. The day that follows the day on which the number of the days of the Persian year is complete is the day of the Nayrūz among the months of the Persians. Know this and understand it, and you will find what is right, if God wills.[230]

If you wish to know the era of the Hijra from the era of the Romans, with the beginning of the Egyptians, take 932 years from the complete years of Dhū l-Qarnayn and multiply the remainder by 365 days and a quarter of a day; if there is a fraction, keep it. Then take 317 days from the days that you have collected, and add to the remainder the days that have passed of the year that you are in, from the first of Aylūl to the day that you are in. The result is the number of days that have passed from the first year of the Hijra to the day that you want. Divide it by 354 days and a fifth and a sixth of a day: what comes out is complete years that have passed from the beginning of the Hijra. If what remains below that has a fraction, and it is less than a half, drop it and do not count it; if it is more than a half, make it up to a day and add it to the days. Then take the days out from al-Muḥarram, for each month the number of its days, a month of 30 days and a month of 29 days. What comes out is complete months that have passed of the coming year, I mean the current year of the years of the Hijra that you are in, which is not included in

[228] The 317 days run from 1 Aylūl 933 of Dhū l-Qarnayn, 1 September 621, to the first day of the Hijra, 15 July 622; 932 years of the era were then complete (Nallino).

[229] 287 is the number of years between the era of Dhū l-Qarnayn and the Coptic era of this chapter (Nallino). Theon's tables give the motions at the beginnings, not the ends, of the months, days and hours, so that their first month adds nothing (Nallino).

[230] The 3624 days run from the first day of the Hijra, 15 July 622, to the first day of the era of Yazdajird, 16 June 632. «The death of Yazdajird» is a slip for Yazdajird's accession, which is not rare in Arabic writers (Nallino).

the number of years; and the days that remain below a month are what has passed of the month of the Arabs that you are in.

If you seek the era of the Hijra from the era of the Persians, take the complete years of Yazdajird and multiply them by 365 days; add to the result [the days] from the first of Farwardīn-māh to the day that you want, and add to the total 3624. The result is the days that have passed from the beginning of the Hijra; make them Arab years in the way given before.

Ar. p. 105

If you wish to know what has passed of the era of the Persians from the era of the Romans by computation, take the complete years of Dhū l-Qarnayn and cast off 943 years from them; what remains is the years that you want, so keep them. Then take a quarter of them; if there is a fraction in it, do not count it. To the days of the quarters always add 77 days, and add to the result [the days] from the first of Aylūl to the day that you want. If the total is more than 365 days, cast off 365 days from it and add another year to the years that you kept; from the days that remain cast off for each month the number of its days, beginning with the first of Farwardīn-māh, in the way given before. If the fraction that comes from the quarters is three quarters, that year is a leap year, so take 29 days for Subāṭ in it. If you need to know on which day of the Roman months the Nayrūz of the coming year falls, take what you have collected from the quarters together with the 77 and always subtract it from 366; cast off what remains from Aylūl, for each month the number of its days. The day of that Roman month at which you stop is the day of the Nayrūz, which is the first day of the coming year of the years of the Persians that you are in. What follows the Nayrūz in the days and months of the Persians is as I have described.[231]

If you wish to know what has passed of the era of the Romans from the era of the Persians by computation, take the complete years of the Persians and multiply them by 365 days; add to that [the days] from the first of Farwardīn-māh to the day that you want, and divide the result by 365 days and a quarter of a day. What comes out is complete years; add to them 943 years, and the result is the complete years of Dhū l-Qarnayn. Cast off what remains of the days from Aylūl, for each month the number of its days, and do not count a fraction; if no fraction remains, the year is a leap year, so allow 29 days for Subāṭ in that year.[232]

If you wish to know the era of the Romans by the era of the Copts, take the years of the Copts, which are the Egyptian years of Dhū l-Qarnayn, the complete ones, and cast off 287 from them. Find a quarter of what remains, and whatever it is, take it from the days that have passed of the coming year of the years of the Copts that you are in, from the first of Tūt to the day that you want. Cast off three days from what remains, and cast off the rest from the first of Aylūl: where you arrive is the day that has passed of the Roman month that you are in. If the days of the quarters are more than the days collected from the first of Tūt, take a year from the years of the Copts, add 365 days to the days that you have, and take from them the days that come from the quarters; take out what remains from Aylūl in the way given before. When there is a fraction in the quarters, do not count it.

If you add 12 years to the complete years of the Copts, they run from the death of Alexander the Macedonian; if you then add to that 424 Egyptian years, the total is the years of Ptolemy's book, with which Ptolemy worked in finding the motions, from the beginning of the reign of Nabonassar to the year at which you arrive of the years of the Copts and their days of the coming year. We have made tables for the eras of the Arabs and the Romans, by which they are found from one another, and tables by which the beginnings of their months are found, and we have explained the working with them at those tables, so that whatever is needed of this may be easily

[231] 943 years of Dhū l-Qarnayn were complete on 1 September 632, and the 77 days run from the beginning of the era of Yazdajird, 16 June 632, to that day (Nallino). The Persian year has no quarter day, so the days of the quarters are added.

[232] As stated, the rule counts the days of the Persian era from 1 Aylūl, although the era began on 16 Ḥazīrān, 16 June 632, 77 days earlier: the 77 days must first be taken from the days, as the converse rule above adds them.

known at any time you wish, if God wills.[233]

Chapter 33. On knowing the mean position of the sun and its true position, in which it is seen on the ecliptic, by the eras of the Romans and the Arabs

Ar. p. 106
Ar. p. 107

Al-Battānī said: If you wish to know the position of the sun on the ecliptic by the era of the Romans, take the complete years of Dhū l-Qarnayn, and do not count the broken year that you are in until the last day of Subāṭ has run out, at noon on it; then count it. Look for the same number of years as you have in the column of numbers of the tables of the collected Roman years, which go in steps of twenty years. Wherever you find the same number, or the nearest one below it, take what stands opposite it of the degrees, minutes and seconds set down in the column of the mean motion of the sun, and write them down. Then subtract the years that you found in the table from the years that you had: what remains is single years. Look for the same number in the column of numbers of the tables of the single Roman years, take again what stands opposite it in the column of the mean motion of the sun, of degrees, minutes and seconds, and write each kind under its kind, under what you wrote first. Then look in the table of the Roman months for the name of the complete Roman month before the month that you are in, take what stands opposite it in the column of the mean motion of the sun, and write those degrees, minutes and seconds under what you wrote before, each kind under its kind. Then enter with the number of the days that have passed of the Roman month that you are in into the table of the days of the column of the mean motion of the sun, take again what stands opposite it of degrees, minutes and seconds, and write them with what you wrote from the three places mentioned before. Then begin by collecting the seconds and add them up; take 60 from them, reckoning a minute for each time you take it, and carry that to the minutes, and write what remains below 60 under the seconds. Then add up the minutes, with what has been carried to them from the division of the seconds; take 60 from the sum, reckoning a degree for each time you take it, and carry that to the degrees, and write the minutes that remain below 60 under the minutes. Then add up the degrees, with what has been carried to them from the division of the minutes. If the sum is more than one circle, or several circles, the amount of a circle being 360 degrees, cast off the circles from it and write what remains below 360 under the degrees. The degrees, minutes and seconds that result are the mean motion of the sun collected from the four entries; it is the position of the sun by its mean course on the ecliptic, from the beginning of Aries. Cast off 30 from the degrees for each sign; what remains below that is the degrees, minutes and seconds that the sun has traversed of the sign that it has not completed, the one that does not make up 30.[234]

If you wish to know the mean position of the sun by the years of the Arabs, take the years of the Hijra together with the year that you are in and enter them in the tables of the motion of the sun, in the column of the collected years of the Arabs, which go in steps of thirty; look for the same number or the nearest one below it, with the number of the single years, and follow the procedure given before, which I set out with the years of the Romans and their months. What is collected of the motion of the sun from the four entries, after the circles are cast off, is the mean position of the sun; it comes to the same whichever of the two eras you have worked with. Let this description be a model for you in finding the mean positions of the other stars and their arguments.

When you know the mean position of the sun, subtract its farthest distance from its mean position: its anomaly remains, so write it down under the mean position of the sun. Then enter

[233] The Arabic calls Nabonassar «the first Bukhtanaṣṣar»; the era of Philip began 424 Egyptian years after the era of Nabonassar (Nallino).

[234] The collected years (*al-sinūn al-majmūʿa*) are tabulated in steps of twenty years, the Arab ones in steps of thirty; the single years (*al-mabsūṭa*, «spread out») run from one upwards. The years of the tables begin on 1 Ādhār, March, so that the leap day is the last day of the year; the mean motions at the epochs are for noon on 1 Ādhār (Schiaparelli, in Nallino's commentary).

with the anomaly of the sun into the tables of the equation of the sun, in the two columns of numbers, take the degrees, minutes and seconds that stand opposite it in the first column after the two columns of numbers, headed «equation of the sun», and write them under the anomaly. Then look: if the anomaly of the sun with which you took the equation is less than 180 degrees, subtract the equation from the mean position itself, and if this anomaly is more than 180, add the equation to the mean position. What results after the addition or the subtraction is the true position of the sun, in which it is seen on the ecliptic. Cast it from the beginning of Aries, giving each sign 30 degrees, and the count stops at the second of the minute of the degree of the sign in which it is.

This equation is for the time of noon at the city of al-Raqqa on the day for which you have computed. If there are minutes with the anomaly, take the equation that stands opposite the complete degree and keep it, and find the difference between it and the equation that stands opposite the degree one above it. Take of the result in the proportion of those minutes to 60, and subtract what you obtain from the equation that you kept if that one is the greater, or add it to it if it is the less. The equation opposite the complete degrees that you kept, after the addition or the subtraction, is the exact equation for that anomaly. Let this be a model for you to work with for all the minutes that you find with the anomaly of the moon and of the stars, if God wills.[235]

Ar. p. 108

The farthest distance of the sun was, in the year 1191 of Dhū l-Qarnayn, on the first day of Ādhār, at about Gemini 22;15, which is 82;15 from the beginning of Aries. If you wish to compute the position of the sun for before this year or after it, find the difference between this year and the year for which you wish to compute, and take one degree for each 66 Roman years. Subtract the degrees and minutes that result from 82;15 if the time of the computation is before the year mentioned, and add them to it if it is after it; the distance of the sun that results after the addition or the subtraction is its farthest distance in the year for which you compute. For its farthest distance moves with the motion of the sphere of the fixed stars, which is, as we found by observation, one degree in each 66 Roman years; that is also about one degree in each 68 lunar years. If your computation is by the era of the Arabs, carry it out as I have described for you.[236]

Chapter 34. On knowing the hours of the computation in every locality, which are the equal hours, also called the mean hours, after noon at the city of al-Raqqa

Ar. p. 108

Al-Battānī said: If you wish to know the hours of the computation in any locality you want — the hours by which the motions of the stars are found in this book, since we have set the computation of the stars in it for the time of noon, at the city of al-Raqqa, of the day for which you compute, which is the time of noon of the morrow — the seventh seasonal hour of the daytime becomes for this reason the first hour of the day that follows it; and so on to sunset, which is its sixth hour; and so on to the sixth hour of the night, which is its twelfth; and so on to sunrise of the morrow; and at noon of the morrow the day that follows also comes to an end.[237]

Ar. p. 109

When you know the number of the hours from the time of noon to the given hour of the daytime or of the night, multiply all that are hours of the daytime by the times of the hours of the daytime, which are taken with the degree of the sun, from its degrees, in the given clime, and multiply what are hours of the night by the times of the hours of the night, which are taken with the counterpart of the degree of the sun. If the hours are equal hours, multiply them all by 15. From what results, whichever kind it is, subtract the degrees and minutes set down under the degree of the sun in the tables of the equation of the days with their nights, which is set down in the

[235] Al-Battānī begins the day at noon, as the astronomers do (chapter 29), not at sunset (Nallino).

[236] 1 March 880 (Nallino). In chapter 28 al-Battānī found the farthest distance at Gemini 22;17 from observations of the year 1194. One degree in 66 years is 54 seconds 33 thirds a year (chapter 51; the modern value is about 50 seconds), and 66 Roman years of 365¼ days are 68 lunar years of 354 11/30 days.

[237] Al-Battānī's day begins at noon, whereas the civil day of the Muslims begins at sunset (Nallino, after chapter 29).

ascensions of the right sphere, in the sign in which the sun is. Divide the remainder by 15: the result is the equal, mean hours, converted from the irregular days into the mean days, after noon. If your computation is at the city of al-Raqqa, these are the hours of the computation. If it is at another city, take the amount between al-Raqqa and that city of the longitude set down in the tables of the longitudes of the cities, whatever it is, and divide it by 15: the hours and parts of an hour that result are the hours of the distance, so keep them. Then look: if the longitude of the city is greater than the longitude of al-Raqqa, which is 73;15, subtract the hours of the distance from those equal, mean hours after noon that have resulted at that city, for that city is then to the east of al-Raqqa; if the distance of the city is less, add the hours of the distance to those hours. What results after the addition or the subtraction is the equal hours after noon at al-Raqqa, which are the hours of the computation. Enter with them into the tables of the hours, take what stands opposite them of the motion of the sun, the moon and the stars, and add it to their mean positions found for the time of noon of the day for which you compute.[238]

If the given hours are before noon of the day for which you compute, take one day from the days that have passed of the month up to the day for which you compute; then take the hours from the time of noon of the day before to the given hour, and proceed with them as you proceeded at first.

Chapter 35. On setting up the ascendant and the twelve houses from the hours, and on knowing the hours from the ascendant

Ar. p. 109
Ar. p. 110

Al-Battānī said: If you wish to know the ascendant and the rest of the twelve houses from the hours that have passed of the daytime or of the night — although this has been mentioned before in this book, briefly, in the chapter on knowing the hours from the altitude — look: if the time is daytime, take the hours from sunrise to the given hour, and if the time is night, take them from sunset. If they are equal hours, multiply them by 15, whichever of the two times they belong to, I mean the night or the daytime. If they are seasonal hours and are hours of the daytime, multiply them by the times of the hours of the daytime, and if they are hours of the night, multiply them by the times of the hours of the night. Add the times that result from the multiplication of the hours of the daytime to the times of the ascensions set down under the degree of the sun in the given clime, and add what results from the multiplication of the hours of the night to the times of the ascensions set down under the degree opposite the degree of the sun in the clime. If either of them comes to more than a circle, cast off a circle from it. With what results after that, or before it if it was less than a circle, find the ascendant and the middle of the sky in the way set out at the beginning of the book: carry the number that you have to the tables of the ascensions of the clime and take what stands opposite it of the degrees of the signs, by the common [interpolation] in that way; the result is the rising degree of the sign in which you found the number. Likewise enter with that same number into the ascensions of the right sphere and take what stands opposite it of the degrees of the signs: the result is the degree of the middle of the sky. When you know the ascendant, the setting point is its counterpart, and the degree of the fourth is the counterpart of the cardine of the middle of the sky.[239]

If you wish to know the ascendant from the hours taken from the time of noon, take their count from the time of noon to the given hour. If they are equal hours, multiply them by 15; if they are

[238] The times of a seasonal hour are the degrees of the equator that rise in it. The equation of the days with their nights is that of chapter 29. Plato of Tivoli has 75;15 for the longitude of al-Raqqa (Nallino). Theon's tables give similar rules for the mean equal hours of Alexandria (Nallino).

[239] The chapter on knowing the hours from the altitude is chapter 16; the ascensions and the hours of the clime are those of chapter 13 (Nallino). Al-Battānī counts the right ascensions from the beginning of Capricorn (chapter 5), so that the ascension of the ascendant in the clime, counted from Aries, is the right ascension of the middle of the sky (Nallino). The cardines are the four principal points of the ecliptic: the ascendant, the setting point, the middle of the sky and the fourth, or lowest, point.

seasonal hours, multiply those of them that are hours of the daytime by the times of the hours of the daytime, and those that are hours of the night by the times of the hours of the night. To what results, whichever of the two times it is, add the ascension of the degree of the sun itself in the right sphere; with the result you find the ascendant and the middle of the sky in that way, if God wills.

Ar. p. 111

If you wish to set up the rest of the twelve houses, take the times of the hours of the degree of the ascendant in that clime, double them, and add them to the ascensions by which you found the ascendant and the middle of the sky, which are the times of the ascensions of the degree of the ascendant in the clime. Look up the result in the ascensions of the right sphere and take what stands opposite it of the degrees of the signs: the result is the beginning of the eleventh house, in the sign in which the number falls. Then add the doubled times of the ascensions of the degree of the ascendant again to these times by which you found the beginning of the eleventh house, and take what stands opposite the result of the degrees of the signs in the ascensions of the right sphere: the result is the beginning of the twelfth house, in the sign in which the number falls. Then add those same doubled times again to the number by which you found the beginning of the twelfth house, and take what stands opposite it in the ascensions of the right sphere: it agrees with the degree of the ascendant exactly. Then subtract the doubled times from 60: the remainder is the rest of the doubled times, so keep it. Add it to the number by which you found the degree of the ascendant in the right sphere, which is the one that I told you agrees with the degree of the ascendant, and take what stands opposite the result of the degrees of the signs, again in the ascensions of the right sphere: the result is the beginning of the second house. Then add the rest of the doubled times again to the number by which you found the beginning of the second house, and take what stands opposite the sum of the degrees of the signs in the ascensions of the right sphere: the result is the beginning of the third house. Likewise, if you added the rest of the times to this number by which you found the beginning of the third house, it would agree with the degree of the fourth. When you know the beginnings of these houses, the beginning of the fifth is the counterpart of the beginning of the eleventh, the beginning of the sixth the counterpart of the beginning of the twelfth, the beginning of the eighth the counterpart of the beginning of the second house, and the beginning of the ninth the counterpart of the beginning of the third. The meaning of «counterpart» is the degree opposite it on a diameter of the sphere, which stands 180 degrees from it. When you have done this, you have computed the beginnings of the twelve houses in degrees of the signs.[240]

As for knowing the hours from the ascendant: look at the given ascendant. If it is between the degree of the sun and its counterpart, in the order of the signs, the time is daytime; if it is between the degree of the counterpart of the sun and the degree of the sun, the time is night. If the time is daytime, subtract the ascension of the degree of the sun from the ascension of the degree of the ascendant in the clime: the remainder is what has turned of the sphere from sunrise to the rising of that degree. If the time is night, subtract the times of the ascension of the counterpart of the degree of the sun from the times of the ascension of the degree of the ascendant: the remainder is what has turned of the sphere from the setting of the sun to the rising of that degree. If the time is daytime, divide what has turned of the sphere by the times of the hours of the daytime: what comes out is hours, and what remains is a fraction of an hour. If the time is night, divide what has turned of the sphere by the times of the hours of the night: the result is what has passed of the night, in seasonal hours. If you divide it by 15, what comes out is equal hours.

[240] The houses are divided as al-Qabīṣī (Alcabitius) and Ibn Ezra teach: the half arc of the day of the degree of the ascendant, which is six of its seasonal hours of the daytime, and its half arc of the night are each divided into three equal parts, and circles through the poles of the equator mark the beginnings of the houses (Nallino). The «doubled times» are the times of two seasonal hours of the daytime of the ascendant; what they fall short of 60 is the times of two seasonal hours of its night, since the hours of the day and of the night of a degree together make 30 times. Nallino would add, among the counterparts, «the beginning of the seventh is the counterpart of the ascendant».

Chapter 36. On knowing the true position of the moon on the ecliptic

Ar. p. 111
Ar. p. 112

Al-Battānī said: If you wish to know the true position of the moon, in which it is seen on the ecliptic, at any time you wish, find the mean position of the moon and its anomaly for the day that you want and the hour sought, in the way that I showed you, from the four entries and the hours of the computation, and find also the mean position of the sun for that time. Then subtract the mean position of the sun from the mean position of the moon and double the remainder: the result is the doubled distance; if it is more than a circle, cast off a circle from it. Enter with the remainder in the two columns of numbers of the tables of the equation of the moon, and take what stands opposite it in the third column, and also the minutes that stand opposite it in the fourth column; keep each of the two apart, under its own name. That is: what results from the third column is the equation of the anomaly, so write it down under the anomaly; what results from the fourth column is the proportional parts of the difference, so write them down apart. Then look: if the doubled distance with which you found the equation is less than 180 degrees, add what you obtained of the equation of the anomaly to the anomaly, and if it is more than 180 degrees, subtract it from the anomaly. What the anomaly of the moon comes to after the addition or the subtraction is the corrected anomaly. Look for the same number in the columns of numbers of the tables of the equation of the moon again, take what stands opposite it in the fifth column, headed «nearest distance», and write it down under the minutes of the fourth column. Then take also what stands opposite that corrected anomaly in the second column, headed «single equation»: what results is its single equation, so write it down apart. Then find what part of 60 the minutes of the fourth column are, and name it by its ratio, whether a half, a quarter or a third, or less or more than that, and take as much of what you wrote down from the fifth column; always add the result to the single equation that you wrote down, and the result is the compound equation. Add this compound equation to the mean position of the moon if its corrected anomaly exceeds 180 degrees, even by a minute, and subtract it from it if it is less than 180 degrees. What the mean position of the moon comes to after the addition to it or the subtraction from it is the true position of the moon, in which it is seen on the ecliptic. Cast it from the beginning of Aries in the way given before, and you come to the degree and the minute of the sign in which it is, if God wills.[241]

Then look: if the corrected anomaly of the moon is less than 180, the moon is increasing in its course, and if it is more, it is decreasing in it. When it is from 0 to 95, its course is less than the mean course; when it is from 95 to 180, its course is more than the mean course; likewise from 180 to 265 its course is more than its mean course, and from 265 to the end of the circle less than the mean course. So too with the sun, in the same way.[242]

[241] The rules are Ptolemy's (*Almagest* V 8). The translation follows Nallino's emendanda (Part II, p. XXXI) in reading «حدَته», «apart», at p. 112, line 4. The four entries are those of chapter 33, the hours of the computation those of chapter 34. The columns are counted without the columns of numbers (Nallino). The third column holds the arc between the true and the mean farthest distance of the epicycle, the second the single equation, the fifth the increase of the equation at the nearest distance of the eccentric, and the fourth the sixtieths of that increase that apply at a given doubled distance (chapter 30).

[242] The true motion equals the mean motion where the moon is on a line from the earth that touches the epicycle, at the anomaly of 90 degrees and the greatest equation, here 5 degrees: hence 95 and 265. For the sun, whose greatest equation is about 2 degrees, the numbers are 92 and 268; and at the quadratures, where the greatest equation of the moon reaches 7;40, they are 97;40 and 262;20 (Schiaparelli, in Nallino's commentary).

Chapter 37. On knowing the position of the northern node, which is called the head of the jawzahar[243]

Ar. p. 113

Al-Battānī said: If you wish to know the position of the northern node, which is called the head, find its mean position for the time sought in the way given for finding the mean positions, and always subtract the result from 360 degrees: the remainder is the position of the northern node on the ecliptic. Cast it from the beginning of Aries in the usual way. As for the position of the southern node, which is called the tail, it lies on the diameter of its sphere: it is the degree opposite the degree of the head, degree for degree, and does not depart from it.[244]

Chapter 38. On knowing the latitude of the moon from the belt of the signs, and its directions

Ar. p. 113
Ar. p. 114

Al-Battānī said: If you wish to know the latitude of the moon, which is its distance from the belt of the signs, subtract the computed position of the head from the computed true position of the moon: the remainder is the argument of the latitude. Or, if you wish, add to the true position of the moon the mean position of the head; if the result is more than a circle, cast off a circle from it, and what results, after that or before it, is the argument of the latitude; the meaning is the same in the two ways. When you know the argument of the latitude, whichever of the two ways it was found, enter with it in the two columns of numbers of the tables of the equation of the moon and take what stands opposite it in the sixth column, headed «latitude of the moon»: the result is its latitude at that time. If you wish to know it by computation, take the sine of the argument of the latitude, multiply it by 5 parts 13 minutes, which are the sine of the whole latitude, and divide the product by the radius; find the arc of the quotient, and the arc that results is the latitude of the moon. When you know the latitude of the moon, whichever of the two ways it was found, look: if the argument of the latitude is from 0 to 180, the latitude is on the northern side of the ecliptic, and if it is from 180 to 360, the latitude is on the southern side.[245]

If you wish to know whether it is ascending or descending on its side, look: if the argument of the latitude is from 0 to 90, the moon is increasing in latitude and ascending in the north; if it is from 90 to 180, it is decreasing in latitude and descending from the north; from 180 to 270 it is increasing in latitude and descending in the south; and from 270 to 360 it is decreasing in latitude and ascending from the south. In short, when the moon leaves the head it is northern until it reaches the tail, and when it passes the tail it is southern until it reaches the head, because from the node of the head its passage is towards the north and from the node of the tail its passage is towards the south, if God wills.

Chapter 39. On knowing the parallax that occurs in the moon in longitude and latitude, and the cause from which it occurs, and on knowing it by computation and by the table

Ar. p. 114
Ar. p. 115

Al-Battānī said: The parallax of the moon is the amount by which the position in which it is seen by measurement differs from the position in which it really is, which is given by computation. For the size of the earth relative to the sphere of the moon is greater than relative to the spheres of the other stars, because the moon is near it, and [it grows less] until the ecliptic is reached,

[243] *Jawzahar*, from the Persian *gawzahr*, means the orbit of the moon, its nodes, and above all its ascending node (Nallino).

[244] The nodes move backwards, against the order of the signs, so the motion taken from the tables is subtracted from 360 (Nallino).

[245] The mean position of the head is the motion taken from the tables, before it is subtracted from 360 (chapter 37). The columns are counted without the columns of numbers (Nallino). 5;13 parts are the sine of 5 degrees, the greatest latitude of the moon (5;13,46 in al-Battānī's table of sines; Nallino); Plato of Tivoli has 5;30. In modern terms the rule is $\sin \beta = \sin 5^\circ \cdot \sin u$, with u the argument of the latitude.

relative to which the size of the earth is like a point. Since the centre of the earth is the centre of the ecliptic, which is the place of true sight, the sight differs [only] by the difference between the centre of the earth and its surface, which is the place from which the eyes see, and the amount of that is the radius of the earth. For this reason the parallax is greater in the moon than in the others and more evident to the senses. It occurs, and varies as it occurs, from two different causes: one is the variation of the distance of the moon from the earth, and the second the variation of its distance from the point of the zenith in the regions of the sphere, on the circle of altitude, which passes through the pole of the horizon, that is, the zenith, and through the moon and the horizon. When the place where this circle cuts [the ecliptic] is half way between the setting degree of the ecliptic and [the ascendant], at a distance of 90 from the ascendant, which is half the semicircle, half of the 180, and the amount of a right angle of the four angles of the sphere, the parallax then falls in latitude alone, not in longitude. This cannot happen on the meridian line except at two points of the ecliptic, the two solstitial points, I mean the beginning of Cancer and the beginning of Capricorn. For when either of them is on the meridian line, one of the two equinoctial points, I mean the beginning of Aries and the beginning of Libra, is on the eastern horizon and the other on the western horizon, everywhere on the earth, and so each of the four angles is a right angle; the amount of a right angle is 90 parts.[246]

As for the other parts of the sphere, when they are on the meridian line their distances from the horizon differ, being more or less than 90, and the angles differ, growing smaller or larger. When one of the parts of the ecliptic between the beginning of Cancer and the end of Sagittarius is on the meridian line, the place half way between the rising and the setting degree of the ecliptic appears in all the climes inclined from the meridian line towards the west; when one of them there is between the beginning of Capricorn and the end of Gemini, the place half way between the ascendant and the setting point inclines towards the east. In these two inclinations the parallax on the meridian line falls in longitude and latitude together. So too in the other regions of the sphere, when the distance of the degree in question from the ascendant is more or less than 90, since the angle is then less than a right angle.[247]

The ratio of the parallax in latitude to the parallax in longitude is as the ratio of the sine of the angle to the sine of what remains of it to a right angle, and the squares of the two parallaxes added together are equal to the square of the parallax between the point of the zenith and the moon on the circle of altitude. The inclination of the parallax in latitude is always towards the side of the degree that this circle cuts, when it is the circle of the middle of the sky, from the point of the zenith; and the inclination of the parallax in longitude is towards the side of the horizon to which the degree of the moon inclines, I mean that the moon is inclined, being nearer, towards that horizon, the eastern or the western, rather than towards the other.[248]

Ar. p. 116

What compels us most of all to the knowledge of this anomaly is the cause of the solar eclipses, for they cannot be grasped without grasping the amount of this anomaly at all places of the horizon. In the lunar eclipses we have no need of it, since the moon is not the cause of its own eclipse, as it is the cause of the eclipse of the sun: the cause of its eclipse is something else. This anomaly is also perceptible in Venus and Mercury, but more in Mercury, because it is nearer the moon, above all when Mercury is at its nearest distance, for its parallax is then like the parallax of the moon at its farthest distance. In the sun it is not perceptible as it is in the other three mentioned; it is, as Ptolemy set it down, in the ratio of one to the 1210 that Ptolemy made the distance of

[246] The text has «where the point of this circle» and, before it, «until it passes» for «which passes»; the translation follows the readings that Nallino proposes.

[247] The translation reads «appears» (يظهر) with Nallino for «rises» (يطلع); «all the climes» means our climes, north of the tropic (Nallino).

[248] With A the angle between the ecliptic and the circle of altitude through the moon and p the parallax in altitude, the parallax in latitude is p sin A and that in longitude p cos A (Nallino, after *Almagest* V 19). The parallax in latitude falls on the side to which the arc from the zenith through the moon points when it is continued beyond the ecliptic; the «middle of the sky» here is the zenith (Schiaparelli, in Nallino's commentary).

the sun from the centre of the earth, without distinction. We find the visible position of the sun agreeing with its true position, because the parallax of the sun entered into the computation of the sun at the time of the observation, since the limit of the ecliptic and its distance from the equator were known only by observation of the sun.[249,250]

It appeared before that the point of the farthest distance of the moon's eccentric sphere is 60 parts from the centre of the earth. If the radius of the earth is one part, the distance of the moon from the surface of the earth is then 59 parts, and in this measure the 5¼ parts that are the radius of the epicycle are about 5⅙ parts and the whole diameter of the epicycle 10⅓ parts. So when the centre of the epicycle is at the point of the farthest distance of the eccentric sphere, which happens at the times of the mean conjunctions and oppositions, and the moon is at the point of the farthest distance of the epicycle, its farthest distance from the earth is 64;10, and this is the first limit; when it is at the bottom of the epicycle, its distance from the earth is 53;50, and this is the second limit. When the centre of the epicycle is at the point of the nearest distance, whose distance from the centre of the earth was shown to be 39;22, which is 38;43 in that measure — this happens only at the two quarters of the month on either side of the full moon — then, if the moon is at the top of its epicycle, its distance from the earth is 43;53, and this is the third limit; and if it is at its nearest point on the epicycle, its distance from the earth is 33;33, and this is the fourth limit. Between these four limits there are limits of differing distances.[251]

Ar. p. 117

If you wish to know the distance of the moon from the earth, take the corrected anomaly of the moon: if it is less than 180, work with it, and if it is more than 180, subtract it from 360 and work with the remainder. The way to work with it is this. Look: if the number with which I told you to work is less than 90, take its sine and the sine of what remains of it to complete 90; multiply each of the two sines by 5;15, which is the radius of the epicycle, divide what results from each of them by the radius, and keep the results. Add what results from the sine of the complement of the number to 60, multiply the sum by itself, add to it what results from the sine of the number multiplied by itself, and take the root of the total. If the number with which I told you to work is more than 90, cast off 90 from it; find the sine of the remainder and the sine of what remains to complete the number to 90, multiply each of the two sines by 5;15 and divide by the radius. Subtract what results for the sine of the number from 60, multiply the remainder by itself, add to the product what results for the sine of the complement of the number multiplied by itself, and take the root of the total. What results from either of the two roots is the hypotenuse of the moon, I mean its distance from the centre of the earth at the times of the mean conjunction and opposition. Subtract a minute from each degree of this distance: the remainder is the distance of the moon from the earth.[252]

Ar. p. 118

If the moon is between the conjunction and the opposition, on either side, take what results from multiplying the minutes of the fourth column of the tables of the equation of the moon into the fifth column of them, which is what I told you to add to the single equation of the moon at the time of the computation, and always add it to the 5 parts 1 minute, which are the whole single equation. Find the sine of the sum: the result is the radius of the displaced epicycle. Use it in place of the 5¼ parts in that same way: the result is the hypotenuse of the moon corrected for

[249] «Compels»: so Nallino's translation; the printed word, «يقطم», is obscure. Ptolemy (*Almagest* IX 1) holds the parallaxes of the five stars imperceptible. Al-Battānī, like al-Farghānī, follows those who make the spheres touch, so that the nearest distance of Mercury is the farthest distance of the moon (chapter 50); hence their parallaxes there are equal (Nallino).

[250] The ratio of 1 to 1210 makes the greatest parallax of the sun 2′ 50½″, about 3 minutes, the value of Ptolemy, Theon and the Arabs (Nallino).

[251] These are Ptolemy's four limits (*Almagest* V 13 and 17).

[252] «Hypotenuse» renders *quṭr*, literally «diameter»: the line from the centre of the earth to the moon. In modern terms the distance is $\sqrt{((60 + r \cos a)^2 + (r \sin a)^2)}$, with r = 5;15 and a the anomaly. Taking a minute from each degree reduces the distance to the measure of the limits above, in which the 60 parts of the eccentric are 59; Ptolemy has no such rules (Schiaparelli, in Nallino's commentary).

the displacement of the epicycle, so keep it. Then take the doubled distance between the sun and the moon by their mean course: if it is from 0 to 180, work with it, and if it is from 180 to 360, subtract it from 360 and work with the remainder. The way to work with it is this. Look: if the number with which you work is less than 90, subtract it from 90, and if it is more than 90, cast off 90 from it; find the sine of whichever of these you have: that is the first sine, so keep it under this name. Then subtract the number whose sine you found from 90 and find the sine of the remainder: that is the second sine. Then take the radius of the eccentric sphere, which has been shown to be 49;41, and multiply it by itself: the product is 2468 degrees 26 minutes. [Then multiply] the second sine by 10;19, which is the amount between the centres, divide the product by the radius, multiply the quotient by itself, and subtract it from the 2468 degrees 26 minutes; take the root of the remainder: that is the corrected side, so keep it. Then multiply the first sine by 10 parts 19 minutes as well, divide the product by the radius and keep the result. If the number with which you worked is less than 90, add what you kept to the corrected side, and if it is more, subtract what you kept from the corrected side. Always subtract from 60 what the corrected side comes to after the addition or the subtraction: the remainder is the share of twice the distance between the centres. Subtract it from the hypotenuse of the moon corrected for the displacement of the epicycle, take a minute for each degree of the remainder, and what remains is the distance of the moon from the earth.[253,254]

By that first procedure in this chapter the distance of the sun from the earth is known, if you use the 2 parts 4 minutes and a half and a quarter that are between the centres for the sun in place of the 5¼ parts that are the radius of the epicycle for the moon. Multiply the distance of the sun from the earth that results by 18;46,24: the result is the distance of the sun from the earth according to its position, known by the computation given before in the pine-shaped figure.[255]

If you wish to know the parallax of the moon on the circle of altitude, take the altitude of the moon at the time that you want and find what the altitude falls short of 90, which is the distance of the moon from the point of the zenith. Find the sine of each of them and multiply it by one minute, so that each degree of the sine becomes a minute and returns to the one part that is the amount of the radius of the earth. Subtract what results of minutes of the sine of the altitude from the distance of the moon from the earth: the remainder is the corrected distance, so keep it. Then multiply the minutes of the sine of the distance of the moon from the point of the zenith by 60 and divide the product by the corrected distance that you kept: the result is minutes; find their arc, and the arc that results is the parallax of the moon on the circle of altitude that passes through the zenith and the moon. Ptolemy set down the amount of this parallax in the tables for the four limits mentioned for the moon, and for the sun for one distance.[256]

Ar. p. 119

If you wish to know the parallax of the moon on the circle of altitude by those tables, which we have set down in this book of ours in that way, so as to know by it the position of the moon in which it is seen on the ecliptic in longitude and latitude, from the arcs and angles that arise

[253] Words are missing after «the radius of the displaced epicycle» (Nallino). Nallino's restoration: «[divide 5;15 by it and multiply the result by 60: the result is the distance of the centre of the epicycle from the earth;] use it in place of [the farthest distance of that centre at the syzygies]», so that the hypotenuse is found as in the paragraph before. Schiaparelli reads what follows as a second way, without the tables: the hypotenuse found with the epicycle at the farthest distance of the eccentric, less the share of twice the distance between the centres, which is nothing at the farthest distance and twice that distance at the nearest.

[254] The words in brackets are supplied by Nallino; only their last letter can be read in the codex. The corrected side is $\sqrt{(49;41^2 - (10;19 \cdot \sin 2\eta)^2)}$, with 2η the doubled distance; together with $10;19 \cdot \cos 2\eta$ it gives the distance of the centre of the epicycle from the earth (Schiaparelli, after *Almagest* V 13).

[255] The pine-shaped figure is that of chapter 30. The factor turns parts of which the mean distance of the sun is 60 into radii of the earth. Nallino reads 18;46,24 after Plato of Tivoli's 18;46,50; the codex has 38;46,24. With the mean distance of 1108 radii of the earth the factor would be 18;28; 18;47 belongs to 1127, half way between the mean and the farthest distance (Schiaparelli).

[256] The altitude here is that seen from the centre of the earth (Schiaparelli). In modern terms the rule is $\sin p = \sin z / (D - \cos z)$, with z the distance from the zenith and D the distance of the moon in radii of the earth; the exact rule has tan p for sin p. Ptolemy's tables are those of *Almagest* V 18.

from the intersection of the ecliptic and the circle of altitude, find the degree that falls in the middle of the sky and the degree that falls on the eastern horizon, I mean the rising degree of the ecliptic, at the time when the moon happens to be above the earth in the given clime. Then find the amount, of the degrees of the signs, between the rising degree and the degree that falls in the middle of the sky, and also between the degree in question, in which the moon is, and the rising degree. Then find the altitude of the degree that falls in the middle of the sky, as I shall describe, although this was given at the beginning of the book. Look at the declination of the degree in the middle of the sky: if it is northern, subtract it from the latitude of the clime, and if it is southern, add it to it; subtract what the latitude of the clime comes to after the addition or the subtraction from 90: the remainder is the altitude of the degree of the middle of the sky. If the declination of the degree of the middle of the sky is northern and you wish to subtract it from the latitude of the locality, but find the latitude of the locality less than that declination, take the difference between them and subtract it from 90: the remainder is the altitude of the degree of the middle of the sky above the northern horizon, and the computation is then reversed. When you know what I have described to you, multiply the sine of the distance of the degree in question from the ascendant by the radius, divide the product by the sine of the [arc] between the ascendant and the degree of the middle of the sky, multiply the quotient by the sine of the altitude of the degree of the middle of the sky, divide the product by the radius, and find the arc of the quotient: the arc that results is the altitude of the degree in question at that time, on whichever side of the horizon it is, I mean in the east or in the west. Keep it, and keep the sine by which you found it. Then subtract the altitude of the degree in question from 90: the remainder is the distance of the degree in question from the point of the zenith. Keep it: with it you know the amount of the parallax on the circle of altitude from these tables.[257]

Then look: if the distance of the degree in question from the ascendant is 90 degrees, the angle is a right angle, the parallax then falls in latitude only, not in longitude, and the parallax that results on the circle of altitude is the parallax in latitude. If the distance of the degree in question from the ascendant is less than 90, subtract it from 90 and work with the remainder; if it is more than 90, subtract 90 from it and work with the remainder. The way to work with it is to take the excess over 90 or the shortfall from it, find its sine and multiply it by the sine of the altitude of the degree in question at that hour, which is the sine that I told you to keep under its name; divide the product by the sine of the distance of the degree in question from the ascendant, multiply the quotient by the radius, divide the product by the sine of the distance of the degree in question from the point of the zenith, and find the arc of the quotient: the arc that results is the amount of the angle of longitude, out of the whole of one right angle. Subtract it from the 90 parts that are the amount of a right angle: the remainder is the amount of the angle of latitude. Keep all this, each on its side and under its name; unless the altitude is from the northern horizon, when the matter is reversed, and the arc that results for you from the table becomes the angle of latitude and its complement to 90 the angle of longitude. This cannot happen in the other localities, whose latitude is greater than the declination together with the latitude that the moon may have when it is northern.[258]

Ar. p. 120

Then enter with the distance of the degree in question, in which the moon is, from the point of the zenith, which I told you to keep, into the tables of the parallax of the moon on the circle of altitude, in the column of numbers that goes in steps of two parts, and take what stands opposite it in the four columns that follow the column of the sun headed «parallax of the sun», namely the third, fourth, fifth and sixth columns; write down what results from each of them on its side.

[257] The altitude of the degree of the middle of the sky is found as in chapter 15. In modern terms the rule is sin h = sin d · sin h_M / sin d_M, with d and d_M the distances of the degree in question and of the degree of the middle of the sky from the ascendant, and h_M the altitude of the latter.

[258] The angle of latitude is the angle between the ecliptic and the circle of altitude through the moon, and the angle of longitude its complement. In modern terms the rule is cos(angle of latitude) = tan h · |cot d|. Schiaparelli, in Nallino's commentary, holds the words on the northern horizon to be a reader's interpolation, and false.

Then take the corrected anomaly of the moon: if it is less than 180, take half of it, and if it is more than 180, subtract it from 360 and take half of the remainder. Enter with whichever of these two halves you have into the two columns of numbers of these tables and take the minutes that stand opposite it in the seventh and the eighth column, headed «epicycle». Multiply what results from the seventh column by the minutes that you took from the fourth column, and what results from the eighth column by the minutes that you wrote down from the sixth column, and divide what results from each of them by 60. Add the minutes that result from the seventh column to what you wrote down from the third column, and the minutes that result from the eighth column to what you wrote down from the fifth column. If you wish to work in another way, see what part of 60 the minutes of the seventh column are, take that part of what you wrote down from the fourth column, and add it to what you wrote down from the third column; then see what part of 60 the minutes that resulted from the eighth column are, take that part of what you wrote down from the sixth column, and add it to what you wrote down from the fifth column. The meaning is the same: whichever of these two you work with, you will be right. What the third column and the fifth column each come to after what you add to it is the amount of the parallax of the moon on the circle of altitude at the two limits of the farthest and the nearest distance of the epicycle; keep them, and find the excess between them. That is the parallax of the moon and the sun together.

Ar. p. 121

Then take the distance of the moon from the sun by their mean motions, either from the mean degree of the sun or from the degree opposite it, whichever is nearer to it, ahead or behind, so that the greatest distance is 90 parts. Enter with the result into the column of numbers of those tables again, and take the minutes that stand opposite it in the ninth column, headed «eccentric». Find what part of 60 the minutes are, and take that part of the excess between the corrected third and fifth columns that I told you to keep; always add the minutes that you obtain from that excess to the corrected third column that you kept. The result is the parallax of the sun and the moon together on the circle of altitude, according to the position of the moon and its distance from the earth; keep it. Then take what stands opposite the arc of the distance of the degree in question from the point of the zenith in the parallax of the sun, set down in the second column; always add to the minutes and seconds that result an eighth of them, because of the change that has come about in the distance of the sun from the earth, and keep the result. Then enter with the anomaly of the sun into the table of the computation and take what stands opposite it in the third column, of the minutes of the shares; see what part of 60 it is, and take that part of the 13 seconds by which the parallax of the sun varies between its farthest and its nearest distance. Add the result to what you kept: what the parallax of the sun comes to after these two operations is its parallax on the circle of altitude according to its position in distance from the earth. Subtract it from the parallax of the sun and the moon on the circle of altitude that you kept at the end of the work [before]: the remainder is the parallax of the moon on the circle of altitude, which appears in the moon at the true position of the sun; keep it, and work with it. Then take the angle of longitude, find its sine, multiply it by this parallax of the moon on the circle of altitude that I have mentioned, and divide the product by 60: the result is the parallax of the degree of the moon in longitude; keep it. Then take the sine of the angle of latitude, multiply it by the parallax of the moon on the circle of altitude as well, and divide the product by 60: the result is the parallax of the moon in latitude.[259]

Ar. p. 122

If you wish to know it in another way, see what part of the 60 that are the radius the sine of the angle of longitude and the sine of the angle of latitude each are, and take that part of the parallax of the moon on the circle of altitude: what results for the angle of longitude is the parallax in longitude, and what results for the angle of latitude is the parallax in latitude. Whichever of the

[259] «An eighth»: Plato of Tivoli has «an eighteenth», which is right. Al-Battānī's farthest distance of the sun, 1146 radii of the earth, is 64 less than Ptolemy's 1210, so the parallaxes of the sun taken from Ptolemy must be increased by about an eighteenth; with al-Battānī's distances of 1146 and 1070 radii the parallax of the sun at the horizon is 3′ 0″ and 3′ 13″, which differ by the 13 seconds of the text (Schiaparelli, in Nallino's commentary).

two ways you work with, the meaning is the same in the two amounts. When you know this, add the parallax in longitude to the true position of the moon on the ecliptic if the distance of the degree in which the moon is from the ascendant is less than 90, because the moon is then nearer to the eastern horizon; and if the distance of the degree in which the moon is from the ascendant is more than 90, subtract the parallax in longitude from the true position of the moon, because the moon is then nearer to the western horizon. The position of the moon after the addition or the subtraction is the position of the moon in which it is seen on the ecliptic in the course of longitude. As for the parallax of the moon in latitude, look: if the position of the moon is to the south of the point of the zenith when the degree of the moon comes to the middle of the sky, the parallax is then towards the south; and if the position of the moon on the circle of the middle of the sky is to the north of the point of the zenith, the parallax in latitude is then towards the north. It is always southern in the localities whose latitude is greater than the declination of the sun together with the northern latitude that the moon may have, approximately. If the true latitude of the moon and the parallax of the moon in latitude are on one side, add them together; if they differ, subtract the smaller from the greater and find the side of the remainder. The result after the addition or the subtraction is the latitude of the moon in which it is seen by measurement.

If the degree of the moon in question is on one of the two horizons, it is known that its distance from the point of the zenith on the circle of altitude is then 90 parts. If you wish to know its angle on the eastern horizon, find the declination of the degree that then falls in the middle of the sky: if its declination is northern, subtract it from the latitude of the clime, and if it is southern, add it to it; what the latitude of the clime comes to after the addition or the subtraction is its corrected latitude, so keep it. Subtract it from 90, find the sine of the remainder, multiply it by the radius, and divide the product by the sine of the [arc] between the degree of the middle of the sky and the degree of the ascendant, which is then the degree in question, in which the moon is, if the degree in question is on the eastern horizon. Find the arc of the result: the arc that results is the amount of the angle of longitude; subtract it from 90, and the remainder is the amount of the angle of latitude. Each of them is [the angle] of the degree in question on the eastern horizon, by which I mean the ascendant. If the latitude of the clime is less than the declination of the degree of the middle of the sky, when the declination is northern, take the difference between them, find its sine, multiply it by the radius, divide the result by the sine of the [arc] between the ascendant and the middle of the sky, and find the arc of the result: the arc that results is the amount of the angle of latitude. We have explained this before, in the knowledge of the angles, when the declination is more than the latitude of the clime. If the degree in question is on the western horizon, find the angle of the degree opposite it, which is then the rising degree, in the way given by which the angle of a degree on the eastern horizon is known: the result is the angle of that degree on the western horizon.[260]

Ar. p. 123

If the degree in question is on the meridian line, its distance from the point of the zenith is then the amount by which the altitude of the degree in question in the middle of the sky falls short of 90, and its angle is found by the procedure that we have set out [in the first of these chapters]; its amount is the same everywhere on the earth. If you wish to know it in another way, take the distance of the degree in question from the beginning of Aries or the beginning of Libra, whichever is nearer, before it or behind it, so that it does not exceed 90. Find the sine of this distance and the sine of what remains to complete this distance to 90; then take the declination of the degree in question and find its sine and the sine of what remains to complete the declination of the degree in question to 90. Multiply the sine of the declination of the degree by the sine of the complement of the distance, divide the product by the sine of the complement of the declination of the degree, multiply the quotient by the radius, divide the product by the sine of the distance

[260]The rule for a declination greater than the latitude is not exact: it agrees with the rule before only when the ascendant is 90 degrees from the degree of the middle of the sky. Where it applies, at latitudes less than the greatest declination, it errs by less than a degree; Schiaparelli, in Nallino's commentary, calls it false. The rule before serves in this case too, with the altitude of the degree of the middle of the sky counted from the northern horizon.

of the degree, and find the arc of the result: the arc that results is the amount of the angle of longitude. Subtract it from 90: the remainder is the amount of the angle of latitude in the middle of the sky, which is also its angle at the horizon at the place of the line of equality. These angles mentioned are the amount of the azimuth of the degree in question on the circle of the horizon, if you take it from the azimuth of the rising or the setting degree towards the middle of the sky, according to the position of the degree in question; for the arc of the circle of the horizon between the azimuth of the rising of the ascendant and the azimuth of the degree in question is equal to the amount of the angle of latitude. Since the parallax that we have described is known truly in these ways only when the moon is on the belt of the signs, while, when it departs from the girdle of the ecliptic in latitude, the angles and arcs vary and change, what falls in the parallax on this account is mostly about 6 minutes; at the solar eclipses the most that can fall on this account is a minute and a half, at the extreme, and in places far from the equator.[261]

Ar. p. 124

If you wish to make this exact, so that no change falls on its account, take the distance from the point of the zenith of the degree in which the moon is, and the angle of latitude and the angle of longitude that result for that degree. Then find the true latitude of the moon, take its sine, and multiply it by the sine of the angle of latitude and by the sine of the angle of longitude; then divide each of the two by the radius. Find the arc of what results for the angle of latitude, and subtract the arc from the distance of the degree in which the moon is from the point of the zenith if the moon is on the side of the zenith from the ecliptic, and add it to it if the ecliptic is nearer to the zenith than the moon. Find the sine of what the arc of the distance of the degree in which the moon is from the point of the zenith comes to after the addition or the subtraction, multiply it by itself, add to the product what resulted for the angle of longitude by the division, multiplied by itself, take the root of the result and find its arc: the arc that results is the corrected arc of the distance of the moon from the point of the zenith; use it in place of the first arc of the distance of the degree of the moon from the point of the zenith. Then take also what resulted for the angle of longitude from that division and find its arc: the result is the difference of the angle. If the corrected arc is less than the first arc, subtract it from the angle of latitude and add it to the angle of longitude; if the corrected arc is more than the first, add it to the angle of latitude and subtract it from the angle [of longitude]. What results for each of the two after that is the corrected angle; use it in place of the two first angles.[262]

If you wish to know the amounts of the parallax of the moon by the tables that Theon, the astronomer of Alexandria, made, which we have set down in this book as Theon made them. Theon set down the parallax of the moon in longitude and latitude for seven climes, at intervals of half an hour in the longest day, on the assumption that the moon is at the beginnings of the signs, after taking the parallax of the sun from the parallax of the moon in the way set down in Ptolemy's book, according to the inclination used there; and made it known by the equal hours of the distance of the degree of the moon from the circle of noon. So the finding of the parallax by these tables varies near noon, which is the meridian line, by day and by night. These amounts are not like those that result from working with the angles and arcs, for various reasons that interfere in them, although they are easier to obtain than those.[263]

Ar. p. 125

[261] The words in brackets stand so in the codex for «at the beginning of this chapter» or «earlier in this chapter» (Nallino); Plato of Tivoli has «at the beginning of this chapter». In modern terms the second rule is cos(angle of latitude) = tan δ · cot λ, with δ the declination of the degree and λ its distance from the equinoctial point. Schiaparelli finds the sentence on the azimuth corrupt or interpolated: the arc of the horizon between the ascendant and the azimuth of the degree is not the angle of latitude.

[262] The words in brackets are supplied by Nallino. The corrected distance from the zenith is found as the hypotenuse of a small right triangle: Ptolemy (*Almagest* V 19) adds the squares of the arcs, al-Battānī those of their sines; the exact rule is cos z = cos a · cos b, and both ways change the parallax by no more than 3 or 4 seconds (Schiaparelli, in Nallino's commentary). For the difference of the angle, the result must also be multiplied by the radius and divided by the sine of the corrected distance from the zenith, words that Nallino suggests have fallen out.

[263] Theon's tables are computed with Ptolemy's inclination of 23;51, 16 minutes more than al-Battānī's; the greatest effect of the difference, at al-Raqqa, is about 16 seconds (Nallino's commentary).

The way to work with these tables is as I describe. Find the distance of the degree in which the moon is from the meridian line, by night or by day, so as to know how many equal hours the degree of the moon is from noon or from midnight towards the east or the west, on whichever side the moon is. This is known as I describe. Take the times of the ascensions of the right sphere that stand opposite the degree of the middle of the sky, and also the times of the ascensions of the right sphere that stand opposite the degree in which the moon is. Subtract the times of the ascensions of the degree of the middle of the sky from the times of the ascensions of the degree of the moon if the moon is on the eastern side of the meridian line, and subtract the times of the ascensions of the degree of the moon from the times of the ascensions of the degree of the middle of the sky if the moon is on the western side of the meridian line. Divide the result, whichever of the two it is, by 15: what comes out is the hours of the distance of the moon from the meridian line, in equal hours, on the side where the moon is. Then see whether the moon is above the earth or below it: if the degree of the moon is between the setting degree and the rising degree on the side of the middle of the sky, it is above the earth, and if otherwise, below the earth. When you know that the moon is above the earth, enter with the hours of the distance of the degree of the moon from the middle of the sky into the tables of the parallax for the given clime to which the latitude of your locality is nearest, and look for the same number in the column of the hours set down in the table of the sign in which the moon is, from the horizon. That is, if the moon is on the western side of the meridian line, you look in the hours after the meridian, and if it is on the eastern side, in the hours before the meridian; the hours that you have will be less than the hours set down at the ends of the tables for the signs, and they can be more only if the degree of the moon is below the earth. Then take what stands opposite those hours in the table of the sign in which the moon is and in the table of the sign that follows the sign of the moon, of the minutes of longitude and the minutes of latitude set down there, with interpolation. That is: if there is a fraction with the hours, see what part of an hour the fraction is and take that part of the difference between the complete hour and the hour one above it; add what results for the longitude to the longitude opposite the hour if this is the lesser, and subtract it from it if it is the greater, and do the same with what results for the latitude. Then look at the degrees that the moon has traversed in its sign and find what part they are of the 30 degrees of the sign; take that part of the difference between the minutes of longitude that you wrote down for the sign of the moon and for the sign that follows it, and add the result to the minutes of longitude of the sign of the moon if these are the lesser, or subtract it from them if they are the greater; do the same with the difference of the minutes of latitude. What the minutes of the sign of the moon in longitude and latitude come to after the addition or the subtraction are the minutes of the degree of the moon; keep them.[264]

Ar. p. 126

Then enter with the corrected anomaly of the moon at that time into the two columns of numbers of the tables of the computation, which go in steps of six parts, and take what stands opposite it in the fourth column. See what part of 60 the minutes that result are, take that part of the minutes of longitude and of the minutes of latitude, and add what results for the longitude to the longitude and what results for the latitude to the latitude: what the minutes of longitude and the minutes of latitude come to after that are the minutes corrected by the fourth column, so keep them. Then enter with the distance between the sun and the moon by their mean course, doubled, which is the doubled distance that we mentioned in the computation of the moon, into the two columns of numbers of the tables of the computation of the parallax as well, and take what stands opposite it in the fifth column. See what part of 60 the minutes that result are, and take that part of the minutes of longitude and latitude corrected by the fourth column; add what each of them comes to to itself, as you did at first, I mean add what results from what you took of the longitude to the longitude, and what results from what you took of the latitude to the latitude. What each of them comes to after that is the minutes corrected by the fourth and the fifth column, and that is the parallax of the moon in longitude and latitude according to its distance from the earth; keep

[264] «From the horizon» is obscure; Nallino translates «of the sign with which the moon is on the horizon».

it, and work with it. Then find the true latitude of the moon and its side, as we have set it out in the chapter on knowing the latitude of the moon, and find the side of the parallax in latitude from the mark in the line of the latitude. If the latitude of the moon and its parallax in latitude are on one side, add them together; if they differ, subtract the smaller from the greater and find the side of the remainder: the result after the addition or the subtraction is the latitude of the moon seen by measurement, on the side on which it results.[265]

As for the parallax in longitude, add it to the true position of the moon if the distance of the moon from the ascendant is less than 90, and subtract it from it if its distance from the ascendant is more than 90 degrees; what the true position of the moon in longitude and latitude comes to is the position in which the moon is seen on the ecliptic.

Ar. p. 127

It may happen that the moon, near the middle of the sky, by an hour or less, up to an hour and a fraction, is to the west of the middle of the sky by measurement while it inclines to the east in its distance from the ascendant, or is to the east of the middle of the sky by the same distance while it inclines to the west. Then examine the parallax in longitude alone, not the latitude, when you take it from these tables near the middle of the sky, on the side on which the parallax in longitude in the hour that follows the meridian is less than its parallax at the meridian, or in the second hour from the meridian less than in the first hour that follows the meridian, on either side, so that you know where the parallax of the moon in longitude should vanish and be nothing at all: that is where the distance of the degree of the moon from the ascendant is exactly 90 parts. When the matter falls out in this way, and the hours of the distance are on the side on which the minutes of longitude vanish, and near the middle of the sky, the way to work is to add together the minutes of longitude for the meridian and for the hour that follows it, or for that one and the hour that follows it, according to the fraction of the hour that you have. If what results is more than the first longitude, which stands opposite the complete hour, or less than it, find its excess over it or its shortfall from it: that is the parallax for the sign in which the moon is, or for the sign that follows it, whichever the matter happens to fall in as we have described, or for both together. Then take the difference between the longitude for the sign of the moon and for the sign that follows it, multiply it by the parts of the moon in the sign in which it is, and divide the product by 30; add the result to the minutes of the sign of the moon if these are the lesser, or subtract it from them if they are the greater. Correct the result by the fourth and the fifth tables of the computation in that way, and proceed with it in the same way in the addition to or the subtraction from the true position of the moon. It may happen that what results for the sign of the moon is opposite to that of the sign that follows it in its inclination to one of the two horizons. When this is so, add together what results for each of the two signs and take of it in proportion to the degrees that the moon has traversed in its sign, out of 30; if the result is more than the parallax of the sign of the moon, take its excess over it, and if it is less, take its shortfall; correct the excess or the shortfall that results by the fourth and the fifth column in that way, and proceed with it in that way. Then you will have found the parallax of the moon on its side in longitude and latitude, and this is nearer to the truth when the moon is on the belt of the signs, if God wills.[266]

[265] The doubled distance is that of chapter 36; the chapter on the latitude of the moon is chapter 38.

[266] The point of the ecliptic 90 degrees from the ascendant is on the meridian only when the beginning of Cancer or of Capricorn culminates; otherwise it lies east or west of the meridian, at a distance that may exceed an hour, and there the parallax in longitude vanishes and changes its side. The parallaxes found from the tables may be wrong by 4 or 5 minutes when the moon is off the ecliptic (Schiaparelli, in Nallino's commentary).

Chapter 40. On knowing the distance of the moon from the earth from its parallax on the circle of altitude, when that is known

Ar. p. 127

Al-Battānī said: If you wish to know the distance of the moon from the earth from its parallax on the circle of altitude, whether this is found by observation or from the tables: add to the corrected parallax of the moon in longitude and latitude, when you have taken it from the tables of Theon, one part in eighteen of it. Multiply what each of the two parallaxes comes to by itself, add them together, and take the root of the sum: that is the parallax of the moon with the sun on the circle of altitude. If you have taken it from the tables of the parallax on the circle of altitude, do not subtract the parallax of the sun from it, so that it is its parallax with the sun on the circle of altitude.[267]

Ar. p. 128

If you wish to find it by observation, you find it as I describe. Observe the altitude of the moon when it is 90 parts from the ascendant, with a large quadrant or with the two long alidades whose making is described in Ptolemy's book, so that the taking of the altitude is more correct and precise. When you know its altitude at that place, keep it. Then find the true position of the moon on the ecliptic in longitude and latitude, and so know its distance from the equator in the way that we have explained at the beginning of the book. If its distance from the equator is to the north, subtract it from the latitude of the locality, taken by observation, and if it is to the south, add it to it; subtract what the latitude of the locality comes to after the addition or the subtraction from 90: the remainder is what its altitude in the middle of the sky must be. Then from its altitude in the middle of the sky find what its altitude must be when it is 90 parts from the ascendant, in the way that we have shown for the altitude of the degree of the moon, and compare this with the altitude of the moon that you found by observation when it was 90 parts from the ascendant. Whatever the altitude taken by observation falls short of the altitude known by computation is the parallax of the moon with the sun on the circle of altitude. It is greater the farther the moon is from the zenith, that is, when it is in the southern signs, and above all at the beginning of Capricorn: for, besides what we have described, if its latitude is to the south, its distance from the equator is the whole declination together with the latitude of the moon; and likewise if its latitude is to the north, its distance from the equator is the amount of the whole declination less the latitude of the moon, since the declination and the latitude then, and only then, come out on one arc. At the beginning of Cancer, which is like the beginning of Capricorn in this respect, the parallax is small, because the moon is near the zenith.[268]

When you know the parallax of the moon with the sun on the circle of altitude, take its visible distance from the point of the zenith, which is what remains to complete the altitude of the moon to 90, and find its sine and the sine of the visible altitude of the moon as well. Then find the sine of the parallax on the circle of altitude: if it is more than a degree, make it all minutes and keep it; if it is less than a degree, it is minutes. Then multiply the sine of the distance by the radius and divide the product by the sine of the parallax of the moon that I have set out for you: the result is parts. Add to them one minute for each degree of the sine of the altitude: what the parts come to after that is the distance of the moon from the earth in the measure in which the radius of the earth is one part.[269]

[267] Nallino reads one part in eighteen with Plato of Tivoli; the codex has one in thirty-eight. Theon's tables give the parallax of the moon less that of the sun, and Theon adds a twentieth for it; 3 minutes, the parallax of the sun, are an eighteenth of 54 minutes, about the parallax of the moon at the first limit (53′ 34″), so that the eighteenth is right (Nallino).

[268] The two long alidades are Ptolemy's parallactic instrument, the long alidade of chapter 4 (*Almagest* V 12), also described in chapter 57 (Nallino). At 90 parts from the ascendant the circle of latitude through the moon is the circle of altitude, so that the whole parallax falls in latitude; Tycho Brahe sometimes observed the moon there for this reason, while Ptolemy (*Almagest* V 13) observed it on the meridian near the beginning of Capricorn (Nallino). The altitude at 90 parts from the ascendant is found as in chapter 39.

[269] Two rules run together here in the codex and in Plato of Tivoli. Nallino restores the missing words after «the result»: «[is the distance of the moon from the earth. If you wish, take the true distance of the moon from the zenith,

Chapter 41. On the seeing of the crescent at the beginnings and the ends of the months, the azimuth of its place in which it is seen at its altitude and its depression, and the shape of its figure according to the light in it, and the levelness of its horns and their inclination to the belt of the signs

Ar. p. 129

Al-Battānī said: The knowledge of the seeing of the crescent at the beginnings and the ends of the months is among the most useful of the things whose knowledge has been given, since the era of the Arabs and the beginnings of their months depend on the seeing of the crescents. Knowing it truly has some difficulty, from various sides: among them the nearness of the moon to the sun and its distance from it, its distance from the earth and its nearness to it, the variation of the latitude of the moon on the northern and the southern side, then the parallax that occurs in the longitude and the latitude of the moon in every locality, the shortness and length of the risings and the settings of the signs in the climes, and the abundance and scarcity of the light in it. For this reason some people of our time who sought the knowledge of it fell into error in knowing the seeing of the crescents, and fell short of reaching the truth of things. They even imagined that the distance of a star from the equator and the latitude of the star come out together on one arc; they worked on the assumption that the parallax of the moon does not come from its variation on the circle of altitude, but arises from its distance from the middle of the sky in degrees of the signs; and they multiplied arcs into sines, with principles that they had adopted before, which measurement does not require and demonstration does not confirm.[270]

As for the ancients, they were not compelled to know this, because the era with them, with which they worked, is the years of the sun, and the beginnings of the lunar months were known to them from the times of the conjunctions, whose truth computation shows. For this reason they set aside any mention of it, despite how much arises in it of what we have mentioned, except in general terms: they mentioned that the crescent cannot be seen in less than a day and a night. When the causes of the seeing are examined, this statement is found to be the principle on which one works. For the amount of the seeing found by observation, although it comes close to the amount that appears in this way mentioned, is known, when the matter is examined, not to be graspable with the most exact truth: what is grasped of it is grasped only approximately.

Ar. p. 130

Since the knowledge of the seeing of the crescent found by observation is right only from the amounts of the arcs of the equator that lie between the sun and the moon at sunrise or at sunset — when these arcs are observed in one of the climes, the amount is known in one clime, and when it is known in one clime it is known in all the climes — that on which people's opinions agree for the amount of the arc of seeing is, as we found by observation, about 12 parts of the times of the equator. It is clear that the course of the moon, when it parts from the sun, in a day and a night, when the mean course of the sun in a day and a night is taken from it, is 12 parts 11 minutes; that is the amount of the distance that arises between the sun and the moon in parts of the signs, and this agrees approximately with what is taken by observation when these parts are of the equator. It is evident that the amount of these times mentioned is about four fifths of an hour, and we find that the moon gains on the sun in this amount of an equal hour about two fifths of a part. So when the sun sets with about 11 and a half and a quarter times of the equator between it and the moon, the moon does not set until the 12 parts 11 minutes are complete. On this reckoning, therefore, the mean arc of seeing is 11 parts and a half and a quarter of a part

which is what the true altitude of the moon falls short of 90, find its sine and the sine of the true altitude of the moon, multiply the sine of the distance by the radius and divide the product by the sine of the parallax of the moon that I have set out for you; what results] is parts». With the visible distance from the zenith ζ and the parallax p, the distance of the moon is sin ζ / sin p radii of the earth; with the true distance from the zenith z, sin z / sin p is the distance from the observer, and the minute for each degree of the sine of the altitude adds the radius of the earth times cos z (Schiaparelli, in Nallino's commentary).

[270] The Muslim months begin with the first sighting of the crescent after the conjunction, attested by witnesses; computation was admitted only by a few jurists of the Shāfiʿite school (Nallino). Nallino supposes that those who erred were jurists or the timekeepers of the mosques.

of the times of the equator, which are the risings and the settings of the signs in the localities. What is lit of the circle of the moon when the distance of the moon from the sun is the amount of these parts of the ecliptic [is] about four fifths of a part, if the whole circle of the moon is 12 parts. The moon may be farther from the sun than this amount, or less, at the times of seeing, so that the light in it is more or less according to the amounts of the distance, and it is seen at less than this arc or at more; moreover, it is near the earth or far from it at those times because of its position on the epicycle, which adds to these amounts or takes from them. For this reason the crescent cannot be seen at one and the same arc: it is seen at different arcs.[271]

Ar. p. 131

If you wish to know whether the crescent will be seen or not, in this way, compute the sun and the moon for the time of sunset of the second day from the conjunction, which is the 29th day of the Arab month, and find their true positions on the ecliptic in the locality that you want; find also the true latitude of the moon and its side. Then find the amount of the parallax of the moon at the time of sunset in longitude and latitude in those ways, so that the visible position of the moon on the ecliptic in longitude and latitude and the side of the latitude come out right for you. When you know that, find its visible distance from the equator and the degree that culminates with it, and with them find half the arc of the day of the moon, which is half its stay above the earth, in the way explained at the beginning of the book, in the chapter on knowing the distance of a star from the equator and the degree that culminates with it from the latitude of the star and the declination of the degree in which it is, and in the chapter on knowing half the arc of the day of a star from its distance from the equator. Add what results of half the arc of the day of the moon to the times of the ascensions of the degree that culminates with it in the right sphere: the result is the times of the ascensions of the counterpart of the degree with which the moon sets in that clime. Subtract from them the times of the ascensions that stand opposite the degree opposite the degree of the sun in that clime: the remainder is the distance between the sun and the moon in degrees of the settings, so keep it. Then find the true degree in which the moon was, and its true latitude; take what lies between the true degrees of the sun and of the moon, multiply it by itself, add to it the latitude of the moon multiplied by itself, and take the root of the sum: the result is the distance of the moon from the sun, approximately.[272]

Ar. p. 132

If you wish to know this from what we mentioned at the beginning of the book, in the chapter on knowing the distances between the stars in their arrangement on the sphere, that is more correct and more exact. If the distance of the moon from the sun is [more than] 12;11, take what exceeds 12;11, and if it is less, find what it falls short of it, and note the amount of the excess or the shortfall with its mark. Then see what part of 12;11, which is the amount of the light in the moon for seeing, that excess or that shortfall is, and take that much of the excess or of the shortfall: that is the part, by which the arc of seeing grows or decreases. Then enter with the corrected anomaly of the moon into the table of the computation and take the minutes that stand opposite it in the third column, in which the shares of the distances of the moon are set down. If those minutes are exactly 30, the moon is at its mean distance from the earth; then, if that part has the mark of the shortfall, add it to 11;45, which is the amount of the arc of seeing, and if it has the mark of the excess, subtract it from 11;45. If the minutes are more than 30 or less than 30, look at what exceeds 30 or falls short of it, find what part of the 30 minutes it is, and take as much of the part. Of the result take half a sixth, since the diameter of the moon varies so that its excess over its mean diameter and its shortfall from it are about half a sixth of its mean

[271] The times of the equator are degrees of the equator, 15 to the hour. 12;11 is the mean daily gain of the moon on the sun (chapter 30): the moon gains about two fifths of a degree in the four fifths of an hour that 12 times take to set, so that 11;47, which al-Battānī rounds to 11;45, is the mean arc of seeing (Schiaparelli, in Nallino's commentary). Four fifths of a part of light follows the rule of chapter 30, one part for each 15 parts of distance. The bracketed word is supplied by Nallino, who also restores the order of the words of the codex.

[272] The crescent is looked for at the sunset that ends the 29th day, which begins the night of the 30th, the Muslim day beginning at sunset; Nallino translates «[after] the 29th day». The chapters cited are 18 and 19. The distance between the sun and the moon in degrees of the settings is counted with the oblique ascensions of the opposite degrees, since a degree sets with the rising of its counterpart.

diameter. Add what you obtain of the half sixth to the part if the part has the mark of the excess and the minutes of the third column are more than 30; if the minutes of the third column are less than 30, subtract that half sixth from the part. If the part has the mark of the shortfall and the minutes are more than 30, subtract the half sixth that you obtained from that part, and if the minutes are less than 30, add it to the part. Then look at what the part comes to after the addition or the subtraction: if it has the mark of the excess over 12;11, subtract it from 11;45, and if it has the mark of the shortfall, add it to 11;45. The result is the amount of the arc of seeing corrected for the increase and the decrease of the light of the moon in its distance from the earth at that time. If what you kept of [the arc] between the sun and the moon in degrees of the settings is equal to the corrected arc of seeing or more than it, the crescent will be seen; if it is less than the corrected arc of seeing, it will not be seen in that locality.[273]

Clearness and purity of the air help the seeing of the crescent, and its thickness and turbidity hinder it, besides the differences that arise between eyes in looking, in strength and weakness. The twilight may be thick and then grow thin before the moon sets from the horizon and reaches the limit of setting, and then the crescent is seen after the time of seeing on which one works. For this reason one should not despair of seeing the crescent until it is known to have set, if it is at a place of seeing, and it is certain that it has gone down below the horizon; then one may despair of it. For these reasons it may be seen in one place and not in another; the like happens also because of the difference of the risings and the settings of the signs in the localities, in length and shortness.

Ar. p. 133

As for what opinion inclines to, and whose truth is not doubted, according to what the ancients set down about the seeing of the crescent in what they laid down and described, that it cannot be seen in less than a day and a night: if we take the distance of the moon from the sun when the moon moves with its least course and the sun with its greatest, that is, when the moon is at its farthest distance on the epicycle and the sun at its nearest distance, we find its distance from the sun in a day and a night to be 10 parts and a half and a third of a part, and that is the amount of the arc of seeing on the equator by this reckoning. When the moon moves with its greatest course and the sun with its least, that is, where the moon is at its nearest distance and the sun at its farthest distance on the epicycle, we find the distance of the moon from the sun in a day and a night to be about 13⅔ parts. So we use this amount of the ecliptic for the light that is in the moon at the time of seeing, and we say that when there are 10 parts and a half and a third of the times of the equator between the sun and the moon, and its distance from the sun in parts of the signs is 13⅔ parts, it is at the place of its seeing, unless something of the state of the air that we have mentioned prevents it; no doubt enters into this for us. Since the moon may be farther from the sun than these parts of the ecliptic mentioned, or less, and may move on the epicycle away from the point of the farthest distance towards its nearest distance, the amount of the seeing changes for that reason, as we said just now.[274]

Ar. p. 134

If you wish to know the truth of the seeing in this way, compute the sun and the moon for the time mentioned in those ways, so that you know its distance from the sun in parts of the settings

[273] The chapter on the distances between the stars is chapter 26. The words in brackets are supplied by Nallino; the codex has 41;45 for 11;45 here and below. As the text stands, the fraction found is taken of the excess or the shortfall itself. In Schiaparelli's account of the rule (Nallino's commentary) the arc of seeing, 11;45, is reduced in the inverse ratio of the elongation to 12;11, a greater elongation giving a broader crescent, so that to first order the part is that fraction of 11;45; in the parallel rule below Nallino supplies «of those 10;50». The arc is then corrected for the distance of the moon: the third column, counted with the two columns of numbers, has 30 at the mean distance, 0 at the farthest and 60 at the nearest, and the apparent diameter of the moon, 0;29,30 to 0;35,20 (chapter 30), varies by about a twelfth on either side of its mean.

[274] Schiaparelli calls this explanation of the two numbers a rather strange one (Nallino's commentary). With them the rule that follows takes the moon at its farthest distance, with an arc of seeing of 10;50 at an elongation of 13;40, where the first rule gives 11;45 × 13/12 × 12;11/13;40 = 11;21; so the second rule sometimes finds the crescent visible where the first does not. With the hourly motions of chapter 30 (the moon 0;30,12 and 0;36,10, the sun 0;2,33 and 0;2,23) the least and the greatest gain in a day and a night come to about 11;4 and 13;31. Plato of Tivoli has 13;30.

of the locality. Then find the distance of the moon from the sun in parts of the signs according to the latitude of the moon, in that way. If it is more than 13;40, find the amount of the excess, and if it is less than that, find the amount of the shortfall; see what part of 13;40 either of them is, and take that much of it: that is the part. If the moon is at its farthest distance, in which it was at the time of the given amount of the arc of seeing — which happens when the corrected anomaly of the moon is about 360, with no excess or shortfall except of no account — subtract that part from 10;50 if it has the mark of the excess, and add it to 10;50 if it has the mark of the shortfall: the result after that is the corrected arc of seeing. If the moon has left its farthest distance, enter with its corrected anomaly into the tables of the computation and take the minutes that are in the third column; find what part of 60 they are, and take that part of the part. Take a fifth of the result, since the excess of the greatest diameter of the moon over its least diameter is that part of its least diameter. Subtract what you obtain of the fifth from that part that has resulted for you if the part has the mark of the shortfall, and add it to it if it has the mark of the excess. See how much the part comes to after the addition or the subtraction in times of the equator; add the result to 10;50 if the part has the mark of the shortfall from 13;40, and subtract it from it if it has the mark of the excess: the result is the amount of the corrected arc of seeing. If it is equal to the distance between the sun and the moon in times of the settings, or less than it, you know that the moon is at the place of seeing, no doubt about it, whether some of what we have mentioned hinders it or not; if the corrected arc is more than the times of the settings, you know that the crescent cannot be seen in that locality. We know how much the part that results comes to in times of the equator in this way. We enter with the times that we described as the times of the ascensions of the degree opposite the degree of the moon in the clime, and find what stands opposite them of the degrees of the signs: that is the degree opposite the degree with which the moon sets. We add to it what has resulted of the part, and keep the result; this we do if the part has the mark of the excess. If the part has the mark of the shortfall, we subtract what has resulted of the part from the degrees of the signs that we have obtained, and keep the remainder. Whichever of the two happens, we find what stands opposite it of the times of the ascensions, and see how much they exceed those first times, the times of the ascensions of the degree opposite the degree of the moon, or how much they fall short of them: the result is the amount of the part that has resulted, in times of the equator. We subtract it from the arc of seeing or add it to it, as is due, if God wills.[275]

As for seeing the moon in the mornings at the ends of the months, it is on this pattern, except that you use the times of the ascensions of the degree of the sun itself and the times of the ascensions of the degree of the moon itself. You find the times of the ascensions of the degree of the moon by subtracting half the arc of the day of the moon from the times of the ascensions of the degree that culminates with it in the right sphere: the remainder is the times of the ascensions of the degree that rises with the moon in the clime. Subtract from that the times of the ascensions of the degree of the sun: the remainder is the amount between the sun and the moon in times of the ascensions, when the moon is on the eastern side. If the arc of seeing that results is equal to the distance between the sun and the moon in times of the ascensions, or less than it, the moon is seen before sunrise in the morning; if it is more, it has been hidden by the rays and is not seen. The computation of the sun and the moon should be made for the time of sunrise of the 28th day of the Arab month, which is a day before the conjunction.

Ar. p. 135

If you wish to draw the shape of the crescent in the state in which it is seen, with its two horns level or inclined, and the amount of the light that is in it: divide the distance between the sun and the moon in parts of the signs, according to the latitude of the moon, by 15, so that the result is a part out of 12 parts of the circle of the moon: the result is the digits of light. Then draw a

[275] «Of it» is of the 10;50, as Nallino understands it (compare the note on the first rule). The codex has 64;50 for 10;50 here and below, the Maghribi ص being 60 (Nallino). The greatest diameter of the moon, 0;35,20, exceeds the least, 0;29,30, by about a fifth of the least (chapter 30).


circle of any size you wish, divide it into quarters by two lines that intersect at the centre at right angles, mark on the ends of the lines their directions on the horizon, and divide each quarter of the circle into 90 parts. Then mark, according to the true latitude of the moon, from the point of the east and the point of the west towards the side of the latitude of the moon, two marks, so that the amount of each of the two arcs is as much as the latitude of the moon. Then put the edge of the ruler on the two marks and draw along it a straight line that passes through the two marks and is parallel to a diameter of the circle, and extend it beyond the circumference of the circle towards the east by the amount of the radius of the circle. On this line is the passage of the moon in longitude at that time, and at the other times according to the latitude that it may have, from the time of its first appearance to the time of its half light, for the centre of its circle then falls at the point where the circumference of the circle meets this line; and from the time of its half light to the time of its fullness the centre of its circle is on the line that goes out from the circumference of the circle and runs towards the east, until it reaches the end of the line, between its circle and the circle of the sun. So the first circle, drawn for the sun, is the circle of the moon at its fullness. Then count on the circumference of the circle, from the point of the north towards the east, the same number as is between the sun and the moon, and likewise from the side of the south towards the east, mark two marks on it, and join one of the marks to the other by a straight line: where the two lines intersect is the centre of the circle of the moon. Draw about it a circle the size of the first circle: the crescent that falls between the two arcs is in the shape of the crescent and the image of its appearance. Then join the two points at which the two circles intersect by a straight line, which is a second diameter of the circle, and draw also a straight line that passes through the centres of the two circles and through the two arcs and divides the crescent into two halves. From this it becomes clear to you how much each of the two horns of the crescent inclines from the middle of the belt of the signs, by the parts into which you divided the circumference, for the ecliptic then has a known limit on the horizon, from the azimuth on the circle of the horizon of what rises and sets with it at that time.[276]

Ar. p. 136

Let the circle of the sun be the one on which ABGD, about the centre H, with the diameters AG and BD. We take A as the direction of the south, G the direction of the north, B the direction of the east and the point D the direction of the west. We take the latitude of the moon to be 5 parts to the north and its true distance from the sun 12 parts. We cut off from the circle, from the points B and D, the amount of the latitude of the moon towards the side of the north, which is the point G, mark on it Ṭ and K, join them by a straight line, the line ṬK, and extend it to the sign L; let the line KL be equal to the line HB. From the points A and G we cut off two arcs towards the side of B, the amount of each of them equal to what lies between the sun and the moon; we mark at the ends of the two arcs the signs M and S, join them by the straight line MS, and mark the place where it cuts the line ṬK with the sign Z. We take Z as centre and draw about it a circle for the moon the size of the first circle, and mark at the intersections of the two circles the signs F and Q. We draw also the line HZ and extend it to the sign ʿ of the first circle; the sign ʿ falls on the middle of the arc FQ. We mark the sign Ḥ on the circumference of the circle of the moon where the line ZHʿ cuts it. The line ʿḤ is the middle of the curve of the crescent and the place of the middle of the light, which is the amount of the digits of light in the moon. The signs F and Q are the two ends of the crescent, and their inclination to the line of levelness standing upright on the ecliptic is known by the arc AF and the arc GQ. For the point D is then in the direction of the setting degree and the point B in the direction of the rising degree on the circle of the horizon, so that the line BD is the line of half the ecliptic. By this figure you know the shape of the light of the crescent at all the times of the month, according to its distance from the sun and

[276] Twelve digits are the whole visible half of the moon at the full, each 15 degrees of the semicircle of its disc (Nallino); Plato of Tivoli has 15 for these 12 parts. The construction gives the inclination of the line of the horns to the ecliptic quite exactly, as long as the elongation is not much greater than on the first evening of visibility. The figure between the two arcs is the visible lune; the crescent actually seen is much thinner, since that part of the moon's surface is seen very obliquely (Schiaparelli, in Nallino's commentary).

the amount of latitude that it has. Whenever the moon is at its nearest distance, the two horns are sharper, because its circle is then greater than the sun's. This is what we wished to explain, if God wills.[277]



[278]


Ar. p. 137

If you wish to know the place of the sky in which the crescent is seen, according to its altitude above the western horizon at the beginnings of the months, and the azimuth of its place in which it is seen on the circle of altitude that passes through the zenith, through the moon and through the horizon, by a pointer, so that the line of sight goes out along its direction to the place of the crescent: add about four minutes to the degree that culminates with the moon, so that this is the degree that culminates with it at the time of seeing; for the rays of the sun prevent its being seen at sunset until the sun has gone down below the horizon about an eighth of an hour. Then find the visible altitude of the moon about an eighth of an equal hour after sunset, and find the azimuth of the moon on the circle of the horizon at that time in the ways that we have set out. Then go to a place where the horizon is open and set up there a column, or something like a column, whose height above the horizon is a person's height, so that the observer can [look] from it at the moon. Let its surface be flat, levelled with the plumb line and parallel to the plane of the horizon. Take a centre on it and draw about it a circle of any size you wish; mark the directions of the east, the west, the south and the north in the way given for finding the meridian line, and divide the quarter of the circle on the side of the crescent into 90 parts. Then take a flat ruler or a hollow tube, and put the edge of the ruler, or the middle of the thickness of the tube, on the centre of the circle and on the amount of the distance of the azimuth of the crescent from the point of the east or of the west, whichever side the crescent is on, in the direction in which the azimuth is. Then hang the astrolabe from your hand, after setting the end of the alidade at the visible altitude of the moon that you have found, and raise the end of the ruler or of the tube that is towards the crescent from the surface of the circle, with something to support it, without its turning aside from the azimuth of the moon or from the centre of the circle, so that the end towards the crescent rises and the end towards the eye goes down, and the sight passes through the two holes of the alidade along the edge of the ruler or the middle of the tube, so that there is a straight line from the place of the eye to the place of the crescent in that direction. When the

[277] The translation reads D (د) for the text's A (ا), with Nallino's translation, which corrects the printed Arabic text here (p. 136, line 5); the codex and Plato of Tivoli have A. The line ʿḤ is the breadth of the visible lune, not of the thinner crescent actually seen (Schiaparelli, in Nallino's commentary). Plato of Tivoli has «the tips will be less sharp».

[278] In the codex the figure, as usual, is carelessly drawn; its quadrant BG is divided into degrees, and under it stands «and the whole circle is divided like this quarter, if God wills» (Nallino).

observer looks at the time of seeing, the crescent will be seen along the direction of the edge of the ruler, or through the tube. This is the figure of what we have described, if God wills.[279]



[280]

Ar. p. 138

Al-Battānī said: We draw the circle of the horizon mentioned, marked ABGD, about the centre H, and let the point H be the place of the centre of the circle of the horizon on the plane, which is the zenith; the point A the point of the south, the point B the point of the east, the point G the point of the north, and the point D the point of the west. We draw the two lines AG and BD. We take the moon to be on the western side, which is the quarter AD, and make the point B of the ecliptic the beginning of Aries, so that the point D is the beginning of Libra: these are the rising and the setting points of the ecliptic. We take the southern half of the ecliptic to be the arc DLB; then the line GL is clearly the place of the beginning of Capricorn, which is on the meridian line. Let the degree that culminates with the moon be the point Ṭ of the ecliptic, which is the beginning of Scorpio. We put the sign Z at the place of the moon in its southern latitude, and make the line KHṬZḤ the place of the edge of the ruler, or of the middle of the thickness of the tube, which passes through the centre of the circle, through the place of the moon and through the degree that culminates with it. We find the arc DḤ of the horizon. Clearly the arc ṬḤ is the altitude above the horizon of the degree that culminates with the moon, and the arc ZḤ the altitude of the moon above it; likewise the arc AL is the altitude of the beginning of Capricorn in the middle of the sky, and the arc DṬ of the ecliptic is that from the point of the beginning of Libra to the degree that culminates with the moon; and the point Ḥ is the azimuth of the moon. So the arc DḤ of the horizon is the distance of the azimuth of the moon from the point of the equinoctial setting. When the line KḤ is raised from the point H and the point Ḥ, by the amount of the altitude of the moon set on the astrolabe, towards the air, the place K of it goes down towards the earth, the sight passes through the two holes of the alidade of the astrolabe, which are the points M and K, and the whole line is joined, so that the whole line MḤ becomes one straight line. When the observer looks from the place K or the place M, the crescent will be seen

[279]The translation follows Nallino's emendanda (Part II, p. XXXI) in reading «سمت القمر», «the azimuth of the moon», for «القمر» at p. 137, line 1. In an eighth of an hour the moon moves about 4 minutes, its mean motion in an equal hour being 0;32,56 (Nallino). «Look» is added after Nallino's suggestion. The meridian line is found as in chapter 12. The translation follows the corrigenda in reading «الدائرة», «the circle», for «الدئراة» (p. 137, line 10). This is the earliest mention of sighting tubes among the Arabs; a tube keeps off much of the diffuse light of the sky, which hinders seeing (Nallino's commentary).

[280]Nallino prints the codex's figure, which Nallino calls rather inept; in the commentary Schiaparelli draws the figure that Schiaparelli takes to be al-Battānī's own.

with that pointer in the direction of the line KḤ, if the air is clear and thin, no doubt about it. If the air is changeable and turbid, it prevents its being seen in that town; but it is seen in other towns whose distance from the equator is like the distance of that town, since a change of the air need not extend over every locality. For this reason also it may not be seen in the villages and dwellings near it.[281]

Chapter 42. On knowing the computation of the conjunctions and the oppositions of the sun and the moon by the era of the Romans and the era of the Copts, and on knowing their times in every locality

Ar. p. 138
Ar. p. 139

Al-Battānī said: If you wish to know the computation of the conjunctions or the oppositions in any month you wish of the months of the Romans, take the years of Dhū l-Qarnayn, and do not count the year that you are in until Subāṭ has run out. Look for the number of years that you have in the column of the collected years of the tables of the conjunction or of the opposition, whichever you want. Wherever you find the same — I mean the same number — or the nearest one below it, take what stands opposite it in the four columns that are for the days, the mean position of the sun and the moon, the anomaly of the moon and the motion in latitude. Then see what remains with you of the years in excess of those that you found in the table, enter with it in the column of the single years, and take what stands opposite it in those four columns; write down what you find in each of them with its counterpart, I mean each kind under its kind. Then take what stands opposite the complete month before the month in which you wish to compute, of the days of the lunar months set down in the first of the four columns, and add it to the sum of the days that came from the collected and the single years that you wrote down. If the sum of all that is more than the number of the days of the Roman months set down under that complete month, and less than the days under the month that you are in, which is the month in which you wish to compute, write down those days that you found opposite the complete month and what is under them in the three remaining columns. If the sum of the days is more than the Roman days set down under the month in which you wish to compute, take the days that stand opposite the month before the complete month, and what is under them in the three remaining columns, and write it down with what you wrote from the tables of the collected and the single years. What each of the four columns comes to after you have added it up, write down in the manner given before. Then subtract the Roman days that stand opposite the complete month before the month in which you wish to compute from the days that came from the sum of what is in the three tables of the collected years, the single years and the months: the days and minutes that remain are days that have passed of the month in which you wished to compute, and equal hours after noon of the last day that has passed of that month up to the time of the conjunction or the opposition of the sun and the moon at that time by their mean course. [From the three remaining columns come the positions of the sun and the moon at that time by their mean course,] the anomaly of the moon and the motion in latitude. [The mean position of the moon] is the mean position of the sun at the time of [the conjunction; at the time of] the opposition the mean position of the moon is necessarily opposite the mean position of the sun.[282]

Ar. p. 140

[281] The words «which is the beginning of Scorpio», «and through the degree that culminates with it», «the arc ṬḤ is the altitude above the horizon of the degree that culminates with the moon, and» and «the arc DṬ of the ecliptic is that from the point of the beginning of Libra to the degree that culminates with the moon», though they are in the codex and in Plato of Tivoli, should be struck out (Nallino, after Schiaparelli): the degree that culminates with the moon lies on the great circle through the moon and the pole of the equator, not on the line of sight, and serves no purpose here. Nallino's translation accordingly names the line KHZḤ. In the last sentence Nallino translates «it may be seen in the villages near it».

[282] The years of the tables begin on 1 Ādhār, March, six months before the year of Dhū l-Qarnayn with the same number, which begins on 1 Aylūl, September; so the year that you are in is counted only when Subāṭ, February, is over (Nallino; see chapter 33). The first bracketed words are supplied by Nallino after Plato of Tivoli. The printed text then reads «and it is the mean position of the sun at the time of the opposition, and the mean position of the moon is necessarily opposite the mean position of the sun»; the other bracketed words follow the correction that Nallino

If you wish to compute the conjunction and the opposition by the era of the Copts, take the years of Dhū l-Qarnayn together with the year that you are in, even if only one day of Aylūl has entered. Then cast 287 from the years, and take a quarter of what remains: the result is the days of the quarters. If a fraction falls in it, do not count it; if no fraction falls, that year is a leap year. When the year is a leap year, drop one day from the days of the quarters, unless Subāṭ has run out and come out at 29 days; when Subāṭ has run out, add the day that you had taken away back to the days. To the days of the quarters that result always add the three days by which the Copts precede the Greeks in Tūt, and to what the days come to after that add the days from the beginning of Aylūl to the end of the Roman month before the month that you want, the month in which you compute. If the sum of the days is more than 365 days, cast 365 from it and add a year to the years of Dhū l-Qarnayn from which you subtracted nothing; if the year is a leap year and Subāṭ has run out, you count the year as 366 days. What results of the days after casting off the year, if they were more than a year, or the days themselves if they were less than a year, are the days of the Copts; write them down apart. Then enter with what you have of the years of Dhū l-Qarnayn, with the year added on account of the days if there is one, into the table of the collected Egyptian years, which go in steps of 25, in the column of the collected years in the tables of the conjunction or of the opposition, whichever you want. Wherever you find the same years, or the nearest number below them, take what stands opposite them in the four columns in that way. Look for the years that remain in the column of the single years, and take again what stands opposite them in the four columns. Then take the days of the Copts and cast them out by thirties; enter with the number of complete months that results into the column of numbers of the tables of the Coptic months, take what stands opposite it in the column of the days, and add it to the days that came to you from the two tables of the collected and the single years. If the sum is equal to the number of the days of the Copts, or more than it by less than a lunar month, write down those days and what is under them in the three remaining columns. If the sum of the days is more than the days of the Copts by more than a lunar month, take one month from the number of the complete Coptic months with which you entered the table; take what stands opposite the number of complete Coptic months that remains in the four columns and write it down. Then add it up in the usual manner, and subtract the days of the Copts from the days that result: the days and minutes that remain are the days and the hours of the conjunction or the opposition that have passed of the month in which you wished to compute, and what results from the three columns is the mean position of the sun and the moon, the anomaly of the moon and the motion in latitude.[283]

Ar. p. 141

When you know that by whichever of the two eras you wish, look at the minutes that are added up with the days, and count each 2½ minutes of them as an equal hour; what does not make up 2½ minutes is parts of an hour. The days and hours that result are the days of the mean conjunction or opposition and its hours after noon at the city of al-Raqqa; keep them.[284]

Then write down the mean position of the sun and the moon in another place, making one of the two places for the sun and the other for the moon, and compute the true positions of the sun and the moon as usual, except that for the moon you then need only the single equation, for the distance between the sun and the moon is not such that a sensible error enters from the second equation. If the sun and the moon are equal to the minute, that is the time of the true conjunction or opposition. Then do with the motion in latitude what you did with the mean position of the moon: add the single equation to the motion in latitude if you added it to the mean position of the moon, and subtract it from it if you subtracted it from the mean position of the moon.

If the positions of the sun and the moon differ, take the excess between them in degrees and

proposes and translates.

[283] The days of the Copts, the days that have passed of the Coptic year, are found as in chapter 32.

[284] A day is 60 minutes, so that 2½ minutes are an hour. The translation reads «الأيّام», «the days», for «الأبّام» (p. 141, line 2), a misprint that the corrigenda do not list.

minutes, and find its sixth and its eighth. If the excess is the sun's, add that sixth and eighth to the anomaly of the moon, and if the excess is the moon's, subtract them from it; what the anomaly comes to after the addition or the subtraction is the corrected anomaly. Enter with it into the tables of the equation of the moon, in the two columns of numbers, and take what stands opposite it of the single equation, set down in the second column. If this anomaly is less than 180, subtract this equation from the mean position of the moon itself and from the motion in latitude itself; if the number of the anomaly is more than 180, add the equation to the mean position of the moon and to the motion in latitude. What the mean position of the moon comes to after the addition to it or the subtraction from it is the true position of the moon.[285]

Ar. p. 142

Then take again the excess between the sun and the moon and know it. Then take the motion of the sun and of the moon in an hour: enter with the corrected anomaly of the moon, with which you found the equation of the moon, and the anomaly of the sun, with which you found the equation of the sun, into the tables of the unequal course of the sun and the moon, in the two columns of numbers, which go in steps of 6 parts, and take what is under them in the column of the course of each of them, by interpolation, after adding to the course of the moon, or subtracting from it, the seconds that you find set down under the excess between the sun and the moon, in the way that we have explained in that chapter, at those tables. Then subtract the motion of the sun from the motion of the moon: the remainder is the unequal gain of the moon on the sun in an hour. Divide the excess between the sun and the moon by the gain of the moon: the hour and part of an hour that result are the hours of the excess; keep them. If the excess is the sun's, add the hours of the excess to the hours of the mean conjunction that came from the tables, and if the excess is the moon's, subtract them from them. What the hours of the mean conjunction come to after the addition or the subtraction are the plain hours of the true conjunction. If they are more than 24 hours, subtract 24 hours from them and add one day to the days that have passed of the month. If you need to subtract the hours of the excess from the hours of the mean conjunction, and the hours of the excess are more than the hours of the mean conjunction, take one day from the days that have passed of the month, count it as 24 hours, and add them to the hours of the mean conjunction; then take the hours of the excess from the sum. What results of the hours of the mean conjunction after the addition or the subtraction is the equal hours that have passed after noon at the city of al-Raqqa of the day that you obtained from the days that have passed of the month.[286]

Multiply the hours of the excess by the course of the sun and the course of the moon in an hour, and keep the products. If the excess is the sun's, add what results for the sun to the position of the sun, and what results for the moon to the position of the moon and to the motion in latitude; to the motion in latitude add besides the motion of the northern node in the amount of those hours. If the excess is the moon's, subtract in all of this instead of adding, so that you obtain the correct positions of the sun and the moon at that time.[287]

If you wish to work approximately in another way, find half a sixth of the excess between the sun and the moon. If the excess is the sun's, add half a sixth of the excess to the sun, and the whole excess with half its sixth to the moon and to the motion in latitude; if the excess is the moon's, subtract half a sixth of the excess from the sun, and the whole excess with half its sixth from the

[285] The excess is the sun's when the true sun is ahead of the true moon, so that the true conjunction comes after the mean one. The reason for adding a sixth and an eighth, 7/24, of the excess to the anomaly is given below. The second column is counted without the two columns of numbers (Nallino).

[286] That chapter is a short unnumbered chapter on the hourly motion of the moon, which stands with the tables in the Escorial codex alone and which Nallino prints after chapter 57 as chapter H. The seconds correct the hourly motion of the moon for its elongation from the sun: about one second an hour for each degree of elongation, taken from it in the upper part of the epicycle and added in the lower (Schiaparelli, in Nallino's commentary). The plain hours are mean hours; they are converted into hours of the irregular days below.

[287] The motion in latitude is counted from the northern node, which moves backwards; so the node's motion in those hours is added to it as well.

moon [and from the motion in latitude]: then the two are equal to the minute. Then divide [the whole excess] and half its sixth by the unequal motion of the moon in an hour: the result is the hours of the excess. Subtract them from the hours of the mean conjunction if the excess is the moon's, and add them to them if the excess is the sun's, in that manner. But the first procedure is more correct.[288]

Ar. p. 143

You should also know the anomaly of the moon at the time [of the conjunction and the opposition]: enter with the hours of the excess into the table of the hours, take the course of the anomaly of the moon in them, and add it to the corrected anomaly of the moon if the excess is the sun's, and subtract it from it if the excess is the moon's. What it comes to after that is the corrected anomaly of the moon at the time of the conjunction, if your computation is for the conjunction; if your computation is for the opposition, it is the corrected anomaly of the moon at the time of the opposition. Then add 180 degrees to the position of the moon that you had made the same as the mean position of the sun, so that the true position of the moon is opposite the true position of the sun, where it is seen.[289]

When you know the plain equal hours of the conjunction, which are the mean hours, convert them into hours of the irregular days. Enter with the degree of the sun into the tables of the right sphere and take the degrees and minutes that stand opposite it in the column of the equation of the days, set down in the sign of the sun; divide what there is by 15: what results is hours, and what remains is part of an hour. Always add it to the mean hours of the true conjunction: what they come to after that is the equal hours of the true conjunction converted into the irregular days, which are found by measurement, after noon at the city of al-Raqqa. Then convert them into hours of the locality that you want. You do this by taking the excess between the longitude of the city that you want and the longitude of the city of al-Raqqa, which is 73;15, and dividing it by 15. Add the hour or part of an hour that results to the hours of the true conjunction that you have obtained if the longitude of the city is greater than the longitude of al-Raqqa, and subtract it from them if the longitude of the city is less than the longitude of al-Raqqa. What the hours come to after the addition or the subtraction is the true equal hours after noon in that city.[290]

If you wish to know the ascendant of the conjunction, multiply all these hours by 15, add the product to the ascensions of the degree of the sun in the right sphere, and with what results you know the ascendant and the middle of the sky as usual.[291]

If you wish to convert these equal hours into seasonal hours, multiply them by 15 degrees and keep the product. Then find the hours of the night and of the daytime from the degree of the sun in that clime. From what you kept of the product take out the times of the hours of the daytime, up to a total of six hours; if it is less than six, add to the hours that come from it six seasonal hours, those from sunrise to noon: the sum is what has passed of the daytime from sunrise to the time of the conjunction, in seasonal hours. If what you took out is six complete hours and a remainder is left with you, take it out by the times of the hours of the night, up to a total of 12 hours; if yet another remainder is left, take it out by the times of the hours of the daytime again: what comes from it is what has passed of the hours of the daytime from sunrise of the morrow. If you wish to know the ascendant from these hours, you know it in the usual way.

Ar. p. 144

It is clear that if the hours of the conjunction are more than half the equal hours of the daytime of that day, and you subtract them from 12 hours if they are less than 12, the remainder is the

[288] The bracketed words are supplied by Nallino after Plato of Tivoli. Half a sixth, a twelfth, of the excess is the motion of the sun while the moon gains the excess on it: the moon moves about 13 times as fast as the sun, so that in that time the sun moves about a twelfth of the excess (Nallino). This is Ptolemy's method in *Almagest* VI 4 (Nallino).

[289] The bracketed words are supplied by Nallino after Plato of Tivoli.

[290] The equation of the days with their nights is that of chapter 29. Here it is added, since the hours are converted from mean days into irregular days; chapter 34 subtracts it for the opposite conversion.

[291] At noon the sun is in the middle of the sky, and 15 times of the right sphere pass the meridian in each equal hour; the ascendant and the middle of the sky are then found as in chapters 16 and 35.

amount in equal hours by which the conjunction precedes the time of midnight. If the hours are more than 12, up to the completion of half the equal hours of that night, and you cast 12 hours from them, the remainder is the amount in equal hours by which the conjunction comes after the time of midnight. If they are more than 12 together with the half of the hours of the night that is added to them, subtract them from 24 hours: the remainder is the amount in equal hours by which the conjunction precedes the time of noon of the morrow. By what we have described you know the time of the conjunction or the opposition, and the positions of the sun and the moon, the anomaly of the moon and the motion in latitude at those times.

What compels us to correct the anomaly of the moon by a sixth and an eighth of the excess is that the time of the mean conjunction cannot be, and need not be, at every time the time of the true conjunction. If we neglect what falls in the anomaly on account of the doubled distance between the sun and the moon, a variation can fall in the time of the conjunction or of the opposition whose greatest amount can reach about a quarter of an hour. For if the equation of the sun amounts to 2 parts and the equation of the moon to 3 parts, then, when one of the two equations is added to the mean course and the other subtracted from it, they make together 5 parts, and twice that is 10 parts, which is the doubled distance; and you find the equation of the anomaly at such a distance, by addition or by subtraction, about a degree and a half, which is about a sixth and an eighth of the excess. When the moon is at the place on the epicycle where its corrected equation must be 3 parts, the share of the degree and a half in it is about an eighth of a part, and that comes, by the gain of the moon, to about a quarter of an hour.[292]

Ptolemy, on the other hand, based the reckoning in this on the greater of the two equations, where the equation of the moon is 5 parts and that of the sun 2 parts and 23 minutes, according to the computation on which Ptolemy worked; the excess between the sun and the moon then comes to 7 parts and 23 minutes, and twice that is about 14 parts 46 minutes. On this reckoning no more than an eighth of an hour need arise from it, as was mentioned. But when the equation of the moon is 5 parts, the share of the one or two parts that is then added to the anomaly of the moon or subtracted from it is only a small thing of no account; it varies more at 3 parts than at 5 parts. For this reason the matter is as we have said.[293]

Ar. p. 145

It is clear also that if we divide the excess between the sun and the moon by the gain of the moon taken with the anomaly that holds between the mean and the true conjunction, that is more correct and more exact. You know it by taking half the excess between the sun and the moon and adding to it half its sixth; then subtract that from the corrected anomaly if the excess is the moon's, and add it to it if the excess is the sun's: so we obtain correctly the anomaly of the moon for the middle between the true and the mean conjunction. With it take the course of the moon in an hour, subtract from it the course of the sun, and use the remaining gain of the moon only in dividing the excess.[294]

If you wish to compute the times in another way, by the method of minutes, which is the method

[292] The doubled distance is twice the elongation of the moon from the sun; away from the mean conjunctions the anomaly needs a correction that depends on it. Schiaparelli (Nallino's commentary) derives the correction from Ptolemy's lunar model, with the distance 10;19 between the earth and the centre of the eccentric in parts of which the centre of the epicycle is 60 from the earth at the conjunctions: it is 20;38/70;19 = 0.2934 of the elongation, against al-Battānī's 1/6 + 1/8 = 0.2917, and for an elongation of 5 parts it is 1;28. At the mean hourly gain of the moon, 0;30,28, an eighth of a part takes about a quarter of an hour.

[293] Ptolemy's values are those of *Almagest* VI 5, on the limits of the eclipses, which take 5;1 for the moon, so that the excess is 7;24 (Nallino). Schiaparelli remarks that that problem has nothing to do with this correction, and would read «an eighth of a degree» for «an eighth of an hour», as in the preceding paragraph (Nallino's commentary). The neglected correction matters most where the equation of the moon is about 3 parts: at the greatest equation the equation hardly changes, and near the farthest and the nearest distance on the epicycle the elongation is only the equation of the sun (Schiaparelli). With a greatest equation of 5;1 and an equation of the sun of 2 parts, it changes the equation of the moon by at most about 0;7, where the equation is about 3 parts.

[294] Half the excess with a twelfth of that half is the motion of the moon, and so nearly of its anomaly, in half the time between the mean and the true conjunction; the twelfth comes from the motion of the sun (Nallino).

by which the day and night are 60 minutes, take the true equal hours of the conjunction after noon in the city and multiply them by 2½ minutes. If the product is 30 minutes, the conjunction is at midnight; if it is less than that, it is before midnight; and if more, after midnight. Put the minutes that you obtain in the place of degrees, so that each minute of them becomes a degree and each second a minute. Then find the times of the hours of the daytime and of the night. If those degrees are less than the times of the hours of the daytime, the conjunction is in the daytime; divide them by a sixth of the times of the hours of the daytime: the result is seasonal hours after noon. If those degrees are more than the times of the hours of the daytime, up to 30, subtract the times of the hours of the daytime from them and divide the remainder by a sixth of the times of the hours of the night: the result is the seasonal hours that pass from the beginning of the night up to midnight. If they are more than 30, cast 30 from them; if the remainder is less than the times of the hours of the night, divide it by a sixth of the times of the hours of the night: the result is seasonal hours after midnight. If the degrees are more than the times of the hours of the night, subtract the times of the hours of the night from them and divide the remainder by a sixth of the times of the hours of the daytime: the result is seasonal hours that have passed from sunrise of the morrow, if God wills.[295]

Chapter 43. On knowing the eclipse of the moon by computation and by the table, and knowing the amounts of the eclipse, its times, and the direction of the darkening and the clearing on the circles of the horizons, which differ for the localities

Ar. p. 146

Al-Battānī said: If you wish to know the eclipse of the moon, examine the mean motion in latitude at the oppositions. If it is between the eclipse limits set down on the page of the months of the conjunctions and the oppositions, the moon can be eclipsed; if it is more than those amounts or less, it cannot be eclipsed. If it can be eclipsed, look at the corrected motion in latitude at the time of the opposition. If it is exactly 360 degrees, the moon is at the very node of the head, and if it is exactly 180 degrees, the moon is at the very node of the tail. If it is more than either of these two numbers, it has passed the node by the amount of the excess, and if less, it is short of the node by the amount of the shortfall. When the moon is at the very node, the eclipse is the most complete that can be. If its distance from either of the two nodes is more than 12 degrees, before it or behind it, it cannot be eclipsed; if it is less than that, it is eclipsed, and its eclipse is according to its distance from the node and its nearness to it. If the time of the opposition is at night, or near sunrise or sunset, the eclipse is seen whole or in part, according to the time.[296]

Ar. p. 147

When you know that it is eclipsed and that the eclipse, or part of it, is seen, enter with the corrected motion in latitude at the time of the opposition into the tables of the equation, take the latitude of the moon and find its side; or, if you wish, find it from the distance of the moon from the node, the meaning being the same in both ways. Keep what results of the latitude of the moon [true for the middle of the eclipse]. Then enter with the corrected anomaly of the moon at the time of the opposition into the tables of the computation and take what is under it in the third column, in which are the shares of the distance. Find what part of 60 the minutes come to, and take the same part of the 5 minutes and a half and a quarter by which the diameter of the moon varies; always add the result to 29 minutes and 30 seconds, the diameter of the moon at its farthest distance: the sum is the corrected diameter of the moon, so keep it. Likewise take, of the 7½ minutes by which the radius of the shadow varies, the part that the minutes of the third column are of 60, and add the result to 38½ minutes, the amount of the [radius] of the shadow at

[295] Taken as degrees, the minutes from noon to sunset equal the times of a seasonal hour of the daytime, each being 1¼ times the length of the daytime in equal hours; so the degrees can be compared with those times directly, and a sixth of them is one seasonal hour. The same holds for the night.

[296] In the codex the eclipse limits stand on the page of the single Egyptian years and on that of the hourly motions (Nallino). At 12 parts from a node the latitude of the moon is 1;2, about the greatest sum of the radii of the moon and the shadow, 0;17,40 + 0;46 = 1;3,40 (chapter 30).

the farthest distance of the moon: the sum is the corrected radius of the shadow.[297]

If you wish to know that by computation in another way, take its unequal motion in an hour, multiply it by six less an eighth, and take a sixth of the minutes that result: that is the amount of the corrected diameter of the moon. If you wish to know the corrected radius of the shadow, multiply half the [corrected] diameter of the moon by two and three fifths: the product is the amount of the corrected radius of the shadow.[298]

When you know the diameter of the moon and the radius of the shadow, in whichever of the two ways you wish, take half the corrected diameter of the moon and add it to the corrected radius of the shadow: the sum is half the two diameters, so keep it. Then look: if the true latitude of the moon is equal to half the two diameters, the moon touches the outermost line of the shadow, and nothing of it is eclipsed. If it is less than half the two diameters, subtract it from half the two diameters and look at the remainder: if it is equal to the diameter of the moon, the moon is eclipsed whole and has no stay; if it is more than the diameter of the moon, it is eclipsed whole and has a stay; if it is less, it is not eclipsed whole. Multiply the minutes that remained to you when you subtracted the latitude of the moon from half the two diameters by 12 and divide the product by the corrected diameter of the moon: the quotient is the amount of the diameter of the moon that is eclipsed, in the measure in which its diameter is 12 parts; these are called the digits of the eclipse, so keep them. If the moon has a stay, subtract the corrected diameter of the moon from those remaining minutes: the remainder is the minutes of the stay. Multiply them also by 12, divide the product by the diameter of the moon, and add the digits that result to the 12 digits that are the whole diameter of the moon: the sum is the digits of the eclipse from the beginning of the eclipse to its middle; keep them. Or, if you wish, multiply those minutes that remain of half the two diameters, whether they are less than the diameter of the moon or more, by 12, and divide the product by the diameter of the moon: the result is the digits of the eclipse.[299]

Ar. p. 148

Then multiply half the two diameters by itself, subtract from the product the latitude of the moon multiplied by itself, and take the root of the remainder: the result is the minutes of the fall and the stay together, if the moon has a stay, and if it has no stay, the minutes of the fall. Whichever of these two it is, divide it by the gain of the moon: the result is the hours of the fall, or the hours of the fall and the stay, as the case may be. Subtract them from the hours of the opposition, which are the hours of the middle of the eclipse: the remainder is the hours of the beginning of the eclipse. Add them also to the hours of the middle of the eclipse: the sum is the equal hours of the end of the clearing. If the moon has a stay, subtract the corrected diameter of the moon from half the two diameters: the remainder is the minutes of the amount of the whole stay. Multiply them by themselves, subtract from the product the latitude of the moon multiplied by itself, take the root of the remainder, and divide it by the gain of the moon: the quotient is the hours of the stay. Subtract them from the middle of the eclipse: the remainder is the hours of the beginning of the stay; and add them also to the hours of the middle of the eclipse: the sum is the hours of the beginning of the clearing.[300]

[297] The words in brackets are supplied by Nallino, the first after Plato of Tivoli. The diameter of the moon varies from 0;29,30 to 0;35,20 (chapter 30), by 5⅝ minutes; the codex and Plato have 5¾, and the codex has 0;29,40 for 0;29,30 (Nallino). The radius of the shadow grows from 0;38,30 to 0;46 (chapter 30). The text has «the corrected diameter of the shadow»; Nallino translates «radius», as the numbers require.

[298] Six less an eighth, divided by six, is 0.979, about the ratio of the diameter of the moon to its hourly motion, 0;29,30 to 0;30,12 and 0;35,20 to 0;36,10 (chapter 30). Two and three fifths is the ratio of the diameter of the shadow to that of the moon, 92 to 35⅓ minutes at the nearest distance and 77 to 29½ at the farthest (Nallino, from chapter 30). «Corrected» is supplied by Nallino.

[299] Half the two diameters is the sum of the radii of the moon and the shadow. Here the minutes of the stay are the amount by which the eclipse exceeds the diameter of the moon; below they are half the path of the moon in the shadow during the total eclipse, and «the whole stay» is their greatest value, for a central eclipse, half the difference of the diameters of the shadow and the moon (Schiaparelli, in Nallino's commentary).

[300] The root is the path of the moon relative to the shadow from the contact to the middle of the eclipse, the latitude being taken as constant; the contact is where the distance of the centres is half the two diameters, or, for the stay, the

If the moon is not eclipsed whole, the eclipse has three times, and likewise if it is eclipsed whole and has no stay; if it has a stay, the eclipse has five times. These times mentioned are given in general terms and are not the most exact truth in the computation, for the latitude of the moon changes between the beginning of the eclipse and its middle, and from its middle to the end of the clearing, so that the amounts of the times on the two sides of the middle of the eclipse change with the change of the latitude of the moon; the middle of the eclipse clearly does not change.

If you wish to make that exact, so that no flaw enters the computation from it, take the minutes of the fall and the stay, or the minutes of the fall, whichever it is — those that I told you to divide by the gain of the moon — and add to them half their sixth. Subtract the sum from the corrected motion in latitude at the time of the opposition: the remainder is the motion in latitude for the plain beginning of the eclipse, so keep it. Then add those minutes with half their sixth also to the corrected motion in latitude at the time of the opposition: the sum is the motion in latitude for the plain end of the clearing. Find the latitude of the moon at each of the two times from the motion in latitude at it. Then multiply the latitude of the moon at the beginning of the eclipse by itself and subtract it from half the two diameters multiplied by itself; to the remainder add the difference between the latitude of the moon at the beginning of the eclipse and its latitude at the middle of the eclipse, multiplied by itself, and take the root of the sum: the result is the minutes of the fall from the beginning of the eclipse to its middle. Divide them by the gain of the moon and subtract the hours that result from the hours of the opposition: the remainder is the hours of the exact beginning of the eclipse. Then multiply the latitude of the moon at the end of the clearing by itself and subtract it from half the two diameters multiplied by itself; to the remainder add the difference between the latitude of the moon at the middle of the eclipse and its latitude at the end of the clearing, multiplied by itself, and take the root of the result: the result is the minutes of the fall and the stay. Divide them by the gain of the moon and add the result to the hours of the opposition: the sum is the hours of the exact end of the clearing.[301]

Ar. p. 149

Likewise, if you wish to make exact the time of the beginning of the stay and the time of the beginning of the clearing, you subtract the minutes of the stay that I told you to divide by the gain of the moon, with half their sixth, from the motion in latitude at the time of the opposition, and add them also to the motion in latitude at the time of the opposition, so that you know the motion in latitude for the two times. Then with it you find the latitude of the moon in that way at each of the two times, and subtract it from half the two diameters; you take the excess of the remainder over the diameter of the moon and multiply it by itself, and subtract the product from the total of the minutes of the stay multiplied by itself, and keep what remains to you of each of the two. Then you add to it what lies between the latitude of the moon at the middle of the eclipse and its latitude at that time, take the root of the sum and divide it by the gain of the moon. What results for the time of the beginning you subtract from the hours of the opposition, and what results for the time of the clearing you add to the hours of the opposition: what each of them comes to is the hours of the beginning of the stay and of the beginning of the clearing.[302]

Ar. p. 150

If the moon is not eclipsed whole and you wish to count the digits of the eclipse by computation, so as to know the area of the part of the circle of the moon that falls in the circle of the shadow, in the measure in which the area of the circle of the moon is 12 parts — these are what are called

whole stay.

[301] The plain times are those of the general rule above. Half a sixth is added because the moon moves in latitude about 13/12 as fast as it gains on the shadow, the node also moving backwards. At the contact the moon is the root of $D^2 - b^2$ from the middle in longitude, D being half the two diameters and b the latitude at the contact; with the change of the latitude as the other side, the root gives its path to the middle.

[302] The passage is corrupt in the codex and in Plato of Tivoli. As Schiaparelli restores it (Nallino's commentary), the latitude of the moon at each of the two times is squared and subtracted from the square of the minutes of the whole stay, half the difference of the diameters of the shadow and the moon; the square of the difference between that latitude and the latitude at the middle of the eclipse is added, and the root of the sum is divided by the gain of the moon.

the digits — take half the corrected diameter of the moon and subtract from it 0;14,50, the radius of the moon at its farthest distance. Multiply the remainder by six and divide it by the radius of the moon at its farthest distance mentioned; add the digit, or part of a digit, that results to the six digits that are the radius of the moon at its farthest distance: the digits that result are the digits of the corrected radius of the moon, so keep them. Then double that: the result is the digits of the whole diameter of the moon. Multiply them by 3 parts 8½ minutes: that is the measure of the circumference of the moon. Take half of it and multiply it by the digits of the radius of the moon: the result is the area of the circle of the moon, so keep it. Then take the excess of the corrected radius of the shadow over 0;38,30, double it, multiply the result by 12 and divide it by 77, the whole diameter of the shadow at the farthest distance; add the digits that result to 31 digits and a fifth of a digit, the least diameter of the shadow, at the farthest distance of the moon: the sum is the digits of the diameter of the shadow. Multiply them by 3 parts 8½ minutes: the result is the circumference of the circle of the shadow. Take half of it and multiply it by the digits of the radius of the shadow: the result is the area of the circle of the shadow. Then add together the digits of the diameter of the shadow and the digits of the diameter of the moon: the sum is the digits of the two diameters, so keep it. Then multiply the digits of the eclipse by the digits of the diameter of the moon and divide the product by 12: the quotient is the corrected digits of the eclipse. Double them and subtract the result from the digits of the two diameters: the remainder is twice the distance between the two centres. Then subtract the corrected digits of the eclipse from the digits of the diameter of the moon, multiply the remainder by the corrected digits of the eclipse, and divide the product by twice the distance between the centres: the result is the sagitta of the circle of the shadow. Subtract it from the corrected digits of the eclipse: the remainder is the sagitta of the circle of the moon. Subtract that from the digits of the diameter of the moon, multiply the remainder by the sagitta of the circle of the moon, and take the root of the product: that is half the common chord, so keep it.[303]

Then take the corrected digits of the eclipse: if they are less than the digits of the radius of the moon, subtract them from the digits of the radius of the moon, and if they are more, subtract from them the digits of the radius of the moon. What results from the shortfall, add to the sagitta of the shadow; what results from the excess, take the difference between it and the sagitta of the shadow. Multiply what results in either way by half the common chord: the product is the area of the triangle of the moon, so keep it. Then take the digits of the radius of the shadow, subtract the sagitta of the shadow from them, and multiply the remainder by half the common chord: the product is the area of the triangle of the shadow, so keep it. Then multiply half the common chord by six, divide the product by the digits of the radius of the moon, and multiply the result by 10 parts, so that it becomes its share of the radius; find its arc from the table of the halved chords. Multiply the arc that results by the digits of a [quarter] of the circumference of the circle of the moon: the result is the share of the arc. Divide it by 90: the result is the arc of the moon. Multiply it by the digits of the radius of the moon: the result is the area of the arc of the moon; keep it in mind. Then take half the common chord again and multiply it by 15 parts and three fifths of a part, which are the digits of the least radius of the shadow; divide the product by the digits of the radius of the shadow, and multiply the result by 3 parts 50 minutes and a half and a quarter of a minute and a [fifth] of a tenth of a minute, so that it becomes its share of the

[303] 0;14,50 is half of 0;29,40, the codex's reading above for the farthest diameter of the moon. With that diameter as 12 digits the 77 minutes of the diameter of the shadow are 31.15 digits, with 0;29,30 they are 31.32; the text has 31⅕. 3;8,30 is Ptolemy's ratio of the circumference to the diameter (*Almagest* VI 7; chapter 3). The corrected digits of the eclipse are the digits on the moon's actual diameter turned into these digits, in which its farthest diameter is 12. With a and c the radii of the shadow and the moon, b the distance of their centres and e the corrected digits, e = a + c − b, the sagitta of the shadow is e(2c − e)/2b, the sagitta of the moon is e less that, and half the common chord is the root of the sagitta of the moon times the diameter of the moon less that sagitta. Schiaparelli, who proves these rules in Nallino's commentary, did not remember finding them in other writers and calls the solution most elegant. The translation reads «التي» for «الني» (p. 149, line 12), a misprint that the corrigenda do not list, and follows the corrigenda in reading «ونُخْمس», «and a fifth», for «وخُمْس» (p. 149, line 17).

radius; find its arc in the tables of the halved chords. Multiply the arc that results by a quarter of the circumference of the circle of the shadow and divide by 90: the result is the arc of the shadow. Multiply it by the digits of the radius of the shadow: the result is the area of the arc of the shadow. Add it to the area of the arc of the moon, and subtract from the sum the area of the triangle of the moon together with the area of the triangle of the shadow: the remainder is the area of the eclipsed segment of the circle of the moon. Multiply it by 12 and divide by the area of the circle of the moon that you kept at the beginning: the digits that result are the amount of the circle of the moon that is eclipsed, in the measure in which its whole area is 12.[304]

Ar. p. 151

If you wish to know the azimuth of the side from which the darkening begins on the circle of the moon, and the side from which it clears, on the circle of the horizon, and the figure of the eclipse, set up the ascendant of each of the times of the eclipse and find the azimuth of the ascendant of each of them on the circle of the horizon in the manner given at the beginning of the book. Then take the latitude of the moon at the time of the beginning of the eclipse and at the time of the end of the clearing, if the moon is not eclipsed whole; if the moon is eclipsed whole and has a stay, take also its latitude at the beginning of the clearing. Multiply each of the latitudes that you have by the radius and keep the products. Divide what results for the beginning of the stay and the beginning of the clearing by all the minutes of the whole stay, and what results for the beginning of the eclipse and the end of the clearing by half the two diameters: what results is degrees. Find their arc in the table of the halved chords: the arc for each of those times is the amount of the deviation of the darkening of the eclipse at that time; keep each of them with its side. If the true centre of the moon is on the belt of the signs, I mean that it has no latitude, at one of the times: if that is at the beginning of the eclipse or the beginning of the clearing, the beginning of the darkening and the beginning of the clearing are on the side of the azimuth of the ascendant at each of the two times; if it is at the beginning of the stay or the end of the clearing, both are on the side of the azimuth of the setting degree at each of the two times.[305]

If the moon is not on the belt of the signs but has a latitude on one of the two sides, lay off the deviation of the eclipse at the time of the beginning of the eclipse and of the end of the clearing: at the time of the beginning of the eclipse, from the limit of the azimuth of the ascendant at the beginning of the eclipse on the circle of the horizon, towards the side opposite to the latitude of the moon; at the time of the end of the clearing, from the limit of the azimuth of its setting degree, again towards the side opposite to the latitude of the moon. At the time of the beginning of the clearing and the time of the beginning of the stay, you lay off the deviation of the darkening of the eclipse at the time of the beginning of the clearing from the limit of the azimuth of the degree that rises at it, towards the side of the latitude of the moon, and likewise you lay off the deviation at the time of the beginning of the stay from the limit of the azimuth of the degree that sets at it, towards the side of the latitude of the moon. Where the count ends for you on the circle of the horizon at each of the times, towards the azimuth of that part of the circle of the horizon is the deviation of the darkening and of the clearing on the circle of the moon.

Ar. p. 152

[304] Where the text has «the sagitta of the shadow» in this paragraph, the codex and Plato of Tivoli have «the circle of the moon»; Nallino corrects them, and Schiaparelli's proof confirms the correction. «Quarter» is supplied by Nallino after Plato, and «fifth» is Nallino's conjecture for a word eaten by worms: 60/15⅗ = 3;50,46 (Nallino). Half the common chord over the radius, in a radius of 60, is the sine of half the angle of the eclipsed arc at the centre; the arc so found, as a length, times the radius is the area of the whole sector, and the sector less the triangle is the segment, for the moon and for the shadow alike (Schiaparelli, in Nallino's commentary). As given, the rule is exact while the common chord lies between the centres of the moon and the shadow. In a deeper eclipse, where the excess of the corrected digits over the radius of the moon is greater than the sagitta of the shadow, the eclipsed segment of the moon is more than half its disc: the table of the halved chords then gives the smaller arc where the larger is needed, and the triangle of the moon has to be added, not subtracted, so that the rule gives too little.

[305] The azimuth of the ascendant is found as in chapter 7; such azimuths are amplitudes, counted from the east and the west points (Nallino). The latitude times the radius, divided by the distance of the centres at the contact, is the sine of the angle that the line of the centres makes with the ecliptic; the darkening begins, or the clearing ends, where that line meets the edge of the moon.

If the moon is not eclipsed whole, the deviation of the darkening at the middle of the eclipse always falls at a right angle to the ecliptic, where it is bounded by the arc that passes through the two poles of the ecliptic, through the place of the moon and through the circle of the horizon. You know it by taking the angle of longitude known for the time of the middle of the eclipse, in the way that we described in finding it for knowing the parallax of the moon, and laying it off from the limit of the azimuth of the ascendant at the middle of the eclipse towards the side opposite to the latitude of the moon, when the moon is towards the east; when it is towards the west, you lay it off from the limit of the azimuth of the setting degree at the middle of the eclipse, again towards the side opposite to the latitude of the moon. Where the count ends for you on the circle of the horizon, to that part of it runs the inclination of the azimuth of the darkening at the middle of the eclipse. This is when the latitude of the moon is to the north; when it is to the south and the moon is on the eastern side, you lay off the angle from the azimuth of the setting degree, and when it is on the western side, from the azimuth of the ascendant, towards the side opposite to the latitude of the moon.[306]

If you wish to know the eclipse of the moon approximately by the table, enter with the true latitude of the moon at the time of the opposition into the two tables of the eclipse of the moon, for the farthest distance and for the nearest distance. If you find it in the table of the nearest distance alone and not in that of the farthest, take what stands opposite it of the digits and the minutes of the fall, and take of each of them the part that the minutes of the shares of the distance, set down in the third column of the tables of the computation opposite the corrected anomaly of the moon at the time of the opposition, are of 60 minutes: what results of each of them is the amount of the digits of the eclipse and the amount of the fall. If the latitude of the moon falls in both tables, take what stands opposite it in each of them of the digits, the fall and the stay, if the moon has a stay, and write down what comes from each of the two tables on its own side. Take the difference between the two tables in the digits, the fall and the stay, and take of each of these differences the part that the minutes of the third column of the tables of the computation, opposite the anomaly of the moon, are of 60 minutes; always add what results from each of them to its counterpart from the first table, that of the farthest distance. What the digits of the first table and the minutes of the fall and the stay in it come to after the addition is the digits of the eclipse of the diameter of the moon, the amount of the fall, and the amount of the stay, if you find a stay for the moon. If these digits are less than 12, the moon is not eclipsed whole, and you will find no stay for it then; if they are more than 12, the moon is eclipsed whole and has a stay according to how far it enters the darkness; and if the digits are exactly 12, the moon is just eclipsed whole.

Ar. p. 153

Then divide the minutes of the fall by the gain of the moon, and likewise the minutes of the stay, if the moon has a stay: the results are the hours of the fall and the hours of the stay, if the moon has a stay. If you find no stay for it, subtract the hours of the fall from the hours of the opposition: the remainder is the hours of the beginning of the eclipse; and add them also to the hours of the opposition: the sum is the hours of the end of the clearing. The hours of the middle of the eclipse are the hours of the opposition. If the moon has a stay, add the hours of the fall and of the stay together and subtract the sum from the hours of the opposition: the remainder is the hours of the beginning of the eclipse; add it also to the hours of the opposition: the sum is the hours of the end of the clearing. Then subtract the hours of the stay alone from the hours of the opposition: the remainder is the hours of the beginning of the stay; and add them also to the hours of the opposition: the sum is the hours of the beginning of the clearing, approximately. If the digits of the eclipse are less than 12, enter with them into the table of the amounts of the eclipses, in the column of numbers, and take what is under them in the second column, headed «amounts of the eclipse of the moon»: what there is, is the amount of the circle of the moon that

[306] The angle of longitude is the one found for the parallax in chapter 39. At the middle of the eclipse the centres of the moon and the shadow differ only in latitude, so that the line of the centres is at right angles to the ecliptic.


is eclipsed, in the measure in which its area is 12.

If you wish to know the side from which the darkening of the eclipse begins and the side from which the clearing ends, enter with the digits of the eclipse, those of the diameter of the moon, in the column of the number of the digits of the tables of the deviations of the darkenings, and take what stands opposite them in the third column, and also in the fourth column if the moon has a stay. What results from the third column is the deviation at the time of the beginning of the eclipse and of the end of the clearing, and what results from the fourth column is the deviation at the time of the stay and of the beginning of the clearing; keep it. Then look in the circle of the azimuths, in which the seven circles for the seven climes are drawn, and take the azimuth set down under the rising and the setting sign in the clime in question and under the sign that follows it. Then take the difference between the azimuths of the two signs, multiply it by the degrees of the ascendant, and divide the product by 30; add the result to the azimuth of the rising sign if that is the smaller, and subtract it if that is the greater. What the azimuth of the ascendant or of the setting point comes to after the addition or the subtraction is the azimuth of the degree of the ascendant at each time and of its setting degree. Know that the azimuth of the setting point is like the azimuth of the ascendant, on the opposite side: if the azimuth of the ascendant is northern, the azimuth of the setting point is southern, so whichever of the two azimuths you know, you know the other by it. The side of the azimuth is known from the drawing of the circle, by the marked directions on which the summer and the winter risings and settings fall, the summer ones being northern and the winter ones southern.[307]

Ar. p. 154

When you know that, lay off the parts of the third column from the limit of the azimuth of the ascendant at the beginning of the eclipse towards the side opposite to the latitude, I mean the latitude of the moon, and lay them off also from the limit of the azimuth of the setting point at the end of the clearing towards the side opposite to the latitude of the moon. If the moon has a stay, you lay off the parts of the fourth column from the limit of the azimuth of the setting point at the beginning of the stay and from the limit of the azimuth of the degree that rises at the beginning of the clearing, towards the side of the latitude of the moon. Where the count ends for you on the circle of the horizon is the azimuth of the darkening and of the clearing that occur on the circle of the moon. This is the figure of the eclipse in its position, with the directions of the darkening and the clearing in it, if God wills.

[307] The circle of the azimuths, with seven circles for the seven climes, is a diagram in the codex (Nallino); its azimuths are amplitudes, counted from the east and the west points (chapter 7). The azimuth of a degree between the tabulated signs is found by proportion.



Ar. p. 155

Al-Battānī said: We begin, with the help of God, by drawing a straight line and dividing it into as many equal parts as you wish, provided they are as many as the number of half the two diameters or more. Then take from this line the amount of half the two diameters and draw a circle with it: this is the circle of half the two diameters, on which the centre of the moon falls at the time of the beginning and at the end of the clearing. Then take also the amount of the radius of the shadow and draw with it, about the centre of the first circle, a circle that falls inside that circle: this is the circle of the shadow. Then divide the two circles into equal quarters, and write on the ends of the lines the directions of the east, the west, the north and the south. Then take from the divided line, with the compasses, the amount of the latitude of the moon at the middle of the eclipse; put one of the two ends on the centre of the two circles and turn the other end towards the side of the latitude of the moon. Where it falls on the line of the north or of the south, mark a sign on the line, which is the centre of the moon at the middle of the eclipse. Then take from that line also the amount of the latitude of the moon at the beginning of the eclipse, do the same with it, and mark a second sign at its place on the line, on the side of the latitude of the moon; do the same with the latitude of the moon at the end of the clearing and mark another sign at its place on the line, on the side of the latitude. Then from the two signs of the latitude of the moon at the beginning of the eclipse and at the end of the clearing draw lines parallel to the line between the east and the west: the one for the beginning of the eclipse you draw towards the west from the centre of the circle, and let the one for the end of the clearing be drawn from the centre of the circle towards the east. Mark two signs where the two lines meet the circumference of the circle of half the two diameters, and join them by a straight line, which passes through the centre of the moon at the middle of the eclipse: on that line is the passage of the moon from the beginning of the eclipse to the end of the clearing. The line from the western circumference of the circle to the sign of the latitude of the moon at the middle of the eclipse is the amount of the minutes of the fall and the stay from the beginning of the eclipse to its middle, and the line that remains, from that sign to the eastern point of the circle, is the amount of the minutes of the fall and the stay from the middle of the eclipse to the end of the clearing; necessarily each of the two lines differs from the other in amount.[308]

Then take from the divided line the radius of the moon as well, and draw with it three circles.

[308]The translation follows the corrigenda in reading «القطرَيْن», «the two diameters», for «القطربْن» (p. 154, line 10).

The centre of one of them is the western point of the circle of half the two diameters, where the parallel line meets it, and the centre of the second circle the eastern point of the circle. These two circles each necessarily touch the circle of the shadow: the one about the western centre is the circle of the moon at the beginning of the eclipse, and the one about the eastern centre is its circle at the end of the clearing. As for the circle whose centre is the sign of the latitude of the moon at the middle of the eclipse: if it falls wholly within the circle of the shadow, the moon is eclipsed whole and stays in the darkness according to what lies between its circle and the circle of the shadow; if the circle of the moon is inside the circle of the shadow and touches it, the moon is eclipsed whole and has no stay; and if the circle of the moon does not fall wholly within the circle of the shadow, as much of the circle of the moon is eclipsed as the circle of the shadow cuts off from it, which is the segment that falls in the circle of the shadow, whose diameter and area are known.

Ar. p. 156

Let the example of this be the circle of the two diameters, on which are K and M, about the centre Z, and the circle of the shadow inside it, on which are S and Ḥ, whose centre is also the point Z. Since we wish to show the azimuth of the deviation of the darkenings and of the clearing on the circle of the horizon, we draw also about the centre Z a third, great circle, with the circle of half the two diameters inside it; let this circle be for the horizon, and mark on it A, B, G, D. We divide the three circles into quarters by two lines that intersect at the centre Z at right angles, the diameters AG and BD; let the sign A be the point of the south, the sign G the point of the north, the sign B the point of the east and the sign D the point of the west. We take the latitude of the moon to the south, and mark on its latitude at the beginning of the eclipse the point Ṭ, on its latitude at the middle of the eclipse the point H, and on its latitude at the end of the clearing the point L. We draw the two lines ṬK and LM parallel to the diameter BD, and join the point K to the point M by a line that passes through the point H. So the point K is the centre of the circle of the moon at the beginning of the eclipse and the point M the centre of its circle at the end of the clearing, and the line KHM passes through the three centres of the circles of the moon; on it is the passage of the moon from the beginning of the eclipse to the end of the clearing. It is clear that the circle whose centre is K touches the circle of the shadow at the sign S, and the one whose centre is M touches the circle of the shadow at the point Ḥ. Therefore, when the line M Ḥ Z LA and the line KSZQ are drawn, the line KSZQ is the azimuth of the beginning of the eclipse on the circle ABGD, bounded by the arc BQ, and the line M Ḥ Z LA the azimuth of the end of the clearing on the circle ABGD, bounded by the arc D LA. It is known that the point D is the azimuth of the setting degree and the point B the azimuth of the ascendant at every time. Since each of the triangles ZṬK and ZLM is right-angled, and each of the lines ZK and ZM is the known amount of half the two diameters, and each of the lines ZṬ and ZL is also known, each of the lines ṬK and LM, the remaining sides of the two triangles, is known as well. Again, since the angles of the triangles MLH and KṬH at L and Ṭ are right, and each of the lines LH and ṬH is of known amount, each of the lines KH and HM is of known amount: they are the amount of the fall and the stay, KH from the beginning of the eclipse to its middle and HM from the middle of the eclipse to the end of the clearing. It is clear in this figure, mentioned above, that the line KH is greater than the line HM. That is what we wished to show.[309]

It is clear also that if the circle of the moon whose centre is H, for the middle of the eclipse, enters the circle of the shadow and does not touch it on any side, the moon is eclipsed whole and enters the darkness by the amount of the stay, according to what lies between the two circles; and that the azimuth of the darkening at the middle of the eclipse, if the moon is not eclipsed whole, is always on the line ZḌ, which is at right angles to the ecliptic. For the line BD is always the line of half the ecliptic, since the point B is the point of the east from which the ascendant rises and the point D the point of the west from which the setting degree is known on the circle of the

[309]The translation reads «at the beginning of the eclipse» for K with Nallino's translation, as the construction requires; the text has «at the middle of the eclipse».

horizon; wherever [the line ZḌ] falls on it, by its distance from the point of the east or of the west, to that point the azimuth of the darkening at the middle of the eclipse inclines.[310]

Chapter 44. On knowing the eclipse of the sun, its amounts and its times in every locality, and the directions of its darkening and of its clearing, by computation and by the table

Ar. p. 157

Al-Battānī said: If you wish to compute the eclipse of the sun, examine the conjunctions of the sun and the moon. If the mean motion in latitude falls in them between the eclipse limits set down for the sun at the top of the page of the months of the conjunction and the full moon, the sun can be eclipsed; if it is more than that or less, it cannot be eclipsed in any of the climes. If you know that it can be eclipsed, examine the time of the conjunction, whether it falls in the daytime or near sunrise or sunset, so as to know, if an eclipse occurs, whether it can be seen whole or in part.[311]

Ar. p. 158

When you know that something of it is possible, find the true equal hours of the conjunction after noon in the locality that you want, and set up the ascendant and the middle of the sky on the ecliptic at that time. Then find the parallax of the moon in longitude only, by the computation of the angles and of the arcs of distance from the zenith on the circle of altitude, as I have explained at the beginning of the book, from the parallax on the circle of altitude less the parallax of the sun, found in that manner. Divide the result by the unequal motion of the moon in an hour: the result is the hours of the first parallax. If the distance of the degree of the conjunction from the ascendant is less than 90, the moon is in the eastern quarter of the sphere: subtract the hours of the first parallax from the hours of the conjunction, and the minutes of the parallax from the position of the moon and its anomaly at the time of the conjunction. If the distance of the degree of the conjunction from the ascendant is more than 90, the moon is in the western quarter: add the hours of the first parallax to the hours of the conjunction, and the minutes of the parallax to the position of the moon and its anomaly. With what the hours of the conjunction come to after the addition or the subtraction, find the ascendant again, and find the parallax of the moon in longitude again in the same way, with the second position of the moon and its anomaly. Divide what you obtain of this second parallax by the gain of the moon on the sun in that hour: the hour or part of an hour that results is the hours of the second parallax. Subtract them from the hours of the true conjunction if the distance of the moon from this second ascendant is less than 90, and subtract the minutes of the second parallax from the position of the moon and its anomaly; if the distance of the moon from this second ascendant is more than 90, add the hours of the second parallax to the hours of the true conjunction, and the minutes of the second parallax to the position of the moon and its anomaly. By «the position of the moon and its anomaly» I mean its position at the time of the true conjunction: so cancel what you had written down on account of the first parallax.[312]

With the hours of the second conjunction that result, I mean these last ones, find the ascendant and the middle of the sky as usual, and with it and with the position of the moon and its anomaly find the parallax in longitude a third time in the very same way. If this third parallax is exactly equal to the second, the hours that you obtained for the conjunction with the hours of the second parallax are the hours of the middle of the eclipse, for the amount of the parallax in longitude is then equal to the minutes between the sun and the moon at that time, without excess or shortfall. If the third parallax is more than the second, the parallax at that time is more than the minutes between the sun and the moon at it by the excess of the third parallax over the second; if the third

[310] The bracketed words follow Nallino's translation.

[311] In the codex the limits stand on the same pages as those of the moon (Nallino; chapter 43).

[312] The parallax in longitude is found as in chapter 39. Between the ascendant and the point 90 parts from it the parallax increases the longitude of the moon, so that the visible conjunction comes before the true one; beyond that point it comes after.

parallax is less than the second, you know that the parallax at that time is less than the minutes between the sun and the moon at it by the amount by which the third parallax falls short of the second. Therefore the time must be found at which the amount between the sun and the moon is equal to the parallax of the moon in longitude at it, so that it is the middle of the visible eclipse. Finding it, and the way of knowing it, are as I describe.[313]

Ar. p. 159

Look: if the parallax is more than the second parallax, subtract from the hours that you have obtained an amount that does not take you out of the whole hour. That is: if the hours that you have obtained, with which you found the third parallax, have a fraction with them, and it is more than a sixth of an hour, subtract a sixth of an hour from them; if it is less than a sixth of an hour, subtract an eighth or a tenth of an hour from them, as is possible, and as does not require you to break an hour from the hours. Use this subtraction if the distance of the moon from the ascendant is then less than 90; if the distance of the moon from the ascendant is more than 90, use addition instead of subtraction on the same condition, namely that what you add to those hours does not make up a whole hour: if the fraction is less than a half and a third, add a sixth of an hour to it, and if it is more than a half and a third, add an eighth of an hour, an amount that does not complete an hour. I have told you this only for finding it from the tables of Theon, which are set up for the climes, so that the difference of the parallax does not go outside that hour. If you work it with the arcs and the angles, you use only the addition of a sixth of an hour and the subtraction of a sixth of an hour. Then find the parallax in longitude with the hours that result after the addition or the subtraction of the sixth. Of the parallax that you obtain at whichever of the two times you use, see what exceeds the third parallax, and multiply it by six if you worked it with the angles, and likewise with the tables of Theon if you used a sixth of an hour in the addition or the subtraction; if you used an eighth of an hour, multiply it by eight, and likewise if you used a tenth of an hour, multiply it by ten, so that what results is the amount for an equal hour. When you have done that, subtract it from the gain of the moon on the sun in that hour: the remainder is the corrected motion. Divide by it the excess of the third parallax over the second: the result is a part of an hour. Add it to the hours of the parallax found with the gain of the moon: the sum is the corrected hours of the second parallax; keep them.[314]

If the third parallax is less than the second, you work the other way round from what you did at first: add a sixth of an hour to the hours that you have obtained if the distance of the moon from the ascendant is less than 90, and subtract a sixth of an hour if the distance of the moon from the ascendant is more than 90. With the hours that result, find the parallax in longitude at the time that you obtain of the two times, in that way; then see the shortfall relative to the third parallax and multiply it by six; if you used less than the sixth, such as the eighth or the tenth, make the multiplier accordingly, so that it comes to a whole hour. Add the product to the gain of the moon on the sun at that time: the sum is the corrected motion. Divide by it what the third parallax falls short of the second: the quotient is a part of an hour; subtract it from the hours of the second parallax — and say that this does not happen except when the moon is near the horizon, the difference between the two parallaxes being small then. The remainder is the

[313] Nallino prints the two sentences on the third parallax being more or less than the second in italics, and Schiaparelli calls them false: that the difference of the two parallaxes and the difference of the visible longitudes agree when both are nothing does not make them agree when they are something (Nallino's commentary). The sentences are correct. The hours of the second parallax are the second parallax divided by the gain of the moon, so at the new time the true moon is exactly the second parallax away from the sun; the parallax at that time is the third, and it exceeds the minutes between the sun and the moon by the excess of the third over the second, the gain being taken as uniform over those hours. Schiaparelli's objection therefore fails, and with it Schiaparelli's claim that al-Battānī divides the wrong quantity by the corrected motion below. In a numerical test with a smoothly changing parallax, the rules bring the time within about a second of the visible conjunction, where the second parallax alone leaves an error of minutes.

[314] Theon's tables give the parallax for whole hours from noon in each clime; with them a fraction below a sixth is taken off, an eighth or a tenth, so that the second time falls on a whole hour of the table (Schiaparelli, in Nallino's commentary). Over so short a time the change of the parallax can be taken as uniform; the corrected motion, the gain less the change of the parallax in an hour, is the gain of the visible moon on the sun (Schiaparelli).

corrected hours of the second parallax.

Ar. p. 160

When you know the corrected hours of the second parallax, multiply them by the unequal course of the moon in an hour and by the unequal course of the sun in an hour, and find the amount of each product. If the distance of the moon from the ascendant is less than 90, subtract the corrected hours of the second parallax from the hours of the true conjunction; subtract what results of the course of the moon from the position of the moon at the time of the true conjunction, from the anomaly of the moon and from the motion in latitude as well, and subtract also from the motion in latitude the motion of the northern node in the corrected hours of the second parallax; and subtract what results for the sun from the position of the sun — the position of the sun and of the moon is, as is known, the position of the conjunction. If the distance of the moon from the ascendant is more than 90, use addition instead of subtraction in everything that I have described to you. What the hours of the true conjunction come to after the addition or the subtraction are the hours of the middle of the visible eclipse, with the positions of the sun and the moon, the anomaly of the moon and the motion in latitude at it. Likewise, if the third parallax is exactly equal to the second, you multiply the hours of the second parallax, which have then become the corrected ones, by the course of the moon, of the sun and of the northern node in an hour, and add the products to the positions of the sun and the moon, the anomaly of the moon and the motion in latitude if you added the hours to the hours of the conjunction, and subtract them from these positions if you subtracted those hours from the hours of the conjunction; you use the motion of the node in the motion in latitude only and in nothing else, so that the position of each of them comes out right in truth. Necessarily, the amount of the parallax in longitude that you obtain at that time is then equal to what lies between the sun and the moon. It is known also that if the distance of the moon from the ascendant at the time of the true conjunction is 90, the hours of the true conjunction are the hours of the middle of the eclipse without difference, and likewise the position of the conjunction is the visible position of the moon and the position of the sun together.[315]

Ar. p. 161

Then set up the ascendant for the middle of the eclipse, and with it and with the position of the moon at it find the parallax of the moon in latitude in that way, which is the procedure given before; then the true latitude of the moon, from the corrected motion in latitude for the middle of the eclipse, in that way, either by the table or by computation. Find the side of this true latitude and the side of the parallax in latitude. If the true latitude of the moon and its parallax in latitude are on one side, add them together; if they differ, subtract the smaller from the greater and find the side of the remainder. What results after the addition or the subtraction is the visible latitude of the moon on the side on which it falls at the middle of the eclipse. If it is more than 0;34,30, the sun is not eclipsed; if it is less, it is eclipsed, though it may not be eclipsed until the visible latitude of the moon comes down to 0;30,25; if it is less than that, the eclipse is certain. The doubt arises only between 0;34,30 and 0;30,25, because of what the radii of the sun and the moon can come to together at their distances from the centre of the earth.[316]

When you know that the sun is eclipsed, or that it can be eclipsed, take the anomaly of the moon for the middle of the eclipse, enter with it in the two columns of numbers of the tables of the computation, and find the minutes of the third column that are under it. Find what part of 60 the result is, and take that part of the 2 minutes and a quarter of a minute by which the diameter of the sun, relative to the moon, varies between the farthest and the nearest distance of the sun; add the result to 0;31,20, the diameter of the sun at its farthest distance: the sum is the corrected diameter of the sun. [If you wish to know that by computation, you should correct the arcs for

[315] The motion of the node goes with the moon's in the motion in latitude, because that is counted from the northern node, which moves backwards.

[316] The translation reads «in latitude» with Nallino's translation, as the sense requires; the text has «in longitude» (p. 160, line 19). 0;34,30 and 0;30,25 are the greatest and the least sum of the radii of the sun and the moon, half of 0;33,40 + 0;35,20 and of 0;31,20 + 0;29,30 (Schiaparelli, in Nallino's commentary); the codex has 0;36,39 and 0;34,36.

the degree of the moon from the zenith, and the angles too, with the latitude of the moon in that way, for that is more correct for the computation.] When you know the diameter of the sun in whichever of the two ways you wish, find the diameter of the moon in the way given for the eclipse of the moon. Then add together the corrected diameter of the sun and the corrected diameter of the moon and take half the sum: the result is half the two diameters; keep it. If the visible latitude of the moon is equal to half the two diameters or more than it, the sun is not eclipsed; if it is less than half the two diameters, it is eclipsed. When you know that it is certainly eclipsed, subtract the visible latitude of the moon from half the two diameters: the remainder is the amount of the diameter of the sun that is eclipsed. Multiply it by 12 and divide the product by the corrected diameter of the sun: the quotient is the digits of the eclipse by which the sun is eclipsed, in the measure in which its whole diameter is 12 parts; they are called the digits.[317]

Ar. p. 162

Then multiply the visible latitude of the moon by itself and subtract the product from half the two diameters, also multiplied by itself; take the root of the remainder: the result is the plain minutes of the fall. Divide them by the gain of the moon in an hour: the quotient is the hours of the fall. Subtract them from the hours of the middle of the eclipse: the remainder is the hours of the plain beginning of the eclipse; and add them also to the plain hours of the middle of the eclipse: the sum is the hours of the plain end of the clearing. Then find the motion of the sun and the moon in the hours of the fall by multiplying the hours of the fall by the course of the sun and of the moon in an hour, as usual, and keep what results for each of them. Then subtract what results for the sun from the true position of the sun for the middle of the eclipse, and what results for the moon from the true position of the moon for the middle of the eclipse, from the anomaly of the moon and from the motion in latitude; and add it also to these positions mentioned for the middle of the eclipse, using in the motion in latitude alone, besides, the addition and the subtraction of the course of the node in the hours of the fall. The diminished positions are their positions for the plain beginning, and the increased positions their positions at the plain clearing. Then find the true latitude of the moon at each of the two times from the motion in latitude at it, and find the side of the latitude. Then set up the ascendant of each of the two times, and find the parallax of the moon at it in longitude and in latitude in the very same ways, so that the visible position of the moon in longitude and in latitude comes out right for you as usual. Then multiply the visible latitude of the moon at each of the two times by itself, subtract it from half the two diameters multiplied by itself, and take the root of the remainder: that is the minutes of the fall for each of the two times. Write down the minutes of the fall of each time apart, with its side, and find the excess between the sun and the moon, with the visible position of the moon and the true position of the sun, at each of the two times.

If the minutes of the fall that result for the time of the plain beginning are equal to the minutes between the sun and the moon at it, the time of the plain beginning is the time of the actual visible beginning; and if the minutes of the fall for the plain clearing are also equal to the minutes between the sun and the moon at it, it goes the same way, without difference. If that differs at one of the two times or at both, the time of the actual visible beginning is not the same as the time of the plain beginning, nor is the time of the clearing either. That happens only because of the parallax of the moon in longitude and its changes at those times. The correction of the computation is as I describe. Look at the plain beginning and the plain clearing that you have found before, the positions of the moon at them corrected by its parallax in longitude, which are its visible positions, and the parallax of the moon in longitude that you obtained at them, and set these down as they are.

Ar. p. 163

[317] The translation follows Nallino's emendanda (Part II, p. XXXI), with Plato of Tivoli, in reading «القمر», «the moon», for «الشمس», «the sun» (p. 161, line 3). The diameter of the sun varies from 0;31,20 to 0;33,40 (chapter 30), by 2⅓ minutes; «a quarter» is perhaps an error of the archetype for «a third» (Nallino). The bracketed passage, which Nallino prints in brackets, has nothing to do with the diameter of the sun; Schiaparelli takes it for an unskilled substitute for a lost rule, perhaps one finding the diameter of the sun from its hourly motion, since al-Battānī makes the two proportional in chapter 30 (Nallino's commentary).

Then look at the time of the plain beginning. If the minutes between the sun and the moon at it are less than the minutes of the fall of the plain beginning, you know that the moon covered the sun before the time of the plain beginning. So subtract a sixth of an hour from the hours of the plain beginning, then set up the ascendant and find the parallax of the moon in longitude in that way. If this parallax is more than the parallax of the plain beginning, take the excess and multiply it by six, so that it comes to a whole hour, and subtract that from the gain of the moon; if it is less, multiply the shortfall by six and add it to the gain of the moon. What the gain of the moon comes to is the corrected motion. Divide by this corrected motion the difference between the minutes between the sun and the moon at the time of the plain beginning and its minutes of the fall: the result is a part of an hour; subtract it from the hours of the plain beginning. If the minutes between the sun and the moon are more than the minutes of the fall, the moon has not reached the place at which it can cover anything of the sun: add a sixth of an hour to the hours of the plain beginning and find the parallax of the moon in longitude in that manner. If this parallax is more than the parallax of the plain beginning, take the excess, multiply it by six and add it to the gain of the moon; if it is less, multiply the shortfall by six and subtract the product from the gain of the moon. What the gain of the moon comes to after that is the corrected motion. Divide by this corrected motion the difference between the minutes between the sun and the moon and the minutes of the fall: the result is a part of an hour; add it to the hours of the plain beginning. What they come to after the addition or the subtraction is the hours of the visible beginning.

Ar. p. 164

At the time of the plain clearing, if the minutes between the sun and the moon at it are more than its minutes of the fall, you know that the moon has passed the place at which it covers the sun: so subtract a sixth of an hour from the hours of the plain clearing, and find the parallax of the moon in longitude in that manner. If this parallax is more than the parallax of the time of the plain clearing, take the excess, multiply it by six and add it to the gain of the moon; if it is less, take the shortfall, multiply it by six and subtract it from the gain of the moon. What results after that is the corrected motion. Divide by this corrected motion the difference between the minutes between the sun and the moon and the minutes of the fall of the plain clearing: the quotient is a part of an hour; subtract it from the hours of the plain clearing. If the minutes between the sun and the moon at it are less than the minutes of the fall, you know that the moon has not reached the place at which it leaves the sun, and it cannot cover the sun there: so add a sixth of an hour to the hours of the plain clearing, and find with it the parallax of the moon in longitude in the manner given before. If this parallax is more than the parallax of the plain clearing, take the excess, multiply it by six and subtract it from the gain of the moon; if it is less, take the shortfall, multiply it by six and add it to the gain of the moon. What results after the addition or the subtraction is the corrected motion. Divide by this corrected motion the difference between the minutes between the sun and the moon and the minutes of the fall: the result is a part of an hour; add it to the hours of the plain clearing. What they come to after the addition or the subtraction is the hours of the actual visible clearing.

When you know these two visible times, I mean the time of the beginning and the time of the clearing, multiply the part of an hour that resulted for the time of the corrected beginning by the unequal course of the moon in an hour, and add the product to the position of the moon for the time of the plain beginning if the time of the visible beginning is after the plain time, and subtract it if it is before; do the same in the motion in latitude. Likewise multiply the part of an hour that resulted for the clearing by the course of the moon and add the product to the place of the moon and to the motion in latitude at the time of the plain clearing if the time of the visible clearing is after the time of the plain clearing, and subtract it from them if it is before. What the position of the moon and the motion in latitude come to after the addition or the subtraction at each of the two times is its position at it. Set up the ascendant and find the parallax of the moon in latitude then in that way, and find also the latitude of the moon at each of the two times and its side, so as to know the visible latitude of the moon at each of the two times in that manner;

keep it.

If you wish to correct the digits of the eclipse, so as to know the amount of the circle of the sun that is eclipsed to the sight when its whole area is 12, the way of doing it is to make the diameter of the sun always 12 digits, whether its diameter is small or large, and to multiply it by 3 parts 8½ minutes: the product is the circumference of the circle of the sun, which is 37 digits and 42 minutes of a digit. Take half these digits, which is 18;51, and multiply it by the digits of the radius of the sun, which are six: the area of the circle of the sun comes to 113;6. Then take half the corrected diameter of the moon, multiply it by six and divide it by half the corrected diameter of the sun: the quotient is the digits of the radius of the moon; keep them. Then double them: the result is the digits of the whole diameter of the moon. Multiply them by 3 parts 8½ minutes: the product is the circumference of the circle of the moon; keep it. Then add to the digits of the radius of the moon the six digits that are the radius of the sun, and subtract from the sum the digits of the eclipse: the remainder is the amount between the two centres. Double it: the result is twice the distance between the two centres. Then subtract the digits of the eclipse from 12, multiply the remainder by the digits of the eclipse, and divide the product by twice the distance between the two centres: the quotient is the sagitta of the circle of the moon. Subtract it from the digits of the eclipse: the remainder is the sagitta of the circle of the sun. Subtract that from 12, multiply the remainder by the sagitta of the circle of the sun, and take the root of the product: the result is half the common chord; keep it.[318]

Ar. p. 165

Then look: if the digits of the eclipse are less than six, subtract them from six, and if they are more than six, take their excess over six. What results from the shortfall, add to the sagitta of the circle of the moon; what results from the excess, subtract from the sagitta of the circle of the moon. Multiply what the sagitta of the circle of the moon comes to after that by half the common chord: the product is the area of the triangle of the sun; keep it. Then multiply half the common chord by ten, so that it becomes its share of the radius, and find the arc of the product in the tables of the halved chords. Multiply the result by a quarter of the circumference of the circle of the sun, which is 9;25,30, and divide the product by 90: the quotient is the arc of the sun. Multiply it by six digits: the product is the area of the arc of the sun; keep it. Then take the sagitta of the circle of the moon that you obtained after adding to it the shortfall of the digits of the eclipse from six, or subtracting from it their excess over six, and subtract it from the distance between the centres that you kept; multiply the remainder by half the common chord: the product is the area of the triangle of the moon; keep it. Then multiply half the common chord by six, divide by the digits of the radius of the moon, multiply the result by 10 parts, and find the arc of the product. Multiply the arc that results by a quarter of the circumference of the circle of the moon and divide by 90: the result is the arc of the moon. Multiply it by the digits of the [radius] of the moon: the product is the area of the arc of the moon. Add it to the area of the arc of the sun, and subtract from the sum the area of the triangle of the sun together with the area of the triangle of the moon: the remainder is the area of what is eclipsed of the circle of the sun. Multiply it by twelve and divide by 113;6, which has been shown to be the area of the surface of the circle of the sun: the result is the amount of the circle of the sun that is eclipsed, in the measure in which its whole area is 12.[319]

Ar. p. 166

If you wish to know the sides of the darkening of the eclipse and of the clearing on the circle of the horizon, look: if the visible centre of the moon at any one of the times of the eclipse is on the

[318] 12 × 3;8,30 = 37;42, its half 18;51, and 18;51 × 6 = 113;6. The rules are those of chapter 43, with the sun as the eclipsed circle.

[319] The radius of the sun, 6 digits, times ten is the radius 60 of the table of the halved chords (Nallino); the codex has six. The text has «the diameter of the moon» for the area of its arc; Nallino translates «radius», as the rule requires. As in chapter 43, the rule is exact while the common chord lies between the two centres. In a deeper eclipse the chord passes the centre of the sun, which happens when the excess of the digits over six is greater than the sagitta of the circle of the moon, or, when the moon is the smaller, its own centre; one of the two segments is then more than half its circle, the table of the halved chords gives only the smaller arc, and the rule gives too little.

belt of the signs, the beginning of the eclipse is on the side of the azimuth of the setting degree of the ecliptic at that time, and the end of the clearing, when it is possible, is on the side of the azimuth of the ascendant at that time; the middle of the eclipse has no side when the darkness surrounds the whole circle of the sun. If the visible centre of the moon is off the belt of the signs, take the visible latitude of the moon at each of the two times, I mean the time of the visible beginning and the time of the visible clearing, which I told you to compute, to know and to keep, multiply it by sixty and divide by half the two diameters together: what results is degrees. Find their arc from the table of the chords: the arc is the amount of the deviation of the darkening or of the clearing at each of the two times. At the beginning of the eclipse you lay off the deviation of the darkening from the limit of the azimuth of the setting degree at that time on the circle of the horizon, towards the side of the visible latitude of the moon at it; at the end of the clearing you lay off the arc that you obtain from the limit of the azimuth of the ascendant then, towards the side of the visible latitude of the moon at the time of the clearing. At the middle of the eclipse the direction of the darkening is at right angles to the ecliptic, and its azimuth on the circle of the horizon is bounded by the arc that passes through the two poles of the ecliptic, through the centre of the moon and the horizon, according to the distance of the sun and the moon from the equator.[320]

If you wish to know the side of the darkening at the middle of the eclipse, find the angle of longitude at it in the way in which you find it for knowing the parallax of the moon, and lay it off from the limit of the azimuth of the ascendant at the middle of the eclipse, or of its setting degree, on the circle of the horizon, according to the place of the eclipse with respect to one of the two horizons, towards the side of the latitude of the moon. Where it ends on the circle of the horizon, towards the azimuth of that part of the horizon the darkening inclines at the middle of the eclipse: I mean, if the sun is towards the west, you count from the side of the azimuth of the setting degree, and if it is towards the east, from the side of the azimuth of the ascendant.

Ar. p. 167

If you wish to know the eclipse of the sun approximately by the tables, when you know that the sun is eclipsed or that it can be eclipsed, take the distance of the true equal hours of the conjunction from the time of noon in the locality that you want. You find it by converting the hours of the conjunction into hours of that locality; then look: if the conjunction is before noon, subtract the hours from 24 hours, and if it is after noon, before sunset, take the hours themselves. What results in either way is the distance of the hours of the conjunction from the meridian line. With it find the parallax of the moon in longitude from the tables set down for the parallax of the moon in the climes, so as to know its parallax corrected by the fourth column of the tables of the computation for the degree in which the moon is, in that manner. When you know that, divide it by the course of the moon in an hour: the result is the hours of the first parallax. If the distance of the moon from the ascendant is less than 90, subtract the hours of the first parallax from the hours of the true conjunction; if the distance is more than 90, add them to the hours of the conjunction. Then take their distance from noon a second time, and find with it the parallax of the degree of the moon in longitude, corrected by the fourth column of the tables of the computation, in that way: the result is the second parallax. Divide it by the gain of the moon: the quotient is the hours of the second parallax. If the distance of the conjunction, I mean of the degree of the moon, from the ascendant is less than 90, subtract them from the hours of the true conjunction, and if it is more than 90, add them to the hours of the true conjunction. Take their distance from noon a third time as well, and find with it the corrected parallax of the degree of the moon in longitude a third time. If it is equal to the second parallax, the hours that you obtained from the hours of the true conjunction after adding the hours of the second parallax to them, or subtracting them, are the hours of the middle of the eclipse.[321]

[320] The moon passes the sun from west to east, so that the eclipse begins on the western side of the sun and ends on its eastern side.

[321] With the parallax corrected by the fourth column «and the fifth» must be added, here and below, as the rules of chapter 39 show; the words seem to have dropped out already in the archetype, since Plato of Tivoli also lacks them

If the third parallax is more than the second, find its excess over it; then add a sixth of an hour to the hours of the distance of the conjunction from noon that you obtained with the second parallax, and find with that the corrected parallax of the degree of the moon in longitude in that way. Take its excess over the second parallax, multiply it by six and subtract the product from the gain of the moon in an hour: the remainder is the corrected motion. Divide by it the excess of the third parallax over the second, which I told you to keep: the result is a part of an hour; add it to the hours of the second parallax: the sum is the exact hours. If the third parallax is less than the second, take what it falls short of it, multiply it by six and add the product to the gain of the moon: the sum is the corrected motion. Divide by it the shortfall of the third parallax from the second: the result is a part of an hour; subtract it from the hours of the second parallax. What the hours of the second parallax come to after that is the exact hours.[322]

When you know the exact hours of the parallax, in whichever of the two ways they came out, multiply them by the unequal courses of the moon and of the sun in that hour, and keep the product of each of them. If the distance of the moon from the ascendant at that time is less than 90, subtract the exact hours of the second parallax from the hours of the true conjunction, and the motion of the sun in that amount from the position of the conjunction; likewise subtract the motion of the moon from the position of the conjunction, from the anomaly of the moon and from the motion in latitude, and subtract from the motion in latitude besides the course of the node in the amount of the hours of the second parallax. If the distance of the moon from the ascendant is more than 90, use addition instead of subtraction in all of this. What the hours of the true conjunction come to after the addition or the subtraction is the hours of the middle of the eclipse, and likewise the positions of the sun and the moon, the motion in latitude and the anomaly of the moon, corrected for the middle of the eclipse. Then find the latitude of the moon and its side from the motion in latitude at the middle of the eclipse, and keep it.

Ar. p. 168

Then take the distance of the hours of the middle of the eclipse from noon and find with it the parallax of the moon in latitude in that way, after correcting it with the fourth column of the tables of the computation, and find the side of the parallax. If the latitude of the moon and its parallax in latitude are on one side, add them together; if they differ, subtract the smaller from the greater and find the remainder and its side. What results after the addition or the subtraction is the visible latitude of the moon for the middle of the eclipse. Look for the same in the column of the latitude of the moon set down in the two tables of the eclipse of the sun. If you find it in the second table, that for the lesser distance, and do not find it in the greater table, take what is under it in the lesser table of the digits and the minutes of the fall. Then enter with the anomaly of the moon into the tables of the computation and take the minutes of the shares set down under it in the third column; find what part of 60 they are, and take that part of those digits and of the minutes of the fall: what results is the amount of the diameter of the sun that is eclipsed, in digits, and the minutes of the fall are the amount of the eclipse in its duration from its beginning to its middle. If the latitude of the moon falls in both tables, take what is under it in the first, greater table and in the second, lesser one of the digits and the minutes of the fall. Then find the difference between the two tables in the digits and in the minutes of the fall, and take of each the part that the minutes of the third column, opposite the anomaly of the moon in the tables of the computation, are of 60; add what results of the digits to the digits that came from the table of the greater distance, the first, and likewise add what results for the fall to the minutes of the fall of the greater table. What each of them comes to is the amount of the digits of the eclipse and the minutes of the fall. It is known that if you find the latitude of the moon in neither of the two tables, the sun is not eclipsed.

(Nallino). The tables of the parallax in the climes are Theon's.

[322] Here the new parallax is compared with the second, where the rule at the beginning of the chapter compares it with the third, the parallax of the time from which the sixth of an hour is counted. On the excess of the third parallax over the second, see the note on the third parallax above.

Then take the minutes of the fall and divide them by the gain of the moon: the quotient is the hours of the fall. Subtract them from the hours of the middle of the eclipse: the remainder is the hours of the plain beginning; and add them to the hours of the middle of the eclipse: the sum is the hours of the plain clearing.

Ar. p. 169

If you wish to follow in this what I set out at the beginning of the chapter, so as to make right the time of the visible beginning or the time of the visible clearing as explained in that way, you may. If you wish to know it approximately, enter with the hours of the distance of each of these three times from noon into the tables of the parallax set down for the climes, and take what is under each of them in the table of the parallax in longitude only, in the sign of the moon and in the sign that follows it, in that way, so as to know the parallax of the degree of the moon in longitude without correcting it with the fourth column of the tables of the computation, so that the computation is easier. Then find the difference between the parallax of the middle time and that of each of the two times, and divide each of them by the gain of the moon: what results is a part of an hour. Put the hours of the fall that you obtained in two places; add to one of the two places one of the two quotients that you obtained from the parallax, and the other quotient to the other place. Then look at the greater of the two that you have obtained, the hours of the fall with what you added to them, and subtract it from the hours of the middle of the eclipse if the eclipse inclines towards the west from the middle of the sky, between the ascendant and the setting point, which is when the distance of the middle of the eclipse from the ascendant is more than 90; and add the smaller to the hours of the middle of the eclipse. If the eclipse is towards the east, which is when the distance of the middle of the eclipse from the ascendant is less than 90, subtract the smaller of the two from the hours of the middle of the eclipse and add the greater to the hours of the middle of the eclipse. For the longer of the two times always falls near the middle of the sphere, which is midway between the ascendant and the setting point: whichever of the two times inclines towards the middle of the sphere is the longer. When you know what the hours of the middle of the eclipse come to after the addition or the subtraction, the diminished hours are the hours of the beginning of the eclipse and the increased ones the hours of the end of the clearing.[323]

If you wish to correct the digits of the eclipse by the table, enter with these [digits] that you obtain into the tables of the amounts of the eclipse, in the columns of numbers, and take what is under them in the second column, headed «amounts of the eclipse of the sun»: what results is the amount of the eclipse to the sight. Likewise, if you wish to know the sides of the darkening on the circle of the eclipse, enter with the digits of the eclipse that are eclipsed of the diameter of the sun, which are the digits that come from the table before you correct them, into the table of the deviations of the darkenings, and take what stands opposite them in the second column, headed «beginning of the eclipse of the sun and end of its clearing»: what results is the parts of the deviation; keep them. Then find the azimuth of the ascendant and of the setting degree at the time of the beginning and of the clearing, in the manner mentioned, from the circles drawn for the climes, as I explained in the chapter on the eclipse of the moon; and lay off the parts of the deviation themselves from the limit of the azimuth of the ascendant for the end of the clearing, towards the side of the latitude of the moon, and from the limit of the azimuth of the setting degree for the beginning of the eclipse, towards the side of the latitude of the moon. Where you end on the circle of the horizon, there is the azimuth of the darkening and of the clearing on the circle of the horizon.[324]

Ar. p. 170

If you wish to draw the eclipse of the sun in the way in which you drew the eclipse of the moon, take from the divided line the amount of half the two diameters, draw a circle with it, and divide it into quarters by two lines that intersect at the centre at right angles. Then take also from the

[323] Near the point 90 parts from the ascendant the parallax in longitude changes fastest and slows the visible moon most, so that the half of the eclipse nearer that point is the longer.

[324] Part of the word «digits» is supplied by Nallino.


line the amount of the radius of the sun and draw with it a second circle about that first centre: it falls inside the circle of half the two diameters. Write the directions of the horizons on the ends of the lines of the greater circle. Then take from the line also, with the compasses, the amount of the visible latitude of the moon for the beginning of the eclipse: put one of its two ends on the centre of the two circles, turn the other end towards the side of the visible latitude of the moon, and mark where it falls on the line a sign for the beginning of the eclipse. Then take the amount of its latitude for the middle of the eclipse and its latitude for the end of the clearing, and do the same with it, until you have the three signs. Then draw from the sign of the latitude for the beginning of the eclipse, towards the west, a line parallel to the diameter, and from the sign of the end of the clearing, towards the east, a line also parallel to the diameter, and mark two signs at the ends of the two lines on the circumference of the greater circle. Then take from the divided line also the amount of the radius of the moon and draw a circle with it about the sign of the latitude of the moon for the middle of the eclipse: what falls of the circle of the sun within this circle is what is eclipsed of the sun. Draw also another circle about the sign that falls on the western circumference of the circle: it touches the circle of the sun, and it is the circle of the beginning of the eclipse; likewise draw about the eastern sign on the circumference of the circle a third circle, which is the circle of the end of the clearing.[325]

For example, we draw the circle of half the two diameters ABGD about the centre H; let the sign A be the point of the west, the sign B the point of the south, the sign G the point of the east and the sign D the point of the north. We draw the diameters AG and BD, and about the centre H the circle of the sun, on which are Z, K, Ḍ, L. We take the visible latitude of the moon to the north, and mark on the sign of its latitude for the beginning of the eclipse the point ʿ, on its latitude for the middle of the eclipse the sign Ḥ, and on its latitude for the end of the clearing the sign M. We draw the line MS and the line ʿQ parallel to the diameter AG, and draw about the sign Q a circle for the moon at the beginning of the eclipse, which touches the circle of the sun at the point Ṭ; we draw also about the sign S another circle, for the end of the clearing, which touches the circle of the sun at the sign N; and likewise we draw another circle about the sign Ḥ, for the middle of the eclipse, within which falls the segment KḌL of the circle of the sun. We draw the two lines HQ and HS for the azimuth of the darkening and of the clearing. So it is clear that the beginning of the eclipse is from the point Ṭ, which is in the azimuth of the arc AQ of the circle of the horizon.[326]

Ar. p. 171

[325]The translation reads «يتقاطعان», «intersect», for «بتقاطعان» (p. 170, line 2), a misprint that the corrigenda do not list.

[326]Nallino corrects the codex, which has M for ʿ and ʿ for M, and BKḌ for KḌL.



Likewise the end of the clearing is from the point N, which is in the azimuth of the arc SG of the circle of the horizon. It is known that the point A is the azimuth of the setting degree and the sign G the sign of the azimuth of the ascendant. Likewise the azimuth of the middle of the eclipse is at a right angle where the line HD cuts the circle of the horizon, according to its distance from the middle of the sphere and its nearness to the horizon, as we have shown for the moon and the sun. This is enough and covers it; that is what we wished to show, if God wills.

Chapter 45. On knowing the positions of the wandering stars on the ecliptic by the era of the Arabs and of the Romans

Ar. p. 171
Ar. p. 172

Al-Battānī said: If you wish to know the position of whichever of the wandering stars you wish, find the mean position of the star on the day that you want and at the given hour, by the hours of al-Raqqa, by whichever of the two eras you wish, as I described for knowing the mean position of the sun, and find also the mean position of the sun at the same time at which you find the mean position of the star. If your computation is for Saturn, Jupiter or Mars, subtract the mean position of whichever of them you compute from the mean position of the sun: the remainder is the anomaly of the star. If your computation is for Venus or Mercury, what comes out for you from the table is the anomaly of the star, and the mean position of the sun is used in place of their two mean positions, since it is what carries their positions along.[327]

When you know the mean position of the star and its anomaly, subtract the farthest distance of the star from its mean position: the remainder is the centre. Look for the same in the two columns of numbers of the tables of the equation of the star, take what stands opposite it in the third column, headed «the equation of the anomaly and the centre», and write it down under the anomaly and under the centre both. If the centre is less than 180 degrees, subtract the equation from the centre and add it to the anomaly; if the centre is more than 180, add the equation to the centre and subtract it from the anomaly. What each of them comes to after the addition or the subtraction is the corrected centre and the corrected anomaly. Enter with the corrected centre in the two columns of numbers and take what stands opposite it of the minutes of the difference of the two distances, set down in the fourth column, and find whether they are increasing or decreasing. You know this from the mark at the head of the column, or from their increasing or

[327] The mean positions are found as in chapter 33.

decreasing as the number increases — except for Mercury, whose increase and decrease is known only from the mark, because, from the speed of its motion on its epicycle, it comes into the region of its nearest distance twice in a circuit of the signs. If these minutes are decreasing, enter with the corrected anomaly of the star into the tables of the equation of the star, in the two columns of numbers, and take what stands opposite it in the fifth column, headed «the farthest distance», and also in the sixth column, headed «the mean distance»; if the minutes are increasing, take what stands opposite the corrected anomaly in the sixth column and in the seventh column, headed «the nearest distance». Multiply what results from the fifth column by the minutes that you obtained from the fourth column, divide by sixty, and subtract the quotient from what you wrote down from the sixth column; and multiply what results from the seventh column by the minutes of the fourth column, divide by sixty, and add the quotient to what you wrote down from the sixth column. Subtract what the sixth column comes to after the addition or the subtraction from the centre corrected by the third column if the number of the corrected anomaly is more than 180, and add it to it if the corrected anomaly is less than 180. What the centre comes to after the addition or the subtraction is the position of the star from the point of the farthest distance. Add to it the farthest distance of the star, which you subtracted from its mean position at the start: the result is the computed position of the star. Cast it off from the beginning of Aries, thirty for each sign, in the usual way: where it ends, there is the position of the star on the ecliptic.[328]

If there are minutes with the centre or the anomaly, take their share of the difference of the equation and its increments, in the manner that I showed you at the beginning of the book in the equation of the sun and the moon.

Ar. p. 173

The farthest distances of the stars from the earth on their epicycles in the year 1191 of the years of Dhū l-Qarnayn, son of Philip, Alexander, were: Saturn 244;28, Jupiter 164;28, Mars 126;18, Venus 82;14, and the sun the same, Mercury 201;28. We have computed them again, verified them and set them down for each of them at the beginning of the tables of its equation. These distances that we have set down also move with the motion of the sphere of the fixed stars, one degree in every 66 solar years, and one degree in every 68 lunar years too. So take the amount of the motion in the years between this year mentioned and the year that you want: if it is after the year 1191, add it to these distances, and if it is before the year 1191, subtract it from these distances, and work with them in the usual way.[329]

Chapter 46. On knowing the retrogradation of the wandering stars

Ar. p. 173

Al-Battānī said: If you wish to know the retrogradation of one of the wandering stars and its direct motion, enter with the centre of the star corrected by the third column into the two columns of numbers, which go in steps of six parts, in the tables of the retrogradation of the stars, and take what stands opposite it in the column of the star that you want: write down what is in the first column as the first station, and what is in the second column as the second station. When you know the first and the second station, look: if the corrected anomaly of the star is less than the second station and more than the first station, the star is retrograde; if it is more than the second station or less than the first, it is direct in its course. If the star is retrograde and you wish to know how long ago it turned back, subtract the first station from the corrected anomaly and divide the remainder by the course of the anomaly of the star in a day, which is: Saturn 0;57, Jupiter 0;54, Mars 0;28, Venus 0;37, Mercury 3;6. What results is the days since it turned back.

[328] The rules are Ptolemy's. The columns are counted without the two columns of numbers. In Ptolemy's model it is the moving centre of Mercury's eccentric that brings the centre of its epicycle twice in a revolution to a nearest distance (*Almagest* IX 8, cited by Nallino).

[329] The farthest distances meant are those of the eccentrics: on the epicycle the farthest distance comes wherever the anomaly is nothing (Nallino). The year 1191 began on 1 September 879 (Nallino). Nallino would read 126;58 for Mars, «كٛ» for «كج», so that the farthest distances of Saturn and Mars lie equally beyond Ptolemy's (chapter 31). One degree in 66 solar years is one in 68 lunar years (chapter 33).

If you wish to know in how many days it will be direct, subtract the corrected anomaly from the second station and follow this procedure with the remainder. Likewise, if you wish to know when it will turn back while it is direct, subtract its corrected anomaly from the first station and proceed with the remainder in the same way.[330]

Chapter 47. On knowing the latitudes of the five wandering stars

Ar. p. 174

Al-Battānī said: If you wish to know the latitudes of the five wandering stars and their sides: if your computation is for Saturn, Jupiter or Mars, enter with the centre of one of them corrected by the third column — for Saturn with 50 added, for Jupiter with 20 subtracted, and for Mars as it is, without addition or subtraction — in the two columns of numbers of the tables of the latitudes of the five wandering stars, which go in steps of six parts, and take what stands opposite it of the minutes of the shares of the latitude, common to all of them, set down at the end of those tables, which is the ninth column of them; write down what results. If the number with which you entered falls in the upper half, which is half of the numbers, from 0 to 90 and from 270 to 360, enter with the corrected anomaly of the star in the two columns of numbers of those tables, take what stands opposite it in the column of the northern latitude of the star, called *afījiyūn* of the north, and take of it the part that the minutes of the shares of the latitude are of sixty. If it falls in the lower half, which is from 90 to 180 and from 180 to 270, take what stands opposite that corrected anomaly in the column of the southern latitude of the star, called *farījiyūn* of the south, and take of it the part that the minutes of the shares are of sixty. What results, whichever of the two sides it is, is the latitude of the star on the side on which you find it.[331]

Ar. p. 175

If your computation is for Venus or Mercury, enter with their corrected anomaly into those tables, take what stands opposite it in the column of the inclination and the column of the slant, and write down each of them as it is. If your computation is for Venus, leave it as it is. If it is for Mercury alone, and the centre corrected by the third column falls in the upper half mentioned, subtract from the slant alone a tenth of it, I mean one part in ten of it; if it falls in the lower half, add to the slant alone one part in ten of it. What it comes to after the addition or the subtraction is the corrected slant of Mercury; write it down in place of what you obtained from the table, and cancel the first. Then add to the centre corrected by the third column 90 for Venus and 270 for Mercury, and enter with what you have, after casting off the circle if it is more than the circle, into those tables; take what stands opposite it in the ninth column, headed «the shares of the latitude for all». Find what part of sixty the minutes that you obtain are, and take that part of the inclination that you wrote down: the result is the first latitude; keep it. If the number of the centre corrected with the addition for the star, with which you found the minutes of the ninth column, and the corrected anomaly of the star both fall in one half, whichever half it is, upper or lower, the latitude that you wrote down is southern; if they differ, one in one half and the other in the other half, that latitude is northern. Know it with its side.[332]

Then take the centre corrected by the third column, for Venus as it is and for Mercury with 180 added, and enter with what you have of the centre, after casting off the circle if it exceeds it, into those tables as well; take what stands opposite it of the minutes of the shares set down in the ninth column, and write them down in two places. Find what part of sixty one of the two places

[330] The daily motions in anomaly are Ptolemy's, rounded to the minute (*Almagest* IX 3; Nallino); the codex has 0;36 for Venus.

[331] The rules of this chapter are Ptolemy's (*Almagest* XIII 6; Nallino). Adding 50 for Saturn and subtracting 20 for Jupiter counts their centres from the northern limits of their latitudes instead of from their farthest distances. In the codex the column of the shares is the seventh; it would be the ninth in the table of the three upper planets (Nallino). *Afījiyūn* and *farījiyūn* are the Greek *apogeion* and *perigeion*, which al-Battānī took from the Arabic copies of the *Almagest*: in Ptolemy's account the latitude of the three upper planets is northern while the centre of the epicycle is in the half of the eccentric that holds its farthest distance, and southern in the other half (Nallino's commentary).

[332] The inclination and the slant are Ptolemy's *enklisis* and *loxōsis*, the two tilts of the epicycles of Venus and Mercury (Nallino).

is, and take that part of the slant: the result is the second latitude; write it down. If the number with which you found these minutes fell in the upper half and the corrected anomaly is less than 180, what you obtained of the second latitude is northern, and if the anomaly is more than 180, the latitude is southern; if it fell in the lower half and the anomaly is less than 180, the latitude is southern, and if it is more than 180, it is northern. Then take of the minutes that you wrote down in the other place their sixth, if your computation is for Venus, which is always northern, and their half and quarter, if your computation is for Mercury, which is always southern. If these three latitudes fall on one side, add them together; if they differ, cast the smaller from the greater and find the side of the remainder: that is the latitude that results for the star, on the side on which it falls.[333]

Know that the whole latitude of Saturn to the north, as Ptolemy found it, is 3;2, and to the south 3;5; the whole latitude of Jupiter to the north is 2;4 and to the south 2;8; the whole latitude of Mars to the north is 4;21 and to the south 7;7; the whole latitude of Venus, to the north and to the south equally, is 8;56, and the whole latitude of Mercury, to the north and to the south equally, is 4;18 as well.[334]

Ar. p. 176

If you wish to know whether the star is ascending or descending on the side on which it is, compute its latitude after ten days. If it is in the north and you find that its latitude has increased, it is ascending, and if you find that it has decreased, it is descending; if its latitude is in the south and you find it increased, it is descending, and if you find it decreased, it is ascending. If it was in the north and you find that it has passed to the south, you know that it was descending in the north; if it was in the south and you find that it has passed to the north, you know that it was ascending in the south.[335]

Saturn, Jupiter and Mars have another way by which this is known for them: if the latitude of one of them is in the north and its anomaly is less than 180, it is ascending, and if it is more than 180, it is descending; if its latitude is in the south and its anomaly is less than 180, it is descending, and if it is more than 180, it is ascending. As for Venus and Mercury, because of the speed of their motion around the sun, although their greatest latitude comes at their conjunction with it, it is difficult to know their state except in the way given before.[336]

Chapter 48. On knowing the rising of the five wandering stars and their setting, which is their appearing and their disappearing

Ar. p. 176
Ar. p. 177

Al-Battānī said: If you wish to know when the stars come out in the east and when they go down in the west, which is their rising and their disappearing: Saturn, Jupiter and Mars, if the anomaly of each of them is from 0 to 180, are in their morning rising, and from 180 to 360 in their evening setting. Venus and Mercury, because of their circling around the sun and their quickening and slowing, have four configurations with respect to the sun. As for Venus, if its corrected anomaly is from 0 to 137, it is in its evening rising, when it is seen on the western horizon, and it is then faster in motion than the sun; from 137 to 180 it is in its evening setting, when it slows down

[333] The four sides of the second latitude are Nallino's correction; the codex has them the other way round (*Almagest* XIII 6). A sixth and three quarters of the sixty minutes are 0;10 and 0;45, Ptolemy's greatest deviations of Venus to the north and of Mercury to the south. Ibn Yūnus counts an error in the side of the latitude of Mercury among al-Battānī's mistakes; Nallino finds none in the rules or the tables, which agree with Ptolemy's, and suggests that Ibn Yūnus had a faulty copy, like the codex here (Nallino's commentary).

[334] Nallino restores these values from Ptolemy's tables (*Almagest* XIII 5) and from Theon's canon; the codex has several of them wrong, among them 8;2 and 33;5 for Saturn and 6 for both latitudes of Mars, and writes the last two without dots.

[335] Theon's canon has similar rules (Nallino).

[336] «Although» follows Nallino's translation; the text is faulty here (Nallino). «Around the sun» describes the apparent motion of Venus and Mercury to either side of the sun, as in the like phrases of the Greek and Latin writers (Nallino's commentary, after Schiaparelli). Their greatest latitudes come at their conjunctions below the sun (Schiaparelli, in Nallino's note).

and turns back and the sun overtakes it; from 180 to 223 it is in its morning rising, and it is then slower in motion than the sun; and from 223 to 360 it sets in the mornings until it overtakes the sun and disappears in its rays, and it is then faster in motion than the sun. As for Mercury, if its corrected anomaly is from 0 to 112, it rises in the evenings; from 112 to 180 it sets in the evenings; from 180 to 248 it rises in the mornings; and from 248 to 360 it sets in the mornings. Its state of speed and slowness is as we have set out for Venus.[337]

If you wish to know the first appearance of Saturn, Jupiter and Mars in the mornings in the east, which is their first coming out from under the rays to the limit of visibility, the sun having passed them, compute for one of them: if its corrected anomaly is about 20 degrees, say that it is seen. For its setting in the evenings, when the sun overtakes it and hides it and covers it with its rays, you reckon it when the corrected anomaly is about 340. As for Venus and Mercury: if the anomaly of one of them is about 20, that is its first appearance in the evenings in the west; if it is about 340 degrees, that is its first disappearance in the mornings in the east; if it is about 160, that is its first disappearance in the evenings in the west; and if it is about 200, that is its first appearance in the mornings in the east.[338]

If you wish to know the first rising of one of them and its disappearance by computation, find the arc of seeing on the equator for each of them. The amount of the arc of seeing is for Saturn 14 degrees, for Jupiter 12;45, for Mars 14;30, for Venus 5;40 and for Mercury 11;30. Then find the distance of the star from the equator and the degree that culminates with it, according to the latitude that it has, and find with these half the arc of its day, which is half its stay above the earth, and the times of the ascension of the degree with which it rises or sets, in the ways mentioned. If there is between the star and the sun, in degrees of the ascensions or of the settings, as much as the arc of seeing mentioned for it, the star is seen on that day, or disappears. If your computation is for the seeing and the appearance from under the rays, and what lies between it and the sun is less than the arc of seeing, it has not appeared, and if it is more, it has appeared; if your computation is for the disappearance, and the distance between it and the sun in times of the settings or the ascensions, according to the horizon at which it is, is less than the arc of seeing, it has disappeared, and if it is more, it has not disappeared.[339]

You should compute the star for the rising or the setting of the sun at the time when its corrected anomaly is about what we have described.

Ar. p. 178

If you wish to know how long ago it rose, or in how long it will rise, or how long ago it disappeared, or in how long it will disappear, find the amount between the arc of seeing and the distance of the star from the sun and keep it; then divide it by the true corrected course of the star. You find that as I describe: compute the star either a day after that day or a day before it, as needed; what lies between the two positions is the true motion of the star. Subtract it from the true motion of the sun in a day: the remainder is the true corrected course. This is for the three upper stars. For Venus and Mercury, you add the course of the star to the course of the sun if it is retrograde, and take the difference between them if it is direct: the result is its corrected course. What comes out of the division is the number of days and hours in which it will rise or

[337] The translation follows the corrigenda in reading «غُروبها», «their setting», for «عُروبها» in the title (p. 176). Rising and setting mean here the growing and the shrinking distance of the star from the sun. For Venus and Mercury it grows from the conjunction beyond the sun, at the anomaly 0, to the greatest elongation, where the line of sight touches the epicycle, and shrinks to the conjunction below the sun, at 180. At the mean distance, with Ptolemy's radii of the epicycles, 43;10 and 22;30 in parts of which the eccentric is 60, the greatest elongation comes at the anomalies 136 and 112. For Venus the codex has 136; Nallino prints 137.

[338] Nallino takes these numbers from Plato of Tivoli and Theon's canon; the codex has 26 for 20, 348 for 340 and 170 for 200.

[339] The arcs are Ptolemy's (*Almagest* XIII 7), which Ptolemy gives as arcs of the ecliptic near the beginning of Cancer; al-Battānī takes them as arcs of the equator, to be compared with the ascensions (Nallino's commentary). The codex has 16, 16;30 and 6;40 for the arcs of Saturn, Mars and Venus (Nallino). The translation reads «والمطالع», «and the ascensions», for «والمطالم» (p. 177, line 16), a misprint that the corrigenda do not list.

set, or the number of days and hours since it rose or set.

I have set down for them the amounts of seeing in degrees of the signs in each clime, according to what has been observed of their appearance in each sign, and that is set down at the heads of the signs, although it is not exact, because of the variation of their latitudes. For this reason we have confined ourselves to setting down these amounts for one clime, so that knowing it from this table is easy, approximately; we have made it for the fourth clime. If you wish to know the seeing of the star and its disappearance, take, of the amounts of seeing and of disappearance set down in the table of the morning risings and the evening disappearances of the three upper stars, what is under the sign in which the star is, and what is under the sign after it. Then take the difference between the two signs, multiply it by the degrees of the star in the sign in which it is, and divide the product by thirty. Add the result to the amount of seeing or of disappearance, whichever you are computing, that you obtain under the sign in which the star is, if that is the smaller, and subtract it from it if that is the greater. What remains is the arc of seeing at that place in parts of the ecliptic, or the arc of disappearance. If that is equal to what lies between the sun and the star in degrees of the signs, it rose or disappeared on that day; if it differs, follow what I have set out and explained in this chapter. It is known that the working of the seeing by computation, in the way that I set out first, is more correct and more exact than what comes out of these tables. For Venus and Mercury, you take the four configurations mentioned in the way that we have stated for the upper stars.

Chapter 49. On knowing the nine configurations that the fixed stars, and some of the wandering ones, have with the sun

Ar. p. 179

Al-Battānī said: Since the stars, fixed and wandering, revolve in their course about the two poles of the ecliptic [ever since their motion in longitude and latitude has been known], while the right sphere revolves about the two poles of the equator, their rising and their setting on the two sides of the meridian line are always of equal amount at the place of the equator, and no change in their motion has been found. In the spheres inclined to the equator, however, their rising and their setting on the two sides of the meridian line are not equal but differ: the southern ones are later in rising than the northern ones, and likewise they precede them in setting. For this reason none of them that is not on the belt of the signs rises, sets and culminates with one and the same part of the signs, but with different parts; and so their configurations differ, as do those of some of the running stars, which are the moving wandering ones, in the regions of the ecliptic and of the horizon, and with the sun and the moon too. The most evident in force are those that they have with the sun, and they come in nine kinds.[340]

(1) The first kind is the morning easting, when the star is with the sun on the eastern horizon. It is of two sorts: one is called the morning one, when the star is not visible in the east and then rises afterwards, after sunrise; the other is called the morning-eastern, when it rises with the sun in the east. One also speaks of easting when the star rises before the sun.

(2) The second kind is called the culmination of the easting, when the star, at sunrise, is on the middle of the sky above the earth or below it. This too is of two sorts: one is called the morning one, when it culminates after sunrise; the other is called the morning culminating one, when the star is in the middle of the sky while the sun is in the east.

Ar. p. 180

(3) The third kind is called the morning westing, when the sun is at the place of rising and the star near the western horizon. This too is of various sorts: the star may be in the west at sunrise, which is called the morning westing, when it sets after the sun rises; the setting of the star may

[340] Nallino brackets these words as inept; Plato of Tivoli lacks them. The nine configurations are Ptolemy's (*Almagest* VIII 4; Nallino's commentary). *Tashrīq* and *taghrīb*, rendered «easting» and «westing», commonly mean the heliacal rising and setting, the appearance of a star in the east before sunrise and its disappearance in the west after sunset; al-Battānī uses them more widely in this chapter (Nallino's commentary).

come with the rising of the sun; or it may precede the sun in setting.

(4) The fourth kind is called the southern easting, when the sun is on the meridian line and the star in the east. It is of various sorts: it may be in the daytime, with the sun in the middle of the sky [so the star is not seen]; or at night, with the sun at the cardine of the earth, and the star is seen on the eastern horizon in those ways, either preceding the sun, or level with it, or behind it, so that it rises after the sun's culmination.[341]

(5) The fifth kind is called the southern culmination, when the sun and the star are in the middle of the sky. It is of two sorts. In one it is daytime and the sun is above the earth, so the star is not seen, or it is night and the sun is with it at the cardine of the earth, so it is not seen either. In the other the sun is at the cardine of the earth and the star in the middle of the sky above the earth, so that it is seen in those ways of preceding, being level and being behind.

(6) The sixth kind is called the southern west, when the sun is in the middle of the sky and the star in the west. This too is of several sorts: it may be daytime, with the sun in the middle of the sky, so the star is not seen; or night, with the sun at the cardine of the earth, so that it is seen in the ways mentioned of preceding, being level and being behind.

(7) The seventh kind is called the evening rising, when the sun is in the west and the star on the eastern horizon. It is of several sorts: the sun may set while the star is seen in the east, having risen before it; the star may rise with the setting of the sun, which is called the evening one; or it may be at the point of rising when the sun sets, so that it is not seen until it rises after the sun has set.[342]

(8) The eighth kind is called the evening culmination, when the sun is on the western horizon and the star in the middle of the sky above the earth or below it. It is of several sorts: at the setting of the sun it may be above the earth, and so seen, or below the earth, and so not seen; and it may precede in its culmination, or be level, or be behind.

(9) The ninth kind is called the evening westing, when the star is with the sun on the western horizon. It is of several sorts: the star may be seen in the west before it enters the rays, and set after the sun sets; the star and the sun may be together on the horizon and set together; or the star may precede the sun in its setting, and so move away from it in setting until it appears in the east before the sun.

Ar. p. 181

We have explained earlier in this book how to know the distances between the stars in their arrangement on the sphere, and shown how to know the parts of the ecliptic with which they rise, set and culminate.[343]

As for the seeing of the stars that are called fixed, and their disappearing on account of the sun: when the amount at which each of the six kinds of their magnitudes mentioned appears and disappears is known, your computation for it is as we described for the seeing. It is said that the amount of the arc at which the stars of the first magnitude appear and disappear — such as the Yemeni Shiʿrā and the Syrian one, the Heart of the Lion, the two Simāks, the end of the River, and those like them in magnitude — is 15 parts, I mean the arc at which each appears and disappears; these parts are of the times of the equator. For the remaining kinds, below this magnitude, the arc exceeds 15 parts in the order of the magnitude, until it comes to the smallest of them in magnitude, which is seen and disappears at the amount of a sign, approximately.[344]

[341] The bracketed words are supplied by Nallino after Plato of Tivoli. The cardine of the earth is the lowest point of the ecliptic, below the earth (chapter 35).

[342] Nallino's translation adds «not» to the first sort, which Ptolemy calls the earlier evening rising, not visible.

[343] Chapters 18, 20 and 26 (Nallino).

[344] The stars are Sirius, Procyon, Regulus, Spica and Arcturus, and Achernar (Nallino). Plato of Tivoli has 12. Ptolemy gives no such arcs. The 15 parts may come from Autolycus, who gives 15 parts of the ecliptic for all the fixed stars, a book known to the Arabs in Qusṭā ibn Lūqā's translation, corrected by Thābit ibn Qurra (Nallino's commentary). Schiaparelli supposes that earlier Arab astronomers had found by rough observation that stars of the first magnitude

Chapter 50. On knowing the distances of the stars, their diameters, the sizes of their bodies and the extent of their spheres, set down as handed down, in the way in which the ancients and the first ones stated them

Ar. p. 181
Ar. p. 182

Al-Battānī said: The distances of the sun and the moon, their diameters and the sizes of their bodies we have explained according to what is said in the book of the *Almagest* and what we found by measuring the eclipses. Let us now begin the account of the other spheres, up to the sphere of Saturn and the sphere of the fixed stars, as the later excellent sages after Ptolemy took pains to set it out. Their account of it was this. It has been shown that the farthest distance of the moon from the earth, in the measure in which the radius of the earth is one part, is 64;10, and that is the nearest distance of Mercury; the spheres of Mercury and Venus lie between the farthest distance of the moon and the nearest distance of the sun. The limit of the air and the fire is the nearest distance of the moon from the earth, which is when it is on either side of the full moon, I mean at the mean quadrature with the sun; it has been shown that its distance from the earth is then 33;33 in that measure. What is above that is the ether, in which the stars run. The two remaining elements, water and earth, end at the amount of the radius of the earth. These four elements, earth, water, air and fire, are the roots of the earthly natures and the cause of coming to be and passing away; as they differ, things differ, according to what of the sun, the moon and the stars is above them, and their change goes on within the nearest distance of the moon from the earth; by that every thing, of the animals and the plants, changes. What lies within this limit, between the centre of the earth and the ether, reaches, as we have said, 33;33 from the earth, in the measure in which the radius of the earth is one part: that is the farthest extent of the earth, the air, the water and the fire. What is above that is a fifth nature, of which nothing true can be said: the senses do not reach it, and the mind does not grasp its quality.[345]

In it is the sphere of Mercury, above the sphere of the moon. What appeared of its distance and size, as they grasped it, is this: it is reported that they measured its size at its farthest and at its nearest distance from the earth and found the variation of its size to be as two and a third and a quarter to one. Since the nearest distance of Mercury is equal to the farthest distance of the moon, which has been shown to be 64;10, when that is multiplied by the two and a third and a quarter, which is the variation of the size of its diameter, its farthest distance comes to 166 times the radius of the earth. When half of what lies between its farthest and its nearest distance is taken and added to its nearest distance, its mean distance is 115. Then they measured its size, when it was at its mean distance, against the sun at its mean distance, and found its diameter to be one part in fifteen of the diameter of the sun. When the 115 is divided by fifteen, the result is 7 parts and two thirds of a part. Since the diameter of the sun is five and a half times the diameter of the earth, if the mean diameter of the sun is made 1108, as we have shown by measurement, the diameter of the earth is 201½ in that measure; and when the 7⅔ parts are compared with the 201½, they are found to be about one part in 26¼ of it. Since the diameter of the earth subtends 1 degree and 57 minutes of the circle of the sphere, the diameter of Mercury subtends about 4 minutes and a half and a sixth of a minute. When that is multiplied in length, breadth and depth, the size of the body of Mercury comes to about one part in [eighteen thousand] parts of the body of the earth.[346]

Ar. p. 183

appear an hour from the sun, 15 times of the equator, and those of the sixth two hours, 30 times, and set the other magnitudes between (Nallino's commentary). A sign is 30 parts.

[345] The translation reads «after Ptolemy» with Plato of Tivoli and Nallino's translation; the text has «before», which does not fit «the later sages». The distances of this chapter rest on Ptolemy's eccentricities and epicycles, with the spheres taken to touch one another without a gap, so that the least distance of each planet is the greatest distance of the one below it. Al-Farghānī gives the same scheme with somewhat different numbers, and Proclus reports it in the *Hypotyposes* (Nallino's commentary). 64;10 and 33;33 are the greatest and the least distance of the moon (chapter 39); the codex has 38;38 for 33;33.

[346] 64;10 × 2 7/12 = 165;46, and (64;10 + 166)/2 = 115. Making the diameter of the sun 1108, the number of its mean distance in radii of the earth (chapter 30), puts the diameter of each planet, its mean distance divided by the ratio of its apparent diameter to the sun's, in the same measure, in which the diameter of the earth is 1108/5½ (Schiaparelli, in

Then they looked at the size and the distance of Venus and found the variation of its size between its farthest and its nearest distance to be as two to thirteen. When the 166, which is the farthest distance of Mercury and the nearest distance of Venus, is multiplied by the six and a half that is the amount of the variation of the size of Venus relative to one, the farthest distance of Venus is 1070, which is the nearest distance of the sun; its mean distance is therefore 618. They measured the diameter of Venus against the diameter of the sun when it was at its mean distance and found it one part in ten of the diameter of the sun. When a tenth of the 618 parts is taken, it is 61 parts and four fifths; when that is divided by the 201½, it is a quarter and half a tenth of the diameter of the earth, and a little that is not to be counted. Therefore its diameter subtends 32 minutes and 27 seconds of the circle of the sphere; when that is multiplied in length, breadth and depth, the size of Venus is about one part in thirty-six of the size of the earth.[347]

As for the centres of the epicycles of Mercury and Venus, their course on the circle of the eccentric is like the course of the centre of the epicycle of the sun. The size of the diameter of the epicycle of each of them is known from what lies between the farthest distance and its first station, which is its greatest distance from the sun on the side preceding in the order of the signs. The greatest distance of Mercury from the sun is 26 parts, when the sun is opposite the centre of the epicycle and the centre of the epicycle is at the farthest distance of the eccentric; Mercury is then once ahead of the sun and once behind it. The greatest distance of Venus from the sun is 46 degrees, when the sun is opposite the centre of the epicycle and the centre of the epicycle is at the point of the farthest distance of the eccentric; Venus is then once in front of the sun, once ahead of it and once behind it. The least distance of Venus from the sun, from the first station to the second, is 41 parts, and the least distance of Mercury from the sun, the amount between the two stations, is 21 parts. From this it is clear that the diameter of the epicycle of Mercury subtends 47 degrees, and the diameter of the epicycle of Venus 87 degrees.[348]

Ar. p. 184

As for Mars, its distance and the size of its body are according to what was said of it when they measured the variation of its size. They also reported that they found its size at its nearest distance to be seven times its size at its farthest distance. Its nearest distance is the farthest distance of the sun, which by our measurement is 1146; multiplied by the seven, that comes to 8022, and its mean distance is 4584. They measured it at its mean distance and found its diameter to be one part in twenty of the diameter of the sun. When its mean distance is divided by the twenty, it comes to 229 times and a fifth; when that is divided by 201½, the diameter of the earth, its diameter is about once the diameter of the earth and less than a seventh. Therefore the diameter of Mars subtends about 2 degrees, 1 minute and 37 seconds of the circle of the sphere; when that is multiplied in length, breadth and depth, the size of Mars is once and a third the size of the earth, less a little that is not to be counted. The size and the extent of its epicycle are known from the motion of the star Mars from its first station to its second. The epicycle moves 0;31 a day, and Mars moves on the epicycle 0;28 a day, so that its motion is left at 3 minutes; from this it is known that it stays in a sign five months and six, because of the variation of its motion as it is seen. In truth it neither increases nor decreases: it is one motion, for all time, for it and for the other stars. The diameter of the epicycle of Mars subtends 82 degrees and 28 minutes.[349]

As for the distance of Jupiter and its size, they found its size at its nearest distance to its size at its farthest distance to be as thirty-seven to twenty-three, which is one and a half and a ninth.

Nallino's commentary); 1108/5½ is 201 5/11 (Nallino). 1;57 divided by 26¼ is 0;4,27. The text has «seventeen»; Nallino takes it for an error of the codex for «eighteen thousand», since $(26¼)^3$ = 18,088.

[347] 166 × 6½ is 1079; Nallino keeps the text's 1070, the nearest distance of the sun in chapter 30, since the mean distance 618 is half of 166 + 1070. 61⅘ divided by 201½ is 0.307 (Nallino).

[348] The apparent diameter of the epicycle is the sum of the greatest and the least elongation: 26 + 21 = 47 and 46 + 41 = 87 (Schiaparelli, in Nallino's commentary). The numbers are Ptolemy's (Nallino).

[349] 1146 × 7 = 8022, and (1146 + 8022)/2 = 4584; 4584/20 = 229⅕, and 229⅕/201½ = 1.14. Nallino would read 82;21, which Ptolemy's ratio of the radius of the epicycle of Mars to that of its eccentric, 39;30 to 60, gives (Schiaparelli, in Nallino's commentary).

When that is multiplied by the farthest distance of Mars, which is 8022, the farthest distance of Jupiter comes to about 12,924, and its mean distance is likewise 10,473. They found the size of Jupiter at its mean distance to be one part in twelve of the diameter of the sun. When its mean distance is divided, its diameter comes to about 872 and a half and a quarter; when that is compared with the 201½, it is four times and a third the diameter of the earth, less a little. When that is multiplied in length, breadth and depth, its size is about eighty-one times the size of the earth, and its diameter subtends about 8;18 of the circle of the sphere. From [its motion from] its first station to its second, and the motion of its epicycle, which is five minutes a day in the order of the signs, while its motion in the lower part of its epicycle is 54 minutes each day, seemingly towards the west, it is clear that the diameter of its epicycle subtends 22 degrees.[350]

Ar. p. 185

As for the distance of Saturn, the variation of its size to the sight between its nearest and its farthest distance is, as they found it, as one and two fifths to one, which is as seven to five. When that is multiplied by the farthest distance of Jupiter, the farthest distance of Saturn comes to 18,094, and its mean distance is therefore 15,509. They found the diameter of Saturn at its mean distance to be one part in eighteen of the diameter of the sun; when its mean distance is divided by that, the diameter of Saturn comes to about 861 and a half and an eighth. When that is compared with 201½, the diameter of the earth, its diameter is about four times and a sixth and an eighth the diameter of the earth; when that is multiplied in length, breadth and depth, the size of Saturn is about seventy-nine times the size of the earth. The diameter of Saturn subtends 8;12 of the circle of the sphere. The extent of its epicycle is known [from its motion] from its first station to its second: the motion of its epicycle is two minutes a day, and its motion in the lower part of the epicycle 0;57 a day, seen as if towards the west; so the diameter of its epicycle subtends 12;26. The diameter of the sun must subtend 39;48 of the circle [of the sphere].[351]

As for the distance of the fixed stars and their size, they reported fifteen stars of the first magnitude and said that their distance is, in the manner we have described, about nineteen thousand times the radius of the earth. They measured their size against the sun and found it one part in twenty of the sun. When their distance is divided by that, the diameter of each of these stars is 950; compared with the diameter of the earth, that is about four times and two thirds and half a tenth of it. When that is multiplied in length, breadth and depth, the size of each of these stars is about one hundred and five times the size of the earth. We have divided the fixed stars that are in the constellations into six magnitudes; each class below these fifteen stars mentioned decreases in size until it comes to the sixth magnitude, where the size of a star is sixteen times the size of the earth. So the greatest of the created bodies of the world is the sun; the second, the fifteen stars mentioned of the first magnitude; the third, Jupiter; the fourth, Saturn; the fifth, the rest of the fixed stars, of the second magnitude [to the sixth]; the sixth, Mars; the seventh, the earth; the eighth, the moon; the ninth, Venus; and the tenth, Mercury, the smallest of the bodies of the world.[352]

Ar. p. 186

Whoever wishes to repeat the test of any of these diameters should take an alidade and fit in it two pierced sights, with their holes facing each other; let the hole next to the eye be small, and the one next to the star of a size to take in the whole body of the star, neither more nor less. Let them measure the sun with another alidade in the same way, know the diameter of the hole with which they measured the sun, and compare with it the hole with which they measured the star;

[350] 37/23 is 1.609, one and a half and a ninth 1.611; 8022 × 1 11/18 = 12,924 and (8022 + 12,924)/2 = 10,473. The translation reads 872 with Nallino's translation, as the division gives (10,473/12 = 872¾); the text has 892. The bracketed words are Nallino's conjecture. From Ptolemy's ratio of the epicycle, 11;30 to 60, the diameter of the epicycle comes to 22;6 (Schiaparelli, in Nallino's commentary).

[351] 12,924 × 7/5 = 18,094 (the codex has 18,074) and (12,924 + 18,094)/2 = 15,509; 15,509/18 is 861 11/18 (Nallino). The bracketed words are Nallino's. From Ptolemy's ratio of the epicycle, 6;30 to 60, its diameter comes to 12;26 (Schiaparelli, in Nallino's commentary). The last sentence makes no sense here: al-Battānī's mean apparent diameter of the sun is 0;32,30 (chapter 30), and Schiaparelli takes the sentence for a senseless interpolation (Nallino's commentary).

[352] 950/201½ is 4.71, and $(4.71)^3$ = 105. The bracketed words are supplied by Nallino.

and let the measurement be made at one and the same place of the horizon.

What remains of what we have described of the amounts of the stars is what their diameters subtend of the circle of the sphere at their mean distance; we shall also show the amounts that they must subtend in the measurement when they are at their farthest distance and at their nearest distance. The Sun: the diameter of the sun, we have shown, is 39;48, and we keep it so at all the degrees of its distances, since its change amounts to nothing sensible. The Warrior: the diameter of Saturn subtends at its farthest distance 16;22, at the mean 36;39 and at the nearest 33;36. Jupiter: the diameter of Jupiter subtends at its farthest distance 35;36, at the mean 14;45 and at the nearest 29;36. Mars: the diameter of Mars subtends of the circle of the sphere at its farthest distance 36;10, at the mean 16;14 and at the nearest 33;36. Venus: the diameter of Venus subtends of the sphere at its farthest distance 0;10, at the mean 0;39 and at the nearest 0;36. The Scribe: the diameter of Mercury subtends of the circle of the sphere at its farthest distance 0;33, at the mean 0;6 and at the nearest 0;14. The Moon: the diameter of the moon has been shown to subtend of the circle of the sphere at its farthest distance 0;29,40, at the mean 0;39,36 and at the nearest 0;36,22.[353]

These amounts vary between the distances mentioned according to the degrees of the stars in their distances, and that is known from their equations. The distance of the star from the point of the farthest distance of the epicycle, and from the point of the nearest distance, is known from the mean equation corrected by the fifth or the seventh column; the distance of the centre of the epicycle from the point of the farthest distance of the eccentric is known from the equation of the anomaly. From these two equations the degree of the star in its distance and nearness to the earth is known, when that is related to the sixty that are the radius, as we have shown in knowing the distances of the moon from the variation of its motions.[354]

Chapter 51. On knowing by observation the motion of the fixed stars, which move in their sphere or whose sphere moves with them, and on knowing the positions of those of them that are needed from the tables

Ar. p. 187

Al-Battānī said: The states of the fixed stars in their rising, their setting, their culmination and their stay above the earth and below it, and the state of those of them that are near the pole or far from it in every locality, we have mentioned before in this book. The fixed stars revolve about the two poles of the ecliptic and have not departed from it since a motion of theirs became known; likewise their latitude is one latitude, from which they do not change, and they are in this state as long as no change in their motion has been known. Likewise the distances between them have stayed in one state since they were observed, and for that reason they are called the fixed stars: what is meant is that their distances are fixed. For their motion is all together one motion, as if they were in one sphere: either they move together in it, or it moves them by its motion and carries them from the azimuth of one place of the sphere to the azimuth of another place of the sphere, from the west to the east, like the other motions of the running stars, which are the seven planets.

We found their positions in longitude and latitude in the book of Ptolemy for the first year of the reign of Antoninus, which is the year 886 of the reign of Nabonassar. One of the observations of them on which Ptolemy worked was the observation that Menelaus reported from the year 845

[353] Schiaparelli and Nallino take this passage for an interpolation. Its numbers are wrong past repair in the codex and in Plato of Tivoli alike; the mean diameters are mostly smaller than the extreme ones; the sun is again given 39;48; and only here are Saturn and Mercury called al-Muqātil, «the Warrior», and al-Kātib, «the Scribe», names used by the Arabs of north-west Africa and Spain. From al-Battānī's distances and the mean diameter of the sun, 0;32,30, Schiaparelli computes what the passage should have given at the farthest, the mean and the nearest distance: Saturn 0;1,33, 0;1,48, 0;2,10; Jupiter 0;2,12, 0;2,42, 0;3,32; Mars 0;0,56, 0;1,37, 0;6,30; Venus 0;1,53, 0;3,15, 0;12,6; Mercury 0;1,30, 0;2,10, 0;3,54; the moon 0;29,30, 0;32,25, 0;35,20 (Nallino's commentary).

[354] The chapter on the distances of the moon is chapter 39 (Nallino).

of the reign of that Nabonassar. Menelaus reported that the northern one of the stars between the two eyes of the Scorpion was in that year, when examined with the moon with the armillary sphere, at 5 parts and 55 minutes of Scorpio; and by what Ptolemy set down in the book, the Heart of the Lion must have been in that year at 2 parts and a sixth of a part of Leo, and the Yemeni Shiʿrā at 17 degrees of Gemini.[355]

Ar. p. 188

We observed these stars that we have mentioned, and other fixed stars, many times in successive years. One of the observations on which we rely was in the year 1191 of the years of Dhū l-Qarnayn: we observed with the moon and with the passage of the stars through the middle of the sky, and so found their distances from the equator and the parts of the signs that culminate with them; then from that we found at which parts of the signs their positions fall in longitude, and their latitudes from the circle of the signs on the side on which we found them. We found the northern one of the stars between the eyes of the Scorpion at 17;45 of Scorpio, the Yemeni Shiʿrā at 28;50 of Gemini, and the Heart of the Lion at 14 of Leo. The year in which we made this observation was the year 1627 of the reign of Nabonassar mentioned. When we divide these 11 parts and 50 minutes between their first positions and the positions they had reached at the time of our observation by the 782 years between the two observations, we find their motion to be one degree in every 66 solar years; so we have set it down in the table of the motions of the fixed stars, which are found from it by the collected and the single years and the months. Likewise we have added these 11 parts and half a third to the positions that we found set down in the book of Ptolemy, and set down their positions in the year 1191 of the years of Dhū l-Qarnayn. In what we observed of many stars we found no evident variation in latitude, except what is of no account and can be passed over. So we have made tables for them, in which we have set down their positions in longitude and latitude, the side and the magnitude, so that the positions that they reach after this year are known from their motions taken from the tables, when these are added to their positions in the year 1191; and likewise their positions before this year are known by what we have said.[356]

The stars that Ptolemy mentions in the book of the *Almagest* are one thousand and twenty-two in number, besides the stars of the Lock, the Solitary One and al-Mirzam. Ptolemy arranged their size in six degrees, the greatest of which is the first magnitude and the smallest the sixth, and stated that these stars make up forty-five figures: of them fifteen constellations are on the southern side, and six constellations of the southern signs, which are Libra, Scorpio, Sagittarius, Capricorn, Aquarius and Pisces; on the northern side eighteen constellations, and the six remaining constellations of the signs. Their sides may change over a long time, so that the northern ones become southern and the southern northern.[357]

Ar. p. 189

Of these northern stars in the constellations of the signs and others are: the stars of Aries, which are 13, among them the two Sharaṭ, on its horns, and al-Buṭayn, on its rump; then the stars of Taurus, 33, the Pleiades on its horn and al-Dabarān on its back; then Gemini, whose stars are 18, among them the front of the two arms, al-Haqʿa and al-Hanʿa; then Cancer, whose stars are 9, among them al-Nathra; then Leo, whose stars are 27, among them the Lock, al-Ṭarf, and al-Jabha,

[355] Ptolemy (*Almagest* VII 4) gives the year 885 of Nabonassar for the first year of Antoninus, 137-138; aṣ-Ṣūfī also has 886 (Nallino). Menelaus observed the star, β Scorpii, at Rome in 98 (*Almagest* VII 3; Nallino's commentary). The Heart of the Lion is Regulus, the Yemeni Shiʿrā Sirius.

[356] The year 1191 began on 1 September 879 (Nallino). 17;45 – 5;55, 28;50 – 17 and 14 – 2;10 are each 11;50. 11;50 in 782 years is 54.48″ a year, and one degree in 66 years 54″ 33‴ (Nallino's commentary). «Half a third», 11;10, is Nallino's reading; the codex and Plato of Tivoli have «a half and a third», 11;50. Al-Battānī took 37′ from the 11;50 for the 41 years between Menelaus and Ptolemy's catalogue, at al-Battānī's own rate; but Ptolemy, at a rate of 36″ a year, had added only 25′ to the longitudes of Menelaus, so that 11;25, not 11;10, should have been added to Ptolemy's longitudes; aṣ-Ṣūfī avoided the error (Nallino's commentary).

[357] Ptolemy has forty-eight constellations, twenty-one of them north of the zodiac; Nallino takes the forty-five and the eighteen of the text for errors. The Lock is Coma Berenices, which Ptolemy leaves out of the count of 1022; the Solitary One is α Hydrae; al-Mirzam is a name the Arabs give to several stars that precede a bright one (Nallino, after aṣ-Ṣūfī).

which is the Heart of the Lion, al-Zubra and al-Ṣarfa; then Virgo, whose stars are 26, among them al-ʿAwwāʾ and the unarmed Simāk. This is what is in the northern half of the constellations of the signs.[358]

In the southern side of the constellations of the signs are Libra, whose stars are 8, among them al-Ghafr; then Scorpio, which has 21 stars, among them the two Zubānā, al-Iklīl, the Heart and al-Shawla; then Sagittarius, which has 31 stars, among them al-Naʿāʾim and al-Balda; then Capricorn, which has 28 stars, among them Saʿd al-Dhābiḥ and Saʿd Bulaʿ; then Aquarius, which has 42 stars, among them Saʿd al-Suʿūd and Saʿd al-Akhbiya; then Pisces, which has 34 stars, among them the front Spout, the rear Spout [and al-Rishāʾ]. All the stars in the constellations of the signs are three hundred and forty-six; all the stars in the eighteen northern constellations named in the table are three hundred and sixty; all the stars in these fifteen southern constellations are three hundred and sixteen. All these stars counted are one thousand and twenty-two: of them fifteen are of the first magnitude, 45 of the second, 208 of the third, 474 of the fourth, 217 of the fifth and 49 of the sixth; the cloudy ones, like clouds, are five, and the dark ones 9; and the stars of the Lock, the Solitary One and al-Mirzam. Of these stars we have set down those for which we found a known temperament in the book of Ptolemy, of the constellations outside the circle of the signs, above all the great ones; for those in the constellations of the signs we have mentioned their temperament and their force, resembling the force of the two luminaries and the wandering stars.[359]

Ar. p. 190

After that we have set down, for those of the first and the second magnitude and some of the third, separate tables, in which we give their distances from the equator, half their stay above the earth, their altitude in the middle of the sky, and the parts of the signs with which they rise, culminate and set, where the altitude of the northern pole above the horizon is 36 parts, which is the latitude of the city of al-Raqqa; we have given these states of theirs described for the year 1211 of the years of Dhū l-Qarnayn. In the tables before these we have set down their positions in longitude from the beginning of Aries. If you wish to know the position of any of the fixed stars set down in the tables that you wish, take their motion in the years that come after the year 1191 of the years of Dhū l-Qarnayn, add it to their positions set down in the tables, and cast that off from the beginning of Aries: where the count ends for you, there is the position of the star in the sign to which it comes. Its latitude is that set down in the table, on the side set down, and so too its magnitude among the six. Likewise you know the parts with which they rise, set and culminate from the later tables, by taking what is in each of the three columns and casting it off from the beginning of Aries; after this year for which we have set down these states in these tables, you add to what is in the tables as much as is due, since there is much change, whose computation must be carried out anew at every time. We have set it down for our time only so that it may be known in it approximately; the method by which these things are known is explained earlier in this book. From these tables the nine configurations mentioned that the stars have with the sun are known in our time, above all for the great ones, which are those set down in the tables.[360]

[358]The named stars, apart from the Lock, are lunar mansions of the Arabs, the twenty-eight stations of the moon that divide the zodiac (Nallino's commentary). Aṣ-Ṣūfī finds several of the placements wrong: al-Buṭayn is three stars in a triangle on the belly of the Ram, and al-Dabarān is the bright red star in the southern eye of the Bull (Nallino's commentary).

[359]The bracketed words follow Nallino's emendanda (Part II, p. XXXI), which add «والرِّشَاء», «and al-Rishā'», after «the rear Spout» (p. 189, line 7). With them the stars named in the twelve signs, apart from the Lock, are the twenty-eight lunar mansions of the Arabs; al-Rishāʾ, the Rope, is the last. The stars counted in the twelve signs come to 290, not 346, since the stars outside the figures are not counted among them (Nallino). 346 + 360 + 316 = 1022, and 15 + 45 + 208 + 474 + 217 + 49 + 5 + 9 = 1022. Nallino takes «temperament» here for the data that fix a star's place, so that al-Battānī listed the stars whose places were not in doubt in the Arabic copies of the *Almagest* (Nallino's commentary).

[360]The year 1211 began on 1 September 899; the codex has 1251 (Nallino).

Chapter 52. On knowing what the astrologers have reported in saying that the sphere has a motion of displacement, advancing and retreating, and on the evident falsity of what they say

Ar. p. 190

Al-Battānī said: It is mentioned in Ptolemy's book that the astrologers claimed that the sphere has a motion of displacement, slow in time, one degree in every 80 years, and they said that this motion goes as far as 8 parts, advancing and then retreating. What they mean is that the sphere of the signs moves 8 parts from west to east, in the same direction as the motion of the sphere of the fixed stars, and then moves 8 parts from east to west, contrary to the first motion. Yet at the same time it must move with the motion of the fixed stars, the first motion, which is from west to east; and this cannot be, nor can it come about, unless something other than it moves it, or else the fixed stars are what move upon it; for one body cannot move with two motions in two different directions at once.[361]

Ar. p. 191

They stated that the end of the advance was 128 Egyptian years before the reign of Augustus, which is the year 166 of Alexander the Macedonian, and that one must take the years after that and reckon one degree for every 80 years of them; what results from that [is subtracted] until it reaches 8 degrees, and what remains is added to the motions of the stars computed before. When the 8 are complete, they are dropped, and what exceeds 8 is taken as it stands and added to the positions of the stars until 8 are complete; then the first procedure is repeated.[362]

The length of the year on which those who held this view worked was greater than 365 days and a quarter of a day by a fifth of an hour or about that; for that reason the mean motion of the sun in the Egyptian year comes to 359;44,43. Hipparchus, who came after them, worked with a year of 365 days and a quarter of a day only, so that the motion of the sun in the time of the Egyptian year comes to 359;45,13; and Hipparchus claimed to have established that it is less than the quarter of a day. Then Ptolemy observed 285 years after Hipparchus and found the length of the year, on which Ptolemy worked, to be 365 days and less than a quarter of a day by one part in 300, so that the motion of the sun in the Egyptian year came to 359;45,25. We observed 743 years after Ptolemy and found the length of the year to be 365 days and less than a quarter of a day by 3 parts and two fifths of a part of 360, so that the motion of the sun in the Egyptian year became 359;45,46.[363]

All these motions have been increasing since the time of Nabonassar or thereabouts. So it is refuted that what has been described agrees with anything in their statement: not in the number of the parts, not in the amount of the motion, and not in the increase and the decrease. Rather, we

[361] Not Ptolemy but Theon of Alexandria, in the fourth century, reports this doctrine of «some of the ancient astrologers» in a work on Ptolemy's Handy Tables, adding that Ptolemy does not hold it, since without it the equinoxes computed from the tables agree with those found with instruments. Theon's remark probably means that Ptolemy passed over the doctrine in silence; al-Battānī took it to mean that Ptolemy had mentioned and refuted it (Nallino's commentary). «The astrologers» renders «aṣḥāb al-ṭilsamāt», literally «the people of the talismans», which here stands for the Greek apotelesmatikoi, the astrologers (Nallino). The doctrine is known as the trepidation of the fixed stars.

[362] The era of Alexander the Macedonian is the era from Alexander's death, the era of Philip (chapter 32). In Ptolemy's canon of kings the reign of Augustus begins when 294 years of this era are complete, and 294 − 128 = 166. The bracketed words are supplied by Nallino. In Theon's account the degrees found are subtracted from 8, and the remainder is added to the positions of the sun, the moon and the five planets computed from the tables (Nallino's commentary). «Computed before» renders «al-mutaqaddima», Nallino's reading for the codex's «al-muqaddama»; Nallino's translation renders the words as «the direct motion of the stars».

[363] The translation follows Nallino's emendanda (Part II, p. XXXI) in reading «او نحوه», «or about that», for «ونحوه» (p. 191, line 3). The year of the astrologers, 365 days 6 hours 12 minutes, is the year that chapter 27 ascribes to some of the ancient people of Egypt and Babylon; Letronne and Martin show that these astrologers lived after Hipparchus, perhaps before Ptolemy (Nallino's commentary). Ptolemy's year is 365 days 5 hours 55 minutes 12 seconds, al-Battānī's 365 days 5 hours 46 minutes 24 seconds (Nallino). The 285 and the 743 years are the intervals between the autumnal equinoxes observed by Hipparchus, Ptolemy and al-Battānī (chapter 27; the codex has 943 for 743). The four motions are 360 parts multiplied by 365 days and divided by the four years; for the first three the codex has 359;44,48, 359;41,53 and 359;44,25, which Nallino corrects.

see this increase come without order in its slowness and speed: Ptolemy corrected Hipparchus by nearly a day in about 300 years, and we have corrected Ptolemy by 4 days and a quarter in about 750 years, besides the day by which Ptolemy had corrected Hipparchus.[364]

If this excess has come about only from an error in the instruments with which the observations were made, from their division or from their changing over a long time, then it must of necessity occur in our observations after a period of time, since in our observations we measure only against those observations. And if it comes from a motion in the sphere whose true nature has not become clear to us, and which neither we nor any of those before us have grasped, then seeking the truth and following it means observing at every time, so that whatever is found and caught at that time is set right, as it was set right in the time before.[365]

Ar. p. 192

As for what may be conjectured, and what the measurements require: since this excess is common to all the motions of the stars, it has come about only from the motion of the sphere of the fixed stars. For Ptolemy stated that this motion, by what was found from Ptolemy's own observations and also by what was worked with before, is one degree in every 100 years; but between Ptolemy's observations and the observations they were compared with there was not a period long enough for an evident change in such a motion to appear, for between the observation that Ptolemy made and the observation it was compared with there are only about 200 years. As the time between us and Ptolemy has grown long, the increase in this motion has become evident, so that it has been found to be one degree in every 66 solar years; and it is from the difference between these two motions that the excess in all of them has come.[366]

Chapter 53. On knowing the times of the revolutions of the years and their ascendants, and the positions of the stars when [the sun] returns to the part in which it was at the root

Ar. p. 192
Ar. p. 193

Al-Battānī said: If you wish to know the revolution of any year you like of the years of nativities and of other things that are reckoned from a fixed beginning — that is, the time at which the sun returns to the part in which it was at the time of the beginning — find the year of the years of Dhū l-Qarnayn in which the beginning was, and also the year in which you wish to know the revolution. Subtract the smaller from the larger: what remains is the complete years that have passed for the nativity or the beginning you want, up to the same day of the Roman month on which the nativity or the beginning was. Multiply these complete years by 86 degrees and 36 minutes, which is the excess of the length of the year over the complete days; cast off the circles from the product, and divide whatever remains below a circle by 15: the result is equal hours. Add them to the hours of computation at the root. If they come to less than 24, take them as they are, with the day of the month that has passed; if they exceed 24, cast off 24 from them and add one day to the days of the month that have passed. Keep the days and the hours that you then have. If the year is a leap year and Subāṭ has run out, subtract one day from the days of the month that have passed, and the result is the day of computation; if the year is not a leap year, leave the days as they are, and the days of the month that have passed and the hours that result

[364] «What has been described» renders «what they described»; Nallino's translation takes the sentence to say that what the astrologers held about the number of degrees, the amount of the motion and the increase and decrease is void. Nallino's translation has «about 4½ days»; neither Nallino's notes nor the corrigenda mention the difference from the Arabic. By chapter 27, al-Battānī's year is shorter than Ptolemy's by 2;12 parts of a day of 360 parts, which in 743 years make 4.54 days; Ptolemy's year is shorter than 365 days and a quarter by 1/300 of a day, which in 285 years make 0.95 of a day.

[365] Nallino suggests that «خطأٌ», «an error», may be missing after «occur»; the Latin translation has «errors will of necessity befall our observations».

[366] «Require» follows Nallino's reading «يوجبه»; the codex has «يوحيه», «suggests». Nallino suggests reading 280, the interval between Hipparchus and Ptolemy, for the 200 years of the codex and of Plato of Tivoli. The rates of one degree in 100 years and one degree in 66 years differ by 18.5″ a year, against the 21.7″ by which al-Battānī's motion of the sun in an Egyptian year exceeds Ptolemy's (chapter 27).

are the days and the hours of computation. With them find the mean of the sun in the year you want, in the way described before: the mean of the sun comes out exactly the same as the mean at the root.[367]

Or, if you like, multiply the years you have by 3 parts and 24 minutes, which is the amount by which the length of the year falls short of the full quarter of a day above 365, and keep the product. Then cast off the years you have four by four: if one remains, take 90 parts for it; if two remain, take 180 for them; if three remain, take 270 for them; and if four remain, take 360 for them. From whichever of these you have, subtract what you kept, and for every 15 degrees of the remainder reckon an hour; add it to the hours of computation in the same way. The meaning of these two ways is one.[368]

Whatever comes out for you by either of the two ways is the date. Compute the mean of the sun for it in the first manner, as usual, then compute its true position. If the true position of the sun comes out the same as the first position, that is the time of the revolution. If it exceeds the true position of the sun at the root, see how much the excess amounts to in the sun's motion in an hour and subtract that from the hours of computation; if it falls short, see how much it falls short in the sun's motion in an hour and add that to the hours of computation, so that you correct the hours of computation by which you bring the sun to the true position in which it was at the root. With them compute also the position of the moon and of the other wandering stars. Then convert them into the hours of the unequal days as they are found, by subtracting the equation of the days that stands opposite the part of the sun in the ascensions of the right sphere, after you know its amount in equal hours: what results is equal hours after noon, with which you find the ascendant and the cardines in the usual way.[369]

This variation in the true position of the sun arises only from the motion of its apogee in the years between the year of the root and the year of the revolution. When the sun is near the apogee, the change is only slight and imperceptible, and likewise near its perigee; the farther it moves from these two points, the greater the variation in it. It is known that, whenever 106 years have passed, the times of the revolutions come one day before the day of the month on which they were at the root.[370]

We have made separate tables for the times of the mean revolutions of the years and the mean motions of the stars in them, and have explained how to work with them in the last of the

[367] The revolution of a year is the moment at which the sun returns to the longitude it had at a birth, or at another beginning such as that of a city or a people; astrologers draw their predictions from it (Nallino's commentary). The root is the moment of that beginning. The heading says only «when it returns»; the text shows that the sun is meant, while Nallino's translation has the planets return to the degree they held at the beginning. 86;36 is the 5 hours 46 minutes 24 seconds by which al-Battānī's year exceeds 365 days, at 15 parts to the hour (Nallino). The rule takes the whole days cast off with the circles to be the leap days that have passed since the root, but they can be fewer, and the day then comes out one too late: after 4 years nothing is cast off, since 4 × 86;36 is 346;24, while one leap day always passes, and the rule subtracts it only when the root falls in a leap year after Subāṭ. A day's error makes the mean sun differ from that of the root by 0;59,8, the sun's motion in a day (chapter 27), and the comparison of the true sun below turns this difference into the missing 24 hours.

[368] 3;24 is the quarter of a day, 90 parts, less 86;36 (Nallino). The two ways agree: the years times 86;36 are the years times 90 less the years times 3;24, and the years times 90 leave 90, 180, 270 or 360 when the circles are cast off. From 29 years on, the product can exceed the parts taken, and 360 must then be added to them first.

[369] Converting the hours turns mean time into true time (Nallino). The equation of the days is that of chapter 29; chapter 34 subtracts it to turn true hours into mean, so that it must be added here, as the short chapter E after chapter 57 does; the text has «subtract». The cardines are those of chapter 35.

[370] The rule about the apogee is the wrong way round. At the revolution the mean sun is the same as at the root, so the motion of the apogee changes the sun's anomaly by the same arc, and the true sun moves by that arc times the rate at which the equation changes with the anomaly. That rate is greatest at the apogee and the perigee, where the equation is nothing, and nothing where the equation is greatest. With the radius 2;4,45 of the sun's epicycle (chapter 28), one degree of the apogee's motion, 66 years at al-Battānī's rate (chapter 45), moves the true sun by 2.0′ at the apogee, by 2.2′ at the perigee and by about 5″ at 90° from the apogee. The Roman year of 365 days and a quarter exceeds al-Battānī's year by 13 minutes 36 seconds, which in 106 years make 24 hours 1 minute 36 seconds (Nallino).

chapters, at the close of the book, so that working with them is easy when it is needed.[371]

Chapter 54. On establishing the amounts of the applications as they depend on the latitudes of the stars

Ar. p. 194

Al-Battānī said: Since the circle of the signs is divided into twelve signs, and nothing measures twelve, among the numbers of which it has an exact part, I mean a fixed ratio, except six twice, four three times, three four times and two six times, these amounts are used and no others. They are four configurations besides the conjunction. Among them is the opposition, which is of six signs and contains two right angles and 180 degrees; the reason for its force is evident in itself. After it comes the configuration of the quadrature, which is half the opposition and contains three signs, one right angle and 90 parts; then the trine, which contains four signs, a right angle and a third of an angle, and 120 degrees; then the sextile, which is half the trine and contains two signs, two thirds of a right angle and 60 degrees. The conjunction, however, is not a configuration. These parts of the sphere of the signs are the ones that share configurations with one another, and no others; signs in this relation to one another are called the connected signs, and the rest, which are not connected with one another and share no configuration, are those that are one sign, five signs or seven signs apart.[372]

Since the rays of the stars, when they share in the four configurations, meet only at the centre of the earth and come together there, attention to their latitudes in that case is superfluous; but their latitudes need attention mostly at the conjunction alone. For when the meeting of two stars is a bodily meeting and their latitudes are not together on one side and of one amount, their conjunction is not a true conjunction, and the lower of them does not hide the higher; for their conjunction, when it is in the state we have mentioned, takes place in longitude and in latitude, and when they are not on one side and of one amount, their conjunction is in longitude without latitude, and that conjunction is not called a true bodily union, above all when they are on different sides, for then no meeting is counted for them at all. When they are united bodily in longitude, latitude and side, they remain in conjunction until one of them moves away from the other by half of their two bodies.[373]

Ar. p. 195

It is also said of the applications that when stars are going towards the sextile, the quadrature or the opposition of other stars, they are applying to them; when they equal them in the number [of degrees], the application is complete; and when the light ones have passed the heavy ones, they are separating from the heavy ones until they apply to other stars; if they do not apply to others, they are called separating.[374]

Likewise of the lights of the stars and their force in the applications it is said that the force of the sun in the applications reaches 15 degrees before it and as many behind it; the force of the moon reaches 12 degrees before and behind it; likewise the force of Jupiter reaches 12 degrees before and behind it as well; the force of Venus 8 parts before and behind it; the force of Mars 7 parts before and behind it; likewise the force of Mercury 7 parts before and behind it; and likewise the force of Saturn 7 parts before and behind it too. As for the force of the strong amounts, they are the amounts that we mentioned in the chapter on the size of the bodies, with the arcs of the circle of the sphere that their diameters subtend, above all of the upper ones; we have explained

[371] The tables are on ff. 239v–240r of the codex; their use is explained in the fifth of the short chapters after chapter 57 (Nallino).

[372] These are Ptolemy's aspects (*Tetrabiblos* I 14; Nallino). Plato of Tivoli adds signs eleven apart, which are as unconnected as those one sign apart.

[373] That is, until their centres are apart by half the sum of their diameters. Ptolemy (*Tetrabiblos* I 24) leaves the interval unstated; the two Latin versions of the *Tetrabiblos* made from the Arabic give half the two bodies, as here (Nallino's commentary).

[374] The bracketed words are supplied by Nallino. The light stars are the faster ones, the heavy the slower.

this fully before.[375]

It has also been said that the parts of the signs whose distances from the two solstitial points, the head of Cancer and the head of Capricorn, are equal, on the preceding side and on the following side, look at one another and are equal in force, because the day of each of the two parts is equal to the day of the other. For example, 10 parts of Cancer equal 20 parts of Gemini in force, because the distances of these two parts from the beginning of Cancer are equal and the day of one equals the day of the other; those of these parts that look at one another are called equal in force for this reason. Likewise the parts equally distant from the head of Capricorn are also equal in force: for example, a star at 5 parts of Sagittarius and another star at 25 parts of Capricorn are, at these two distances, equal in force.[376]

Ar. p. 196

Likewise also the parts whose distances from one of the two equinoctial points are equal, on the preceding side of the signs and on the following side, are called the commanding and the obeying; they are also said to be the high and the low. Those that hear and obey [the others] are the low ones, and those that are obeyed are the high ones. The parts in the southern half of the sphere, from the beginning of Libra to the end of Pisces, are the low ones, and the parts in the northern half of the sphere, from the beginning of Aries to the end of Virgo, are high above those parts; for the amount by which the day increases at these northern parts is the amount by which it decreases at those southern ones, when they are equally distant from one of these two points. For example, 20 degrees of Pisces hear and obey 10 parts of Aries, because the increase of the day at 10 of Aries is equal to the decrease at 20 of Pisces.[377]

These amounts that we have mentioned in these two kinds may coincide and fall in one of the configurations. So it happens and comes about that the beginning of Sagittarius is connected with the beginning of Aquarius and shares with it the configuration of the sextile, while their distances from the beginning of Capricorn are equal, so that it combines both; likewise the beginning of Pisces shares a configuration with the beginning of Taurus, and the beginning of Pisces hears the beginning of Taurus, so that it combines both as well. This may also happen with the trine, the quadrature and the opposition: the middle of Taurus may be in quadrature with the middle of Leo, the middle of Aquarius in quadrature with the middle of Taurus, the beginning of Taurus in trine with the beginning of Virgo, the beginning of Capricorn in trine with the beginning of Taurus, and the head of Cancer in opposition to the head of Capricorn, while the distances of these parts from the solstitial point and the equinoctial point are equal; and likewise the beginning of Aries is opposite the beginning of Libra.[378]

The wandering stars may also apply to the fixed stars, when there is between them the distance of a sextile, a trine, a quadrature or an opposition; likewise the wandering and the fixed stars cast their rays on the circle of the sphere of the signs at different amounts, which increase and decrease with the difference of the latitudes, so that when the amount between the two stars is known, it is known whether they are in one of the configurations of the applications. As for the fixed stars, because of the slowness of their motion no account is taken in these configurations of the application of the wandering stars to them, nor of the casting of their rays on the circle of the signs, their distance from the circle of the signs being always the same; but one looks to the configurations that they have with them at the cardines, and to the bodily union, above all with the sun. As for the wandering stars, one needs to know their distances from one another and

[375] Ptolemy gives Jupiter 12 degrees and Venus 8 (*Tetrabiblos* III 10); Porphyry gives the sun 15 degrees on each side, the moon 12, Saturn and Jupiter 9, Mars 8, Venus and Mercury 7 (Nallino's commentary). The chapter on the size of the bodies is chapter 50 (Nallino).

[376] The parts that look at one another and are equal in force are Ptolemy's (*Tetrabiblos* I 16; Nallino).

[377] The commanding and obeying parts are Ptolemy's (*Tetrabiblos* I 15; Nallino). The bracketed words are added for the sense.

[378] The beginnings of Capricorn and of Taurus are in trine, but they are not equally distant from a solstice or an equinox; the pairs in trine that are are the beginnings of Taurus and Virgo, of Leo and Sagittarius, of Scorpio and Pisces, and of Aquarius and Gemini. Nallino's translation has the same example. The other examples hold.

the amounts at which they cast their rays on the circle of the signs according to their latitudes, at nativities and in the directions from one to another.[379]

Ar. p. 197

As for the opposition, it is evident that it is complete only if the two stars are both on the circle of the signs, or the latitude of each of the two stars is equal to that of the other and they are on different sides. If one of the two stars is on the circle of the signs and the other is inclined from it in latitude, the distance between them is then less than the distance of the opposition by the latitude of the star; and if the latitudes of the two stars are one latitude on one side, the distance between them is less than the opposition by the two latitudes together. As for the quadrature that falls from any of the stars on the circle of the signs, it is always in one state, neither more nor less than 90, whether the latitude is great or small; this is evident on the sphere on whose poles the circles fall. As for the sextile, if the star has a latitude, its ray is cast on the circle of the signs at less than 60 parts from the part in which it is, and its ray of the trine is cast at more than 120 by as much as the sextile falls short.[380]

If you wish to know at how many parts a star that has a latitude casts its ray of the sextile and of the trine on the circle of the signs, subtract the latitude of the star from 90 and find the chord of the remainder in the tables of halved chords: it is always the full chord of the second side, which we have mentioned in the chapter on the diagonals of quadrilaterals earlier in this book, and in this chapter in which we are, at this place only. Keep it: it is the chord of the second side. Then find the full chord of the latitude of the star, by taking half its latitude, finding its halved chord and doubling it: the result is the full chord of the latitude of the star. Multiply it by itself and keep the product under its name. Then take the full chord of the second side that you kept and multiply it by 60; to the product add this product of the chord by itself that you kept under its name, and take the root of the sum. Of what results take what exceeds 60, multiply it by itself, and divide the product by the full chord of the second side that you kept; subtract what results from the division from 60: the remainder is the corrected chord. Keep it. Then take the excess of the root over 60 once more, a second time, multiply it by the full chord of the second side that was kept, and divide the product by the corrected chord: the result is the share of the correction. Keep it. Then take the full chord of the latitude of the star multiplied by itself and subtract it from 3600, which is the full chord of the sextile multiplied by itself; take the root of the remainder, and from the root that results subtract the share of the correction that you kept: the remainder is the corrected second side. Note it. Then subtract the full chord of the latitude multiplied by itself from 3600 once more, and divide the remainder by the corrected second side: the result is the chord that you want. Turn it into an arc as you turn full chords into arcs, by taking half of it and finding its arc in the table; double the arc that comes out: the arc that results is the amount of the star's sextile, on whichever side its latitude is. Subtract it from 180: the remainder is the amount of the star's trine. Subtract each of these two amounts from the part of the star, and add each of them to the part of the star as well, and note where the part of the star comes after the addition or the subtraction: the diminished position is the position of its first sextile and trine, and the increased position is the position of the second trine and sextile, from which they fall on the circle of the signs, if God wills.[381]

[379] «Their distance from the circle of the signs being always the same» renders «when their distance from the circle of the signs is one distance»; Nallino's translation has «when they are distant from it by some aspect». The directions are the astrologers' way of timing events by the arc through which a point of the horoscope is carried to the place or the ray of another star.

[380] The quadrature stays 90° because the two points of the ecliptic 90° from the star are the poles of the great circle drawn through the star at right angles to the ecliptic, and so are 90° from its foot on the ecliptic as well; the rays of 60° and 120° lie on one great circle and meet the ecliptic at two opposite points, so that the sextile and the trine on the ecliptic together make 180° (Schiaparelli, in Nallino's commentary). Ibn Yūnus objects that by al-Battānī's principles a star with a latitude of 60° has no sextile at all; the astrologers, however, use the rays of the planets only, whose latitudes are far smaller (Nallino's commentary).

[381] The translation reads «التي» for «الني» (p. 197, line 13), a misprint that the corrigenda do not list. The chapter on the diagonals of quadrilaterals is chapter 26 (Nallino). The exact amount x of the sextile for a latitude β follows from

Chapter 55. On knowing the ascensions of the signs between the cardines, in the quarters of the sphere

Ar. p. 198

Al-Battānī said: What must follow what we have described of the amounts of the rays on the circle of the signs is the knowledge of the ascensions of the signs between the cardines. Their ascensions have been known only in the right sphere, which are their ascensions at the cardine of the middle of the sky and the cardine of the earth, and in the climes, which are their ascensions and settings at the two horizons, the cardine of the ascendant and the cardine of the setting point of the circle of the horizon of each town; and what we have described differs in amount. So what remains of the kind of the ascensions is that you know the ascensions of the signs between these cardines, in the regions of the sphere, so that you know in how many times of the equator one of the signs rises at any place of the sphere. By this you know the amount of the times of the equator that lie between the preceding degree of the sphere of the signs and the following degree, in times of the passage of the preceding degree at that place.[382]

Ar. p. 199

For example, the whole sign of Aries rises at the middle of the sky with 27;53 of the times of the equator and passes the cardine of the earth with as many; in the fourth clime it rises with 19;12 of the times of the equator, and in this clime it sets with the amount with which Libra rises in it, which is 36;34. Between each of these cardines and the cardine next to it there are 6 seasonal hours, which are the hours of one quarter of the quarters of the day and the night: in the two quarters above the earth its hours are hours of the day, and in the two remaining quarters, below the earth, its hours are hours of the night. When the sign of Aries moves away from one of these cardines, the amounts of its ascensions vary, becoming more or less than these amounts that we have mentioned, according to the number of seasonal hours by which the beginning of Aries is distant from the cardine with which the comparison is made. Let us first suppose the beginning of Aries to be 2 seasonal hours from the middle of the sky towards the east: the ascensions of Aries there become less than its ascensions at the middle of the sky by 2;54, which is a third of the difference between its ascensions at the middle of the sky and its ascensions in the clime at the eastern horizon, as the 2 hours by which it is distant from the middle of the sky are a third of the 6 hours between the middle of the sky and the ascendant. When the beginning of Aries is 3 seasonal hours from the middle of the sky on this side, its rising there is less than its rising in the right sphere by 4;20, which is half the difference between its rising in the right sphere and its rising at the horizon of the clime; until it comes to the ascendant, where its rising is less than its rising in the right sphere by 8;41, the whole difference between them in the ascensions. Let us suppose too the beginning of Aries to be 2 seasonal hours from the middle of the sky towards the west: since its settings in this western half are like the ascensions of Libra, its settings at this distance are greater than its ascensions in the right sphere by a third of this difference, which is 2;54; when its distance is 3 hours on this side, its passage there is greater than its passage in the right sphere by half the difference, which is 4;20; until it comes to the western horizon, where its passage and crossing in its setting is greater than its rising in the right sphere by the

---

the right spherical triangle whose hypotenuse is the ray of 60° and whose legs are the latitude and x: cos x = cos 60° / cos β. In the terms of chapter 26, with chords in a circle of radius 1, crd² x = (crd² 60° − crd² β) / cos β. Nallino takes the long rule of the text for the work of an interpolator and restores this one as al-Battānī's; the Alfonsine *Libro de las taulas* gives it as al-Battānī's method (Nallino's commentary). The rule of the text begins with the chord of the second side that an arc of 60° would give, 60 cos β, and ends with the theorem of chapter 26, dividing 3600 − crd² β by a corrected second side. Read as the Arabic has it, the rule is not exact but close: it falls short of the exact amount by less than 1″ at a latitude of 5°, by 13″ at 10° and by 3′ at 20°. Nallino's translation squares the excess of the root over 60 a second time in finding the share of the correction, where the Arabic takes the excess itself; with the square the rule falls short by 7′ at 5° and by 17′ at 10°.

[382] The translation follows Nallino's emendanda (Part II, p. XXXI) in reading «وفي الاقاليم», «and in the climes», for «في الأقاليم» (p. 198, line 5). The cardines are the four points of the ecliptic on the horizon and the meridian (chapter 35). The ascensions between the cardines are what the astrologers need for their directions: to direct one point to another is to find the arc of the equator after which the first reaches the circle of position drawn through the second (Nallino's commentary).

whole difference, 8;41. Likewise, when its distance is from the cardine of the earth towards the ascendant, it goes the way it goes between the middle of the sky and the ascendant; and when its distance is from the cardine of the earth towards the setting point, the matter is as it was between the middle of the sky and the west.[383]

Ar. p. 200

If you wish to know the ascensions of any degree you like, in whatever region of the sphere you want, begin by finding the distance of the degree you want, or of the star you want, from one of the cardines. This is found by looking at the degree or the star you want. If it has no latitude, it goes the way of the degree of the signs in which it is: find the times of the hours of the day and of the night of the degree, whichever degree of the sphere you like, which is the degree in which the star is, or another of the degrees of the signs. If the star has a latitude, find the degree that culminates with it and the times of its hours above the earth and below it: find half its stay above the earth and take a sixth of it, which is the times of an hour above the earth; subtract that from 30, and the remainder is the times of its hours below the earth, as we explained at the beginning of the book. You use the degree that culminates with it in place of the degree in which it is [if it has a latitude, and you use the degree in which it is] if it has no latitude; and likewise the times of the hours of the star in place of the times of the hours of its degree that [culminates with it]. If whichever of the two degrees you use is above the earth, take its distance from the part of the middle of the sky by the ascensions of the right sphere; if it is below the earth, take its distance from the part of the cardine of the earth, again by the ascensions of the right sphere. Subtract the ascensions of the degree of the middle of the sky from the ascensions of the degree that you use if it is on the eastern side of the middle of the sky, and subtract the ascensions of that degree from the ascensions of the degree of the middle of the sky if it is on the western side; and do the same with its ascensions and the ascensions of the part of the cardine of the earth in the right sphere, so that you know the distance between the degree you want and the degree of the middle of the sky or of the cardine of the earth in the right sphere. Divide the times of the distance that you have by the times of the hours of the day if the degree used is above the earth, or by the times of the hours of the night if it is below the earth: the hours that result are the distance of the star or of the degree from one of the two cardines, either the cardine of the middle of the sky or the cardine of the earth. Whether the star or the degree is below the earth or above it is known as I shall describe: look at the part that you want to use of the two parts; if it lies between the degree of the ascendant and the degree of the setting point in the order of the signs, that degree is below the earth, and if it lies between the degree of the setting point and the degree of the ascendant in the order of the signs, it is above the earth. You know this another way too: look at half the stay of the star above the earth; if it is more than the times between the degree of the middle of the sky and the degree that culminates with the star, in the right sphere, you know that the star is above the earth, and if half its stay above the earth is the less, you know that it is below the earth. When you know how many seasonal hours the star, or the degree in which it is, is distant from the middle of the sky or from the cardine of the earth, and you wish to know its distance from the ascendant or from the setting point, subtract those hours from 6: the remainder is its distance from one of these two cardines, I mean the cardine of the east or the cardine of the west.[384]

Ar. p. 201

Whenever you wish to know the ascensions of any degree you like at the place of the regions of

[383] The translation follows the corrigenda in reading «البا**قِ**يَنْ», «remaining», for the misprint «البا**فِ**يَنْ» (p. 198; the corrigenda give line 15 for line 17). 27;53 is the right ascension of Aries with al-Battānī's obliquity of 23;35; 19;12 is its ascension at a latitude of 36° with Ptolemy's obliquity of 23;51, which with al-Battānī's own gives 19;21. The rule makes the ascension change in proportion to the seasonal hours from the meridian: 27;53 − 19;12 = 8;41, of which a third is 2;53,40 and a half 4;20,30, and 27;53 + 8;41 = 36;34.

[384] The words in the first brackets are supplied by Nallino after Plato of Tivoli; for the words in the second the codex has «in which it is», and Nallino follows Plato. For a star with latitude al-Battānī takes the degree that culminates with it for the right ascensions and the degree that rises with it for the oblique ones, where Ptolemy, like Alcabitius and others, treats the points as if they had no latitude (Nallino's commentary). The hours above and below the earth together make 30 times, a twelfth of the circle, since the arcs of the day and of the night make 360.

the sphere where that degree happens to be, it is clear from what we have described that by this the amount of the times of the equator between the preceding degree of the sphere of the signs and the degree on the side following it is known, as the amount between two degrees is known by the ascensions of the clime and the ascensions of the right sphere: that is, to know in how many times of the equator the following degree of the sphere of the signs travels to the place where the preceding degree was. Look: if the given preceding degree is between the middle of the sky and the cardine of the earth on the eastern side, it is in the eastern half of the sphere, and if it is between the middle of the sky and the cardine of the earth on the side of the west, it is in the western half. If it is in the eastern half of the sphere, find how many seasonal hours it is from the middle of the sky, the cardine of the earth or the ascendant, whichever you like, and keep them. Then look at the following degree: if it is with it in the eastern half of the sphere, take the distance between the two degrees by the ascensions of the right sphere and the distance between them by the ascensions of the given clime. If the two numbers are equal, that is the distance of the preceding degree from the following degree in times of the equator. If they differ, subtract the smaller from the larger and take a sixth of the remainder, which is the share of one hour of the difference; multiply it by the hours of the distance of the preceding degree from whichever of the cardines you like to make the comparison with, I mean the middle of the sky, the cardine of the ascendant or the cardine of the earth. If you multiplied it by the hours of the distance of the degree from the middle of the sky or the cardine of the earth, add the product to the times of the ascensions between the two degrees in the right sphere if they are less than those between them by the ascensions of the clime, and subtract it from them if they are the greater; and if you multiplied it by the hours of the distance of the degree from the ascendant, add the product to the times between the two degrees by the ascensions of the clime if they are the less, and subtract it from them if they are the greater. What the times of the ascensions of the cardine with which you compared come to, after the addition to them or the subtraction from them, is the distance between those two degrees by the ascensions of the place of the preceding degree, where it is in the eastern half of the sphere.[385]

Ar. p. 202

If the given preceding degree is in the western half of the sphere and the following degree is with it in this half too, take the times of the ascensions between them in the right sphere and the times of the ascensions in that clime between the two degrees opposite those two degrees, which is the amount between the two degrees by the times of the settings of the clime. Then take a sixth of the excess between these two numbers and multiply it by the hours of the distance of the degree from whichever cardine you like, the cardine of the earth, the cardine of the west or the cardine of the middle of the sky, whichever you want. Add the product to the times of the ascensions or the settings that you have from the cardine with which you compared, if they are the less, and subtract it from them if they are the greater, in the manner given before: that is, if your comparison is with the cardine of the west, add it to the settings between the two degrees in the clime if they are less than what is between them in the right sphere, and subtract it from them if they are the greater; and if you compared with the cardine of the earth or the middle of the sky, add it to what is between the two degrees by the ascensions of the right sphere if they are the less, and subtract it from them if they are the greater. The result is the distance between the two degrees by the settings of the place of the sphere where the preceding degree was.[386]

If the place of the given preceding degree is in one of the two halves of the sphere and the following degree in the other half, find the amount between the preceding degree and the middle of the sky if it is in the western half, or, if it is in the eastern half, between it and the cardine of the earth, by this method that I have described to you; to the result add what lies between the part of the middle of the sky or of the cardine of the earth and the following degree by the

[385] Nallino's commentary works out the rule as: arc = $\alpha + (\beta - \alpha) \times$ the seasonal hours of the preceding degree from the meridian $\div 6$, where α is the difference of the right ascensions of the two degrees and β the difference of their ascensions in the clime.

[386] In every clime a sign sets with as much as its counterpart, the opposite sign, rises with (chapter 13).

ascensions of the right sphere: the sum is the amount between those two degrees.[387]

Ar. p. 203

If you wish to know this another way, find the hours of the distance of the given preceding degree from the cardine, as I have described to you. Then look: if the preceding and the following degrees are between the middle of the sky and the ascendant, or the preceding part is there and the following part between the ascendant and the cardine of the earth, that is, both in the eastern half, multiply the times of the hours of the day of the following part, which are the times of the hours of that part itself, by the hours of the distance of the preceding part from the middle of the sky, and subtract the product from the times between the part of the middle of the sky and the following part by the ascensions of the right sphere. If the preceding part and the following part are in the western half of the sphere, which is from the cardine of the earth to the middle of the sky on the side of the west, multiply the times [of the hours of the night of the following part by] the hours of the distance of the preceding part from the cardine of the earth, and subtract the product from the times of the ascensions between the part of the cardine of the earth and the following part in the right sphere. If the preceding part is in one half and the following part in the other, that is, the preceding part between the ascendant and the cardine of the earth and the following part between the cardine of the earth and the setting point, multiply the times of the hours of the night of the following part, taken from its counterpart, by the hours of the distance of the preceding degree from the cardine of the ascendant, and subtract the product from the times of the ascensions between the rising part and the following part by the ascensions of the clime. If the preceding part is between the west and the middle of the sky and the following part between the middle of the sky and the ascendant, that is, in different halves, multiply the times of the hours of the day of the following part by the hours of the distance of the preceding part from the cardine of the west, and subtract the product from the times of the ascensions, in the given clime, between the degree opposite the degree of the setting point and the degree opposite the following degree. What remains, whichever of the numbers it is, is the distance between the two degrees in times of the ascensions of the first degree or of its settings. In the same way, conversely, one also knows how many times of the equator ago the preceding part left the place of the following part. These amounts are needed above all in nativities, in directing the significators in their places; this is what Ptolemy mentioned in the book of the Four Treatises that Ptolemy composed on foreknowledge of events from the science of the stars; and in the same way the haylājs are directed for the lengths of life.[388]

[387] Beyond the meridian the following degree must go on, along its own parallel, as many of its own seasonal hours as the preceding degree is from the meridian; Nallino notes that the codex and Plato of Tivoli do not say that the hours of the preceding degree are to be multiplied by the times of the hours of the following one, and that without this the rule is not right (Nallino's commentary).

[388] The bracketed words are supplied by Nallino after Plato of Tivoli. This rule is Ptolemy's, who sets it out with a worked example in the *Tetrabiblos* III 10 (Nallino's commentary). Ptolemy counts as the same place of a point the place that has the same position with respect to the horizon and to the meridian, that is, the same number of seasonal hours from the meridian; on that definition both rules of this chapter are exact and give the same arc. Schiaparelli, in Nallino's commentary, takes the circle of position to be the great circle through the north and south points of the horizon, on which Ptolemy says such places lie only nearly, and holds the error of the rules small for the declinations of the planets in the latitudes of al-Raqqa, Antioch and Baghdad. At a latitude of 36°, three hours from the meridian, that circle departs from the seasonal hours by 3.8° of the equator for a point on the equator and one 24° north, and by almost 10° for points 24° south and 24° north; in a direction for a nativity a degree of the equator counts as a year (Nallino's commentary). The significator is the star or point that governs a life, which the Arabs also call by the Persian name haylāj; Nallino takes the last words, on the haylājs, to be probably an interpolation.

Chapter 56. On making a horizontal and a vertical instrument, with each of which the seasonal hours that have passed of the day are known in every town; it is also called the sundial

Ar. p. 203

Al-Battānī said: If you wish to know the seasonal hours that have passed of the day, from sunrise to sunset, with the horizontal instrument, from the sun's shadow on its surface, take a slab of marble or a plate of copper with a level surface and a smooth face, of any size you like; it is best that its width be two thirds of its length. Mark a point at two thirds of the width, on the middle of the length; take it as a centre and draw about it a circle of any size you like. Then divide the circle into quarters by two lines that cut each other at its centre at right angles and divide the circle into equal quarters, and divide each quarter into 90 parts, exactly, at intervals of a degree or more, as the size of the circle allows. Then find the shadow of the beginning of Cancer and of the head of Capricorn for 1, 2, 3, 4, 5 and 6 seasonal hours, and the azimuth of the shadow at each of these hours on the circle of the horizon, by the methods given to you at the beginning of the book, in the chapter on knowing the azimuth of the shadow and of the altitude for the parts of the signs in every town: that is, find the altitude of each of these hours, and from it find its shadow and its azimuth in the manner given before, in any town you like.[389]

Ar. p. 204

Then take a ruler with straight edges, one of whose faces is divided into as many equal parts as you like, provided they are as many as the number of the shadow of the head of Capricorn or more. Put the first point, from which you began, on the edge of the ruler, on the point of the centre of the circle, and lay the edge of the ruler along the azimuth of the shadow of one hour of the hours of Capricorn, towards the wide side of the slab, beginning the count of the azimuth from the point of the east on the circumference of the circle. Then count off on the ruler, from the point of the centre, as many parts as the shadow of the first hour, and mark there, at the edge of the ruler, a point, which is the mark of the shadow of one hour. Do the same for the shadow of two hours and the azimuth of two hours, and of three, four and five, until you come to six hours, when you mark the place of the shadow on the line that cuts between the north and the south, on the wide side, which is the meridian line. Then turn the ruler to the other quarter, next to the meridian line, and do in it as you did in the quarter before, so that the shadows of one hour, two, three, four and five fall on both sides of the meridian line, on the wide side of the slab, towards the east and the west, for the beginning of Capricorn; mark a point at the shadow of each hour. Then do the same with the azimuths of the hours of the head of Cancer, putting their shadows on the other, narrow, side of the slab, as you did with the hours of Capricorn, on both sides of the meridian line, until the shadow of the end of the sixth hour falls on the meridian line.

It is known that when the azimuth is northern, it lies towards the narrow side of the slab from the line between the east and the west, and when it is southern, towards the wide side of this line. Then join the points marked for the hours of the head of Cancer and of the head of Capricorn with straight lines, running from the point of the first hour of the hours of Cancer to the point of the first hour of the hours of Capricorn, and likewise from the point of two hours to the point of two hours, up to the end of the five hours on both sides of the meridian line. Likewise join all the points of the hours of Capricorn to one another, and the points of the hours of Cancer, by lines across the slab, which end on both sides, from the point of the first hour to the sixth, marked on the meridian line; so that the place of the shadow is a known passage on the slab, which it does not go beyond.[390]

Ar. p. 205

Then set up at the centre of the circle on the slab a style of copper or iron, round, turned on the lathe, with a pointed head, and let what shows of it above the surface of the slab be 12 parts of the parts of your ruler with which you took the amounts of the shadow. Check this style with the

[389] «Sundial» renders «al-rukhāma», literally «the marble slab». The chapter on the azimuth of the shadow and of the altitude is chapter 11 (Nallino).

[390] «Narrow» is Nallino's reading here and below; the codex has «الصيفية», «summer», for «الضيّقة» in several places.

compasses, from the sides of the circle to its pointed end, so that you know that it stands truly upright on the centre. Make the hole that you bore for the style, at the place of the centre, go through to the other side of the slab, so that the end of the style that enters the hole is fastened from the other side firmly, so that it neither shakes nor moves. Then make the wide side of the slab its northern side and the narrow side its southern side, so that the point of the north falls on the meridian line on the wide side and the point of the south on the meridian line on the narrow side, and the point of the east and the point of the west fall in their places on the line at right angles to the meridian line, which is the line between the east and the west. Begin the hours from the side of the west, in the wide part of the slab, and write the first hour, the second and the third under each of the points of the hours of Capricorn, up to the end of the eleventh. With the dial one cannot know more than the time from the end of the first hour of the day to the end of the eleventh, because of the length and spread of the shadow at the two ends of the day, for which a very large instrument would be needed to receive the surface of the shadow. If you wish to divide between the hours into halves and thirds, more or less, find the azimuth and the shadow of each fraction that falls between those hours and mark it as you wish; that is not difficult.

When you have finished making the dial, go to a place where the horizon lies open from the first hour of the day to the end of the eleventh; draw a circle there and find in it the meridian line in the way described at the beginning of this book. Then lay the meridian line drawn on the dial on the meridian line that you found with the circle, fitting it exactly, neither inclined nor turned aside, so that the southern direction of the dial, which is the narrow side, faces the south of the line along its direction, and the wide, northern, side accordingly lies along the meridian line towards the north. Let the upper surface of the dial be parallel to the plane of the horizon, levelled with the plumb line and inclined to no side. Then from the place where the end of the style's shadow falls on the lines of the hours, the seasonal hours that have passed of the day are known in every town whose latitude is the same as the latitude for which you made the dial.[391]

Ar. p. 206

The setting of the dial can also be adjusted another way. Find the altitude whose azimuth has no inclination, in the way that I explained to you at the beginning of the book; then watch the altitude, and when it has come to the amount of the altitude you worked out [for it], turn the dial until the shadow of the style falls on the line between the east and the west. When that is right, the setting of the dial is right, provided its face is levelled and not inclined. If you like, find the altitude of one hour, or of two or three: when you know it by computation, watch the shadow, and when the altitude has come to the one you want, turn the dial until the shadow of the style falls on the line of the hour for which you found the altitude. You can also find the azimuth of the altitude you want; then watch the altitude, and when it is equal to the altitude whose azimuth you found, turn the dial until the shadow of the style falls at the amount of the azimuth of that altitude on the circle drawn. If the shadow does not reach the circumference of the circle, tie a thin thread to the foot of the style and stretch it out to the amount of the azimuth from the limit of the east or of the west, on the side on which it is at the time of the observation; then turn the dial until the middle of the shadow of the style falls on that thread. Then the dial is set right, and the line of the sixth hour falls in line with the meridian line, along its direction, if God wills.[392]

If you wish to find from this chapter the azimuth of Mecca, which is the azimuth of the qibla for prayer, so as to draw a line along it from the centre of the circle, the line being the azimuth of the qibla in that town, find the latitude of the town in which you are and the latitude of Mecca, and find the direction of Mecca, God guard it, from that town, whether it is north of it or south. Find the longitude of Mecca and the longitude of the town and subtract the smaller from the larger,

[391] The meridian line is found in chapter 12 (Nallino).

[392] The altitude whose azimuth has no inclination is the altitude of the sun when it stands due east or due west, where its azimuth, counted from the east and west points, is nothing (chapter 12; Nallino). The bracketed words are Nallino's conjecture.


so that you know the amount between them in longitude, and where Mecca lies from that town, towards the east or towards the west: if the longitude of Mecca is greater than the longitude of the town set down in the tables of the latitudes and longitudes of the towns, Mecca is east of the town, and if it is less, Mecca is west of the town. Then put the end of the ruler at the number of the latitude between them, counting it from the line of the east towards the side on which Mecca lies in latitude, and likewise from the line of the west towards that side, on the circumference of the circle, so that the edge of the ruler passes at the amount of the latitude between them; and draw along the edge of the ruler a line joining the eastern mark and the western. Take also the difference between them in longitude and count as much on the circumference of the circle from the meridian line towards the side on which Mecca lies in longitude, on the southern part of the circumference, and count as much again on its northern part; put the edge of the ruler on the two marks and draw along its edge a straight line. Where these two lines cut each other is the place of Mecca in its azimuth from that town. Put the edge of the ruler on the centre of the circle and on the place of the intersection, and draw along it a straight line, carrying it out on the dial to the southern circumference of the circle: that line is the azimuth of the qibla in that town.[393]

Ar. p. 207

If you wish to know the amount of the azimuth of the qibla by computation, take the chord of what lies between the two towns in longitude and the chord of what lies between them in latitude; multiply each of them by itself, add the two, and take the root of the sum: the result is the hypotenuse of the triangle, which subtends the right angle, and it is the distance between the centre of the circle and the place of the intersection made by the lines of the longitude and the latitude in the circle. Keep it. Then go back to the chord of what lies between the two towns in latitude, multiply it by the half diameter and divide by the hypotenuse of the triangle; turn the result into an arc: the arc that results is the azimuth of Mecca. Count as much on the circumference of the circle from the point of the azimuth of the east or of the west, according to the place of Mecca from that town in longitude, towards the side on which Mecca lies in latitude; where it ends, make a mark on the circumference of the circle, and draw a straight line from the centre of the circle to that mark: that line is the azimuth of Mecca from that town.[394]

[393] The qibla is the direction of the Kaʿba at Mecca, towards which Muslims turn in prayer (Nallino).

[394] The chords here must be half chords, sines, as in the construction, where the two lines stand at the sines of the two differences from the line of east and west and from the meridian line; Nallino's translation has sines. With a the azimuth from the east or the west point, the rule is $\sin a = \sin \Delta\varphi / \sqrt{(\sin^2 \Delta\varphi + \sin^2 \Delta\lambda)}$, $\Delta\varphi$ and $\Delta\lambda$ being the differences of latitude and longitude; the construction gives the same line. This is not the azimuth of the great circle to Mecca. Nallino explains the simplification as meant for the builders of mosques, for whom an error of a few degrees did not matter (Nallino's commentary). With al-Battānī's coordinates, al-Raqqa at 73;15 of longitude and 36;0 of latitude and Mecca at 77;53 and 21;40, the rule gives 71;56 from the east towards the south and the great circle 73;1. Nallino puts the error at 3° or 4° in Syria and Mesopotamia; with the positions of the towns as now known it is about 1° there, and less than 1½° at every place between 30° and 37° north within 12° of longitude of Mecca.



Divide the two remaining quarters in the manner of the division of these two quarters, if God wills.[395]

Ar. p. 208

Al-Battānī said: Take a wide, oblong, four-sided marble slab and mark its corners A B G D; take a centre at two thirds of its width and the middle of its length, marked H, draw a circle about it and divide it into quarters by two lines that cut each other at right angles, carried out to the edges of the slab. Make the one, longer, line, which runs along the length of the slab, the line between the east and the west, and the shorter line, which runs across the width of the slab, the line between the north and the south, and write on it «meridian line»; write the directions of the horizon at the ends of the lines. Make the beginning of the azimuth on the circumference of the circle at the two points of the east and the west on the longer line: what of it is southern we count towards the north, and what is northern we count towards the south, after dividing each quarter of the circle into 90 parts in black or in red, so that it leaves no lasting trace on the face of the slab; and the circle likewise. As for the two diameters of the circle, which are the two lines mentioned, we draw them by cutting, so that their trace remains on the surface of the slab. On each of the azimuths of the hours of Cancer we write the mark M, and on the azimuth of each of the hours of Capricorn the mark L, and at the place of the shadow of each hour something by which its number is known, beginning from the side of the west; and we join the points along the length and the width of the slab with the lines between the figure of the hours and their shadows on it. We put Mecca in the region of the east and the south, and mark on the arc between them in latitude M K; we take as much on the side of the west and draw through the two marks K a line parallel to the line of the east and the west. We mark on the arc between them N Ḍ, and at the place where the two lines cut each other LA, and draw the line H LA ʿ, which is the azimuth

[395] In the figure the south is at the top and the east at the left; the tens of its scale, in letters in the Arabic, are given in figures. The codex adds that the picture of the dial is drawn on the other side of the leaf; its drawing is very poor, and Nallino's translation has one drawn again by Schiaparelli from the rules of the chapter for a latitude of 36° (Nallino's commentary).

of Mecca. We make the length of the style from the mark H — it is the line H S that shows — and set it upright on the centre H. That is what we wished to show. We have made tables of the azimuths of the hours of Capricorn and of Cancer, of their shadows and of their altitudes, for a latitude of 36 degrees.[396]

The making of the vertical dial, whose upright face faces the south, is by this same method in the azimuth; only the shadows change, in the way that we have described in the knowledge of the vertical shadow. When you have finished the dial with the amounts of the vertical shadow and set its face upright on the line of the east and the west, the face of the dial looks to the south, lying across between the east and the west, with the wide side towards the earth and the narrow side upwards. It is known that the longest shadow on this dial is at the head of Cancer and the shortest at the head of Capricorn. Let the style here too be 12 parts of the parts of the ruler by which the shadow is measured; then from the place where the end of the shadow falls on the lines of the hours you know all the seasonal hours that have passed of the day. The hours are known in many ways and with various instruments, but these two instruments are the most correct of those that I have worked with, and the safest for this knowledge, if God wills.[397]

Chapter 57. On the close of the book, and the making of the egg, the brick and the alidade for observation

Ar. p. 209
Ar. p. 210

Al-Battānī said: What we have mentioned and set down in our book of the causes of things and of the derivations of the principles of the computation, which proceeds by the way of geometrical proof, is in a state that does not change, and no doubt touches it in any circumstance, through all the ages. But what is established by measurements, observations, trials and tests may be found to need correction, by excess or by defect. What of it comes from establishing the very truth of the thing, and falling short of it, becomes small when it is divided over a long time, even if it is perceptible, and what is divided over a short time becomes large, even if it is small. As for an error that arises from the instrument, in its division, its setting up and its adjustment: if one tests with that same instrument while it is in its first state, the error is the same at both times; and if the error comes from the division alone, its setting up and adjustment may be corrected if they are changed, while the error from the division remains as it was, and when one observes with another instrument the difference appears. It may also happen that over a long time the instrument changes from its state, in widening, contracting, bending and the like; the error that comes from this may increase or decrease, according as these are small or great. When one measures after that with a correct measurement in which there is no doubt, there must accumulate in it later, over a period like the one between the two times, an error like the first, if it proceeds in one way without changing. Things of this kind are sound only when the measurement is made with two instruments perfect in all respects, or with one correct instrument that has not changed from its first state in anything; and what there is in them of the shortcoming of human beings, by their nature, in reaching the truths of things in act as they reach them in potency, is slight and imperceptible with diligence and care, above all over long periods. Talent helps, and so do zeal, true observation, the use of thought and patience with things, even when

[396] The text is defective after «N Ḍ»: the codex and Plato of Tivoli lack the marking of the difference in longitude and the line through it parallel to the meridian line, which Nallino's translation supplies from the rule above (Nallino). The tables are on f. 240r of the codex; the tables for latitudes of 36° and 38° that Plato of Tivoli has here seem to be the work of a reader of that version, and do not agree with al-Battānī's (Nallino).

[397] The vertical shadow is that of chapter 10. Taken as written, the rule for the vertical dial is not right. On a wall facing south, a style 12 parts long at right angles to the wall casts the end of its shadow 12 tan A parts sideways and 12 tan h / cos A parts down from its foot, for the sun at altitude h and at azimuth A from the south; the rule puts it 12 tan h parts from the foot, in the direction of the azimuth. The two agree only when the sun is on the meridian: with the sun at 30° of altitude and 45° from the south, the rule gives a shadow of 6.9 parts at 45° below the level, the wall one of 15.5 parts at 39° below it. «The safest» renders Nallino's reading «أسلمه»; Nallino also considers «أسهله», «the easiest», for the codex's «اسلهه». Plato of Tivoli lacks the passage (Nallino).

they are hard to grasp; and much of this is hindered by impatience and by the love of glory and of favour with earthly kings, in grasping quickly what cannot truly be grasped, or in grasping what by its nature no one can grasp.[398]

Since we have come in this book to this place [and have dealt, as far as we could, with everything that had to be mentioned first, we think it right to close at this place with our description of] the instrument whose form is the form of the sphere, which is called the egg, and of the two instruments described for observation, if God wills.[399]

The making of the instrument in the form of the sphere, on which the stars of the ether are drawn, which is called the egg. Al-Battānī said: We take a ball of copper, perfectly round, true on every side, with a smooth surface, turned on the lathe, of any size you like. We mark on it two poles opposite each other on its diameter, halve the distance between the poles on the outside of the ball, and draw at the halfway mark a circle that cuts the ball in halves; we divide it into equal quarters and mark a point at each quarter. We take one of the points as a centre and draw about it a circle as large as the first, which passes through the first two poles of the ball and cuts the first circle into two opposite halves. We divide one of the quarters of the first circle into 90 and take from it the amount of the whole declination, which is 23 parts and 35 minutes; we take with the compasses as many of the parts of the quarter, put one of its points on one of the two poles and turn the other point to the second circle, whose pole is one of the points, and mark a point on it. We do the same with the other pole, turning the point of the compasses to the side opposite the first, so that one of these two points is opposite the other on the diameter of the circle as well. We take one of them as a pole and draw about it a circle midway between these two points; so we have drawn two circles that cut each other at two opposite points. We make one of the two circles the circle of the equator and the other the circle of the sphere of the signs. It is known that the pole of the circle of the sphere of the signs lies below the pole of the equator, towards the north, and that the circle that passes through the poles is the circle of Cancer and Capricorn; the point of the circle of the sphere of the signs that is above the equator is the point of the head of Cancer, and the point below the equator the point of the head of Capricorn; of the two points at which the circle of the sphere of the signs and the circle of the equator cut each other, one is the point of the head of Aries and the other the point of the head of Libra.[400]

Ar. p. 211

We draw the signs in their order, making each quarter three signs, divided equally, each sign into six cells with 5 parts in each cell, and we write on the cells the totals of the count in the letters of the abjad, up to 30 parts. We complete the division of the circle of the equator into 360 parts, in which there are 72 cells, and write in each cell its number in the letters of the abjad, up to 360 parts, beginning the writing from the point that cuts the head of Aries, so that the end of the 360 also falls at the beginning of this point, which is the end of its twelfth sign.[401]

We draw the positions of the fixed stars in all the constellations, or those of them that we like, in the way that I shall describe. We take with the compasses from the circle of the equator the amount of the latitude of the star, put one point of the compasses on the part in which the star is and turn the other point towards the side of the latitude, drawing a faint line that leaves no lasting trace on the ball. Then we take other compasses, opening their points to a quarter of the circle that goes round the ball, and put one point on the quadrature of the star's part on the circle of the signs, 90 parts from the star's degree; the other point then necessarily falls on the part in which the star is. We turn it towards the line that we drew for the latitude with the other

[398] Ptolemy makes the same points on the errors of instruments and on long intervals (*Almagest* III 1; Nallino).

[399] The bracketed words are restored by Nallino in the commentary, in place of «فوصفنا», «we have described», where the printing left them out (Part III, p. 210, line 2).

[400] The instrument joins the uses of Ptolemy's spherical astrolabe (*Almagest* V 1) and of the solid sphere (*Almagest* VIII 3); al-Battānī may have been the first to devise it (Nallino's commentary). 23;35 is al-Battānī's obliquity of the ecliptic.

[401] The letters of the abjad have the values of numbers.

compasses: where the two lines cut each other is the centre of the star, and we draw it there; and so until we have finished all that we want of them in this way, each according to its place in longitude and latitude, having drawn first, if we like, through each sign a circle passing through it and through the two poles of the sphere of the signs, to show the divisions of the signs more clearly. So there are twelve circles on the outside of the ball, passing through the poles of the sphere of the signs and dividing the signs.[402]

Then you take a ring of copper with square faces, true in its roundness and its edges, its thickness the breadth of a thumb and its breadth as much as its strength requires, so that it does not shake; and you take another ring like it, made in the same way, striking its inside with the compasses of the inside of the first and its outside with the compasses of its outside, and you file it until it is even on every side and true in its roundness. Make the width of each of these two rings the amount of the diameter of the ball, so that the ball turns inside these two rings, fitting them closely. You take two other rings, making the thickness of one of them a third of the thickness of one of the two [first] rings and the other two thirds of that thickness, so that when the smaller of these two is set in the larger they are like one of the two rings: that is, you strike the inside of the smaller with the compasses of the inside of the two rings and its outside as is fitting, and the inside of the larger with the compasses of the outside of the smaller and its outside with the compasses of the outside of the two rings. You take also a fifth ring, striking its inside with the compasses of the outside of the large rings mentioned above and its outside as is fitting, so that these rings turn inside this ring, fitting it closely, without play or shaking in any of these rings; and let its faces be even.[403]

Ar. p. 212

Then you take one of the two first rings as the ring of the horizon, and divide it and the rest of the remaining rings into equal quarters, dividing each quarter into 18 cells of 5 parts each, so that each quarter has 90 parts; you write in the cells, in the letters of the abjad, what is due to them, beginning the count from one of the quarters up to the end of the 90 on both sides; you divide the opposite quarter in the same way and write it in the letters of the abjad as well, so that the 90, which would fall in four places of the ring, falls in two places of it, fixed at the end of each quarter. On one of the two places where the 90s meet you write «the point of the north», and on the place opposite it «the point of the south». You set a mark on the small ring at one of its quarters and make it the north pole, and the one opposite it, half the ring away, the south pole; you bore this ring at these two opposite places with a hole in the middle of its breadth and thickness, and likewise you bore the two poles of the equator in the ball, and fix the ball in this small ring at these two places. We nail it with two nails filed flush with the outside of the ring, so that the ball turns on the two poles of the equator, which are these two poles. Then we fit on it the ring inside which this one lies, after dividing it into 360 parts and 72 cells and writing on it in the letters of the abjad as we wrote before, except that the letters written in the cells reach to the edge of the ring and those that fall in the circle of the horizon two thirds of that; we make the writing in the manner given before, so that the 90s meet in two opposite places, twice in each place.

Ar. p. 213

Then, from the place where the count began, towards the lower part of the ring, we cut a notch sunk into this ring to half its thickness, making the width of the notch the thickness of the ring of the horizon; this notch is on the outside of this ring; and we cut a like notch at the opposite place as well. Then we cut in the ring of the horizon, on its inside, a notch as deep as the notch in the other ring together with the thickness of the small ring, making the notch on both sides of the line of the north and the south, evenly, as wide as the thickness of the ring in which we cut the first notch. Then we fit one of the two rings into the other on the ball, so that the plane of the circle of the horizon bounds the upper half of the ball, the thickness of the ring lying towards

[402] The second compasses, opened to a quarter of a great circle with one point 90 parts from the star's longitude, draw the circle through the poles of the ecliptic and the star's degree; on it the star lies at its latitude from the ecliptic.

[403] The text passes from «we» to «you» here and back to «we» below, as the codex does (Nallino).

the lower half, and from every side of the plane of the ring of the horizon to the top of the dome there are 90 parts. Then we cut on the outside of the ring of the horizon, on both sides of the line of the east and the west, two even, opposite slots, half its thickness deep, and in the inside of the other remaining ring, on both sides of its two opposite quarters, a notch as deep as the notch of the other ring, and we fit it on the ring of the horizon, having also cut on the outside of the ring of the middle of the sky, on both sides of the line of the dome and of the cardine of the earth opposite the dome, a notch half the thickness of the upper ring deep, and cut in this ring, on its inside, on both sides of the two remaining quarters, a notch as deep as that notch together with the thickness of the small ring in which the poles are. When we have done this, the ring that stands on the ring of the horizon and cuts between the north and the south is the ring of the middle of the sky, with the line of the middle of the sky in the middle of its thickness; and the other ring, which cuts between the east and the west, bounds the part of the ball between the north and the south, with the line of the east and the west in the middle of its thickness.[404]

Then you divide the quarters of the great ring, in which these rings turn, into 90 parts and 18 cells, and we set in each cell its number in the letters of the abjad up to 90, as we did before. We bore in the middle of the thickness of this ring a hole going through, on both sides of the line of the quarter from which we began the division, and above it we cut a slot in the top of the ring, on both sides of the line, as long as a quarter of the ring. We make a square piece of copper, of the thickness of the ring and the width of the slot, and cut in its middle a straight line dividing it into two equal halves; we file it on both sides of this line with the file and thin it towards the lower part of the piece, filing it round, and make its lower end sharp like a nail; its length is such that it goes through the edge of the ring and its sharpened lower end touches the face of the ball. We notch the rest of its square part, in the slot, to the depth of the slot; and what shows of it above the ring is the size of a thumb, or as is fitting, so that this part that shows is an indicator of the ray and of the altitude; we fix it in its place whenever we wish. Then we mount this ring in two clamps like the pin of the astrolabe, with two pointed ends, for which we bore holes in the middle of the thickness of the ring of the middle of the sky and of the ring between the east and the west; the ring runs in the housings of these two pins, as with the horse in the pin of the astrolabe, towards the north and the south. We make the upper of them a loop and a ring, by which the ball is hung as the astrolabe is hung. We contrive to fasten the ends of the two pins so as to fix the ring in its place, and it turns with the turning of the pins towards the east and the west; we contrive this by cutting in the great ring a slot as long as the end of the pin that goes into the hole, so that when the ring is set right in its place we fasten it with a piece of copper that fills it, and it does not move from its place, if God wills.[405]

Ar. p. 214

When we wish to take the altitude in any town we like, we raise the north pole of the equator, marked on the small ring, above the northern horizon by the latitude of the town and fix it in that state; then we fit the indicator of the ray and the altitude in its place, hang the ball by our hands as the astrolabe is hung by its handle, and turn the indicator towards the sun in the quarter of the horizon in which it is; we turn the ring towards the north and the south until the indicator shades itself, which happens only when it points straight at the sun. Then we find the part of the signs in which the sun is, turn that part to the quarter in which the sun is, and keep the ring as it is: the parts of the quarter that rise above the circle of the horizon are the amount of the altitude. When we move the ring towards the part of the sun, we keep moving it and moving the part of the sun until the sharp end of the indicator that touches the ball falls on the part of

[404] The top of the dome is the zenith, 90 parts from the horizon all round, and the line of the dome the upper end of the meridian, opposite the cardine of the earth below; Nallino compares the dome of the earth of chapter 6.


[405] The horse is the wedge through the pin of the astrolabe that holds its parts together (Nallino's commentary). Schiaparelli, in Nallino's commentary, explains the instrument with a drawing: the globe turns on the poles of the equator in the smallest ring, a movable meridian, which turns in its own plane inside a fixed meridian joined to the horizon and the prime vertical; this frame turns about the vertical line inside the great ring, a vertical circle that carries the indicator of the sun's rays.

the sun drawn on the line of the sphere of the signs; and this can happen as we have described only at the place of the sphere where the sun is at that time, according to its altitude above the horizon. When it falls so for us, the sphere stands for us in its configuration at that time: the part of the sphere of the signs that the ring of the horizon cuts on the side of the east is the part rising at that time, and the part that it cuts on the side of the west is the part setting; the part of the sphere of the signs cut by the middle of the thickness of the ring of the middle of the sky is the part in the middle of the sky, and likewise the cardine of the earth opposite it.

When we wish to know the hours that have passed of the day, we look at the arc of the equator that the ring of the horizon cuts from the time when the sun's part rises on the ball until the part rising at that time rises: that is what has turned of the sphere from sunrise to the hour of the measurement, and every 15 degrees of it are one equal hour; divided by the times of the hours of the sun's part, it shows the seasonal hours. Whenever we raise the pole, the turning of the signs and the increases of the day become clear to us, until we raise it 90 parts; and the ascensions of the signs in every town become clear in the usual way, and other things. We should write on the ring of the horizon, in the third of it that remains, towards the north, «the summer risings», and towards the south of the line of the east «the winter risings»; likewise from the line of the west, towards the north, «the summer settings», and towards the south «the winter settings»; so that we have shown all that is needed of the azimuths of the risings and the settings. When we have set the part of the sun, with the indicator in its state on it, facing the sun, the ring of the middle of the sky faces the meridian line.[406]

This is the picture of the brick for observation, so that the account may refer to it.[407]

Ar. p. 215



Al-Battānī said: You take a square brick of copper, of stone or of wood, its side two cubits; the larger it is, the more accurate. It is the brick A B G D. We take the point A as a centre and draw about it, with the amount of A B, A G, the arc B G, and divide it into 90 divisions, the parts of the quarter, by lines that pass through the centre and the divisions marked on the arc, and between the parts into as many minutes as possible. Let the face of the brick be smooth, perfectly level, neither inclined nor shaking, so that the divisions on it are true.


Ar. p. 216

[406] Nallino takes «the third» for an error for «the quarter».

[407] The brick is Ptolemy's plinth (*Almagest* I 12; Nallino). In the figure the quarter of the circle is divided from the side A B, 5 to 90; the letters of these numbers are given in figures.

Then we take two pegs of copper of equal size, turned on the lathe, pointed at the ends, and fix one at the centre of the point A and the other at the centre of the point G. We have first found the meridian line, which is the line H Z, letting the plumb line down from the end of the rod at the centre A onto the end of the peg at the centre G, so that neither the face of the brick nor its setting is inclined; the face with the drawings and the divisions faces the east, and its side on which A B are lies along the direction of the south. We observe the shadow at the times of noon and note the place of the shadow of the peg at the centre A among the divisions of the quarter each day. We take a piece of copper fitted to the curve of the arc B G, the piece Ṭ, and draw in its middle a line, the line at the place Ṭ, so that this piece is put under the place of the shadow and its place among the parts shows clearly, so that its marking is not confused for us; the line Ṭ is on the middle of the width of the peg's shadow, and so we know on which line of the parts of the divisions and of their minutes it falls. From that we know the extreme distances of the sun from our zenith in summer and in winter: let the point Ḥ be the summer limit and the point K the winter limit; so the arc K Ḥ is the arc between the two solstices, and its half is the mark L. Whenever the sun passes the vernal or the autumnal equinoctial point, the shadow of the peg at the place A falls on the point L of the arc B G. By this the distance of the sun from the point of the zenith is always known, every day, and its altitude above the horizon, if God most high wills; success is from God. The brick must also be truly square, its angle a right angle in agreement with the count, if God most high wills.[408]

This is the picture of the long alidade.[409]



Ar. p. 217

Al-Battānī said: We take three rulers of wood, straight, with square faces, and draw along the middle of each of them a line running along the length of its face; we make this figure a picture of the lines that run along the middles of the rulers: they are the ruler Z Ḥ, the ruler Z L and the

[408]For G the codex has B, here and below; «the rod» is, Nallino thinks, the peg; for «the south» the codex has «the qibla», and for «autumnal» «winter» (Nallino). Nallino takes «which is the line H Z» for a wrong addition of the codex, which Plato of Tivoli has too: in the codex's figure H and Z stand near B and D, and the meridian line, along which the brick stands, can only be A B. The noon zenith distances of the two solstices are the latitude less and more the obliquity, so that the arc K Ḥ is twice the obliquity and L stands at the latitude of the place; Ptolemy found the arc between the solstices with this instrument (*Almagest* I 12).

[409]The long alidade is Ptolemy's parallactic instrument (*Almagest* V 12); other Arabs call it «the one with two branches» (Nallino's commentary).

ruler Ṭ M. We put on the ruler Z Ḥ, on its line, the mark Ṭ, making the line Z Ṭ five cubits, and fix the line Ṭ Ḥ, the rest of the ruler, in a stone or a pillar, firmly, so that it neither moves nor changes nor shakes. Then we take the second ruler, which is smaller than the third, and make its line Z L equal to the line Z Ṭ; we put on it two sights of copper of equal size, like the sight of the astrolabe, across its breadth, which passes over the face of the ruler Z Ṭ, fixing them firmly on the face of the ruler, and make in their middles two holes opposite each other; we fix one of the two sights near the point Z and the other near the point L. We bore these two rulers at the mark Z and join them with a pin, fastening it as we fasten the pin of the astrolabe, so that we can move the ruler Z L towards the north and the south as we like, without shaking, play or twisting. Then we take the ruler Ṭ M and make its line Ṭ K equal to each of the lines Z Ṭ and Z L; we divide the line Ṭ K into 30 parts, and between the parts into as many minutes as possible, a true division of equal sizes, and divide the line K M, the rest of the ruler, by the size of those divisions, as finely or as coarsely as we like, up to the halved chord of 45 parts, so that the most that the divisions of the line Ṭ M reach is about 42½ parts; what remains of the ruler we cut off. Then we bore the rulers Z Ṭ and Ṭ M at the point Ṭ with two round holes, as we bored the first ones, and join them with a pin, fastening it as we join the pin of the astrolabe, so that we can move the ruler Ṭ M to the north and the south as we like, without play or shaking.[410]

In the ruler Ṭ M, along the line Ṭ M, we cut a slot in half its breadth, its upper, outer half, as deep as half the thickness of the ruler, over its whole length; likewise we cut in the end of the ruler Z L a notch of half the thickness and the breadth of the ruler Ṭ M, and take off the corners of the square of the ruler Z L on both sides, little by little, so that its turning and its motion along the line Ṭ M are easy and smooth; because of the slots that we have cut, the faces of the two rulers lie in one plane, neither rising above the other nor standing out from it. Then we turn the pillar A B G D, in which we have fixed the ruler Z Ṭ Ḥ, until the line B G of its square stands on the meridian line, and the plumb line, let down from the point Z, falls on the point Ṭ, so that the ruler stands at right angles; the face of the ruler stands upright on the meridian line, levelled on it, facing the east; so do the two sights fixed on the second ruler, and the divisions on the ruler Ṭ M face the east too, drawn along the half of the ruler in whose other half the slot was cut.[411]

When the sun passes the meridian line, we move the ruler with the two sights towards the north and the south until the upper sight shades [the lower sight] entirely and the ray of the sun passes from the hole of the upper sight into the hole of the lower sight; at the same time we draw out the ruler Ṭ M and move it towards the north and the south until we bring the line Ṭ M, along the breadth of the slotted ruler, against the point L of the ruler Z L, by means of the two slots that we cut; and we note at which number of the divisions on the ruler Ṭ M the point L falls, enter it in the table of the halved chords and find its arc: doubling the arc that comes out, the result is the distance of the sun from the point of the zenith, if the count of the ruler begins from the point Ṭ. Likewise, if we divided the line Ṭ K into 60 parts, by the amount of the half diameter, and divided the line K M up to 85 parts, then took the number on which the point L falls, took its half, found its arc and doubled the arc that came out, the meaning would be the same.[412]

Ar. p. 218

Observation with this ruler is more accurate, because it is made on a circle whose diameter is ten cubits. Likewise, if we made the length of the ruler Z L twice as much, or less, so that we pass on to the mark ʿ, and fixed the sight that is near Z at the place ʿ, the distance between the two sights would be greater, and so more accurate. The altitude can be taken with these rulers at any time,

[410] Nallino expects «the smallest of the three», as Plato of Tivoli has; for «these two rulers» the codex has «these two sights». The cubit of the astronomers is the common cubit of 24 digits, about half a metre (Nallino).

[411] For Z the codex has D (Nallino).

[412] The bracketed words are supplied by Nallino. Ṭ L is the chord of the sun's zenith distance in a circle whose radius Z Ṭ is 30 parts, so that its length is the halved chord, in the table of radius 60, of half the zenith distance; at 90° from the zenith it is 42.4 parts, and with Z Ṭ of 60 parts 84.9, whose half is entered in the table. Ptolemy marks the scale on the upright ruler and refers the third ruler to it; al-Battānī marks it on the third ruler itself, as Regiomontanus was later to do (Nallino's commentary).

if the ruler Z Ḥ is mounted firmly in the pillar A B G D so that we can turn it to the regions of the horizon wherever the sun is. Likewise, if the altitude of the moon or of another star needs to be taken with them, it is known how great the altitude is when the arc of the distance from the zenith is subtracted from 90: it is what remains from the zenith to 90 when the arc of the distance is subtracted from it, if God wills.

A. On finding the beginnings of the years of the Arabs and of their months, which are worked with in dating by the tables[413]

Ar. p. 219

Al-Battānī said: If you wish to know the sign of the year you are in, of the years of the Arabs, which are the years of the Hijra, look at how far the years of the Hijra exceed 210 years: cast them off by 210s and work with what remains below that, for in every 210 years they return to their first order, always. When you know the years that result, with the year you are in, even if only one day of it has begun, look for the same number in the rows of the numbers of the tables of the collected years and take the sign of the years opposite it; if you do not find the same number in the collected years, look for the nearest to it below it, and where you find it take the sign of the years under it. Then see what years remain up to the year you are in, enter them in the row of the single years and take the sign of the years under them, and add it to the first sign, which you kept from the collected years: if the sum is more than 7, cast off 7 from it, and what remains is the sign of the year you want. If you entered the number in the collected years and nothing remains to enter in the single years, always add one to the number you find under the collected years; or, if you like, take in the collected years what is 30 less than the number you have, take what stands opposite 30 in the single years and add the one to the other: you will hit the right result whichever way you work, and it is the sign of the year you are in. Cast off the number from Sunday: the day at which your count ends is the day on which the year begins, the first day of al-Muḥarram of that year. If you want another of the months, take the sign of the month you want from the table of the months and add it to the sign of the year; if the sum is more than 7, cast off 7 from it, and cast off what remains, or what you have below 7, from Sunday: the count stops at its end at the name of the day on which the month you want begins. By this reckoning you work in finding the motions of the stars in the tables set out for the era of the Arabs; pay no attention to any other, if it gives more or less.[414]

If you wish to know the leap years of the Arabs, cast off the years of the Hijra by 30s and compare what remains with these letters: any year that agrees with one of these letters is a leap year, and one that does not agree with them is not a leap year. The letters are 2, 5, 7, 10, 13, 16, 18, 21, 24, 26 and 29. I shall show this in the single years of the Arabs in the table for finding the signs, if God most high wills; success is from God and from no other.[415]

[413] Eight short chapters without numbers follow chapter 57 in the Escorial codex; Nallino marks them A to H. Plato of Tivoli has none of them. Nallino holds them genuine except D and probably F: A, B and C complete chapter 32, at whose end al-Battānī promised them, E is announced at the end of chapter 53 and H in chapter 42, and they explain al-Battānī's own tables, beside which some of them probably once stood (Nallino's commentary).

[414] The sign of a year is the day of the week of its first day, counted from Sunday as 1. A common Arab year of 354 days moves it on by 4, a leap year of 355 days by 5, thirty years by 5, and so 210 years by 35, a whole number of weeks; for the astronomers the epoch of the Hijra was a Thursday, so that the sign of the first year is 5. The signs of the collected years are one less, since they count from a year before the Hijra, and so one is added when they are used alone (Nallino's commentary). The words «at which your count ends» are partly eaten by worms in the codex (Nallino).

[415] The letters are numerals. Nallino restores 7, 18 and 26, the leap years of almost all the Arab astronomers and of civil use, for the codex's 8, 19 and 27, which contradict the signs of the years in al-Battānī's own tables and may come from Ḥabash (Nallino's commentary). Eleven leap years in thirty make 10631 days.

B. On knowing the beginnings of the Roman months by the era of Dhū l-Qarnayn, cast off by 28, with the addition of a year

Al-Battānī said: If you wish to know the beginning of any month you want of the Roman months, and on which day of the week it falls, take the years of Dhū l-Qarnayn with the year you are in, counted from the entry of Aylūl, even if only one day of it has begun, and add to that one year, as a base already past, always. Cast off the sum by 28s, and look for what remains below 28, or 28 itself, in the tables of the single Roman years, and take what stands opposite it in the row of the month you want of the Roman months: the result is the sign of that month. Cast it off from Sunday: it brings you, against the number, to the name of the day on which that month begins. The first of Aylūl is the first day of the year. The leap year is known from the mark that you find against the month of Subāṭ: you find «leap year» on it in every four years, if God wills.[416]

C. On knowing the eras of the Arabs and of the Rūm, each from the other, from these tables

Ar. p. 220
Ar. p. 221

Al-Battānī said: If you wish to know the era of the Rūm from the era of the Hijra, look in the years of the Hijra written in the first rows for the same number as the years you have, and where you find it, take what is under it of the number of the Roman years in the table in which the years of Dhū l-Qarnayn are written, and the number of the days passed of the month written under the years: the years, the complete months and the days passed of the Roman month that result are what has passed of the years of Dhū l-Qarnayn, with the year you are in, and the day passed of the Roman month, up to the first day of al-Muḥarram of the year of the Hijra that you are in. Then find on which day of the week it falls, by taking what stands under that year of the Hijra that you are in, of the number of the days of the week, in the column headed «the first of al-Muḥarram»: it is the day passed of the Roman month that you found in the table, and it agrees with the era set down at the beginning of the book. If you want another of the Roman months, from the month of the Arabs that you are in, find on which day of the week the beginning of the Arab month you want falls: take the number of the days by which you knew the first of al-Muḥarram and add to it the sign of the month you want of the Arab months, set down in the table of the signs of the Arab months; if it is more than 7, cast off 7 from it, and what does not make up 7 cast off from Sunday: the day at which you stop is the first day of the Arab month that you wanted. Find how many days of that month have passed, from its beginning; then count from the first of al-Muḥarram to the day you want of that month, reckoning for each month of the year that has passed its number of days, one month 30 days and one month 29 days; from all these days, together with the days passed of the month you want, subtract one day, and to what remains add the number of the days passed of the Roman month that you found in the table. Cast off the sum from the beginning of that Roman month, for each month its number of days: the day to which you come, of the month in which that number ends, is the day you are in of the Roman month, of the year of Dhū l-Qarnayn that you found in the table, until you come to Aylūl; if one day of Aylūl has begun, add another year to the years of Dhū l-Qarnayn; and if the year is a leap year and the count reaches Subāṭ, take 29 days for it in that year. The leap year is known from the mark set down in the table made for the signs of the Roman months.[417]

In the same way you know the day you are in of the Arab month, of the year of the Hijra you are in, from the era of the Rūm: look in this table, in the row of the years of Dhū l-Qarnayn, and take what stands against the year of Dhū l-Qarnayn that you are in, of the days passed of the Roman month: on that day passed of the month falls the first of al-Muḥarram of the year of the

[416] «Already past» is Nallino's conjecture for the codex's meaningless «ماصلا», here and in C. A common Roman year of 365 days moves the day of the week on by 1 and a leap year by 2, so that after 28 years, 10227 days or 1461 weeks, the signs of the months return in the same order. Nallino holds the rule false: adding a year to the given years would be right if every Roman year were common, but after a leap year the sign grows by two, so that the rule fails whenever the given year is a leap year; one should enter the table with the given year and add one to its sign (Nallino's commentary).

[417] The era set down at the beginning of the book is that of chapter 32.

Hijra that you are in. Keep it. Then take the days that remain of that Roman month and add to them what you have of the months and days after that month up to the day you want, taking for each month its number of days; add one day to the sum, as a base already past, always; then cast off the sum from al-Muḥarram, for each month its number of days: the day to which you come is the day of the Arab month that you are in, of the year that you found of the years of the Hijra, until you come to al-Muḥarram; when you come to it and one day of it has begun, add another year to the years of the Hijra that you have. On this era your work is done, if God wills.

D. On knowing the direct motion of the stars, their stations and their retrogradations, and their crossing of their epicycles

Ar. p. 222

Al-Battānī said: Of the stars, Saturn moves directly from the top of its epicycle for 118 days and a half; then it stays for 2 days, a half, a quarter and an eighth; then it goes back in its course for 135 days, a third and a quarter; then it stays a second time, like its first stay, and then moves directly like its first direct motion until it returns to the top of its epicycle. All its days, in which it crosses the epicycle, are 378 days and 2 hours, approximately. When its corrected anomaly is from 0 to 112;45, it is direct; when it passes that up to the end of 115;29, it is stationary; when it passes that up to the end of 244;31, it is retrograde; when it passes that up to the end of 247;15, it is stationary; and up to the end of the circle, direct, if God wills. Jupiter moves directly from the top of its epicycle for 137 days and a half; then it stays for 3 days, a quarter and a fifth; then it goes back in its course for 117 days; then it stays a second time like its first stay and then moves directly like its first direct motion. All its days, in which it crosses its epicycle, are 399 days less 2 hours, approximately. When its corrected anomaly is from 0 to 124;5, it is direct; up to the end of 127;11, stationary; up to the end of 232;49, retrograde; up to the end of 235;55, stationary; and up to the end of the circle, direct.

Mars moves directly from the top of its epicycle for 341 days and a fifth; then it stays for 25 days and a third; then it goes back in its course for 46 days and two thirds of a day; then it stays a second time like its first stay, and then moves directly like its first direct motion again. All its days, in which it crosses its epicycle, are 780 less a tenth of a day, approximately. When its corrected anomaly is from 0 to 157;33, it is direct; up to the end of 169;14, stationary; up to the end of 190;46, retrograde; up to the end of 202;27, stationary; and up to the end of the circle, direct. Venus moves from the top of its epicycle directly for 269 days and half a sixth of a day; then it stays for 4 days; then it goes back in its course for 37 days and four fifths of a day; then it stays a second time like its first stay, and then moves directly like its first direct motion. All its days, in which it crosses its epicycle, are 583 days, two thirds of a day and a quarter of a day, approximately. When its corrected anomaly is from 0 to 165;53, it is direct in its course; up to the end of 168;21, stationary; up to the end of 191;39, retrograde in its course; up to the end of 194;7, stationary; and up to the end of the circle, direct.

The Scribe moves directly from the top of its epicycle for 46 days, a third and a quarter of a day; then it stays about 20 hours; then it goes back in its course for 21 days and a tenth of a day; then it stays a second time like its first stay, and then moves directly like its first direct motion. All its days, in which it crosses its epicycle, are 115 days, a half, a quarter and an eighth of a day, approximately. When its corrected anomaly is from 0 to 144;40, it is direct; up to the end of 147;13, stationary; up to the end of 212;47, retrograde; up to the end of 215;20, stationary; and up to the end of the circle, direct in its course; and God knows best.[418]

[418] The Scribe is Mercury, a name used by the western Arabs, as in the passage interpolated into chapter 50. Schiaparelli, in Nallino's commentary, takes the chapter for an interpolation that misreads the tables of the stations of the planets, Ptolemy's in *Almagest* XII and al-Battānī's own: the anomaly of the first station changes with the place of the epicycle on the eccentric, from 112;45 for Saturn when the epicycle is at the apogee to 115;29 at the perigee, and the chapter makes that range a stay, which for Mars becomes 25⅓ days. Ptolemy's and al-Battānī's own rule for the stations is that of chapter 46. Nallino corrects the numbers only to the interpolator's meaning, taking the anomalies from al-Battānī's tables of the stations and dividing them by the mean daily motion in anomaly; the codex has 112;44

E. On knowing the times of the revolutions of the years, their ascendants, and the excesses of the mean motions of the stars in them over their mean motions at the root, by the tables set out for this at the end of the book

Ar. p. 223

Al-Battānī said: Whenever you wish to know the times of the revolutions of the years, their ascendants and their excesses in the mean motions over the mean motions of the stars at the root, take the complete years that have passed for the nativity, from the year of the root to the year of the revolution, having found the mean and the true position of the sun at the root. Then look for the same number as the complete years you have in the table of the collected Roman years, and where you find it, or the nearest to it below it, take what you find under it of the times of the ascensions and keep it; then enter with the remainder of the years that you have in the table of the single years, take what stands opposite it of those times too, and add it to the first. What results, after casting off the circle if it is more than a circle, keep, and divide it by 15: the result is equal hours. Add them to the hours of computation at the root: if the hours come to more than 24, cast off 24 from them and add a day to the days passed of the month of the root, and if they are less than 24, work with them. Look at the days passed of the month and the hours that you then have: if the year is a leap year and Subāṭ has run out, subtract one day from the days passed of the month, and if it is not a leap year, subtract nothing. Then compute the sun at that date of that year: the mean of the sun comes out for you like the first mean, of the root; compute its true position by the equation, according to the place of its apogee in the year of the revolution. If the true position of the sun comes out like the first, [that is the time]; if not, find its excess over the first, or its shortfall from it, and divide that excess or that shortfall by the varying motion of the sun in an hour: the hour that results, add to the hours of computation if the second position of the sun is less than the first, and subtract from them if it is the greater. The hours of computation that you have after that, convert into the hours of the unequal days, by looking at what stands opposite the sun's part of the equation of the days set down in the right sphere: find its amount in equal hours and add it to the hours of computation: the result is the hours of the time of the revolution. Multiply them by fifteen, add to them the ascensions of the sun's part in the right sphere, and find from this the ascendant and the middle of the sky as usual. Then enter with the number of the complete years in the tables of the motion of the moon and of the stars in the years of revolution, and take what stands opposite it.[419]

Ar. p. 224

What results is the excess of the mean motions of the stars and of the node. For the moon, its anomaly and the node, you add what results for each of them to its mean at the root; for the three upper ones, add it to their means at the root and subtract it from the anomaly of each of them at the root; for Venus and Mercury, you add what results for each of them to its anomaly at the root, while their means are like the mean of the sun. When you have done that, compute them as usual. Know that the times of the revolutions fall short by one day in every hundred and six years: whenever 106 years have passed, always subtract one day from the days passed of the month of the root, if God wills. This does not come about in nativities; it comes about only in the lives of cities, dynasties and religions, when their revolutions are needed, if God most high wills.[420]

---

and 247;14 for Saturn, 116 days, 369 days and 235;0 for Jupiter, 24⅓ days, 700 in words (with 780 in numerals above), 167;32 and 202;26 for Mars, 3 days and 483 days for Venus, and 215;0 for Mercury. Each count of days is the arc of anomaly divided by 360 parts in the days of the whole period, to within about a tenth of a day, and the periods are the synodic periods of the planets.

[419] The bracketed words are added for the sense. The equation of the days is added here to turn the mean hours into true ones, as the rule of chapter 34 requires, which subtracts it to turn true hours into mean; chapter 53 has «subtract». To be added to the ascensions the hours must be multiplied by fifteen; the text, and Nallino's translation, have «divide». These tables are on ff. 239v–240r of the codex (chapter 53).

[420] For 106 the codex has «a hundred and sixty», twice (Nallino's notes to the Arabic; the Latin notes give 166). The year of the revolution, 365 days 5 hours 46 minutes 24 seconds, is 13 minutes 36 seconds shorter than the Roman year, which in 106 years make a day (chapter 53).

F. On directing the degrees from wherever you like to wherever you like, approximately

Know that this directing is what Ptolemy explained in the directing of the haylāj, where the ascensions in it are called al-jūy-rāst, saying the jūy-rāst of Capricorn, which are the ascensions of the right sphere, and the jūy-rāst of the town, which are the ascensions of the town; it is the correction of their distance from the cardines, if God most high wills.[421]

Ar. p. 225

Al-Battānī said: If you wish to direct a degree to some place, look at the degree from which you wish to direct, which is the first degree, and at the second degree, to which you wish to direct, which is the other. Then subtract the ascensions in the right sphere of the first degree from the ascensions in the right sphere of the second degree: the remainder is the first residue; keep it. Then subtract the ascensions of the first degree in the clime from the ascensions of the second degree in that clime, as you did first with them in the ascensions of the right sphere: the remainder is the second residue; keep it as well. Then take the difference between the first residue and the second residue, and see to which of them the excess belongs, the first residue or the second; keep it and mark it with its name: it is the difference of the two residues. Then take the distance of the first degree from the degree of the cardine before it. If the cardine before it is the tenth, express this distance as a fraction of half the arc of the day and take that fraction of the difference of the two residues: the result is the share. Then look: if the excess belongs to the first residue, subtract the share from the first residue, and if the excess belongs to the second residue, add the share to it; what the first residue comes to after the addition to it or the subtraction from it is the number of the degrees of the direction, if God wills. If the cardine before it is the fourth, take the distance between the degree from which you direct and the degree of the fourth, express it as a fraction of half the arc of the night, and take that fraction of the difference of the two residues: the result is the share. Then look: if the excess belongs to the first residue, subtract the share from the first residue, and if the excess belongs to the second residue, add the share to it, I mean to the first residue: what the first residue comes to after the addition to it or the subtraction from it is the number of the degrees of the direction.[422]

If the cardine before it is the ascendant, take the space between the rising part and the degree from which you direct, take its ratio to half the arc of the night, and take in that ratio of the difference of the two residues: the result is the share; keep it. Then look: if the second residue is more than the first residue, subtract the share from the second residue, and if it is the less, add the share to the second residue: what the second residue comes to after the addition or the subtraction is the number of the degrees of the direction. If the cardine before it is the seventh, take the distance between the degree from which you direct and the degree of the seventh cardine, take its ratio to half the arc of the day, and take in that ratio of the difference of the two residues: the result is the share; keep it. Then look: if the second residue is more than the first residue, subtract the share from the second residue, and if the second residue is less than the first residue, add the share to it: what the second residue comes to after the addition to it or the subtraction from it is the number of the degrees of the direction, which are the corrected parts, mixed from the ascensions of the town and of the right sphere.

[421] Nallino takes this chapter for spurious: it repeats chapter 55 more briefly, leaves out the planets with latitude and uses words and turns foreign to al-Battānī, found otherwise among the arithmeticians of western Africa and Spain. *Jūy-rāst* is Persian, «right ascension»: rāst is «right»; the codex always has «جواراسب». The one printed Arabic text in which Nallino found the word gives it for the ascensions of the right sphere, and Kūshyār's tables «by the jūy-rāst» are right ascensions counted from the beginning of Capricorn, so that its use here for the ascensions of a town seems false. «In the directing» follows Nallino's later reading «تسيير» for «تسيُّر» (Nallino's commentary).

[422] «Express as a fraction of» and «that fraction» render «name from» and «that name», technical words of the arithmeticians of western Africa and Spain for dividing a smaller number by a greater: the rule takes the difference of the residues times the distance divided by half the arc of the day, that is, times the seasonal hours of the distance divided by 6, as in chapter 55 (Nallino's commentary). The tenth and the fourth are the cardines of the middle of the sky and of the earth, the beginnings of the tenth and the fourth house.

G. On knowing the ascensions of the signs in the right sphere at intervals of ten parts, and the halved chords of these ascensions, to make the ascensions of the signs easy to know for any town you like

Ar. p. 226

We have set down the ascensions of every ten parts, summed with what comes before them, up to 90, in the right sphere, and drawn the halved chords of the ascensions under them. When we wish to know the ascensions, we work in the manner given at the beginning of the book: we take the chord of half the excess of the longest day in that town and multiply it by the chords of these tens set down under them, and find the arc of the result: the arc that results is the share of the collected tens in the difference of the day. We proceed so until we tabulate it for all the signs at intervals of ten parts; this suffices for what is needed of the knowledge of the single ascensions for the town and for places whose latitude agrees with it. This work is done with the little table set down under the square of the ranks of the declination.[423]

H. Chapter

If you wish to know the varying motion of the moon in an hour, for the computation of the conjunction and the opposition, take the exact difference between the sun and the moon and find what stands opposite it in the tables of the increase and the decrease of the motion of the moon in an hour — this is for each degree in particular. The minutes that there are, subtract from the varying motion of the moon in an hour when the corrected anomaly of the moon, for which you found its motion in an hour, is from 0 to 95 and from 265 to 360, and add them to that motion when that anomaly is from 95 to 265: the result after the addition or the subtraction is the exact motion. Subtract from it the motion of the sun in an hour: the remainder is the gain of the moon.[424]

[423] The chords here are halved chords, sines. The rule is exact: since the tangent of the declination of a degree is the tangent of the obliquity times the sine of its right ascension, the sine of the difference of the day at that degree is the sine of half the excess of the longest day times the sine of the right ascension. The difference of the day, subtracted from the right ascension, gives the ascension in the town (chapters 13 and 19).

[424] This is the short chapter announced in chapter 42, where Schiaparelli's explanation is given: the correction is about one second an hour for each degree of the elongation from the sun, taken off in the upper part of the epicycle and added in the lower (Nallino's commentary).

The tables of Part III

In the Escorial codex the tables follow the chapters. Of them Nallino printed in Part III only those that contain words, the chronological and the geographical tables and the names of the fixed stars, as the codex has them; the tables of numbers only are in the Latin version (Part II). The English below translates the words of these tables and gives their numbers in figures, read from the abjad letters with their Western values. Where Nallino corrects a number of the codex in Part II, the English gives Nallino's value, marked *, and the codex's reading in the notes; where Part II differs from Part III without a note of Nallino's, the English keeps the value of Part III, marked †, and gives that of Part II in the notes. In the star catalogue the longitudes are counted in degrees from the beginning of the Ram through the whole circle of the signs, and N or S gives the side of the ecliptic on which the latitude lies; a magnitude «greater» or «lesser» is a little brighter or fainter than its number. The column «Star» gives Nallino's identification in the modern designation. Where Nallino's translation corrects the wording of the Arabic, the English follows it and the notes give the Arabic. The tables of the stars for the year 1211 give, for the latitude of al-Raqqa, each star's distance from the equator, its altitude when it culminates, half the time it stays above the earth in degrees of the equator, and the degrees of the ecliptic that culminate, rise and set with it; their stars are numbered as in Nallino's translation. The codex draws the two figures of pp. 243 and 244 as circles, and the English sets out what they contain as tables: in the figure of the seven climes each line of the circle becomes a row, with the climes as columns; in the astrological figure each sign becomes a column, with its circles as rows. The numbers of the figures are those of the codex; where Nallino's Latin figure differs, the English marks the codex's number † and gives Nallino's in the notes. Names of persons and places are transliterated as they are written, with Nallino's reading of them beside them. The pages of Part III are given in the margin.

Notice

Ar. p. 227

Carlo Nallino, who has taken care of establishing and correcting the text of this book, says: All the chapters are complete, and in the Escorial copy the tables follow them. We, however, have taken from them only what concerns chronology, geography and the names of the fixed stars, and have printed it without correcting the errors and the corruptions in the abjad letters — and, by God, how many these mistakes are! Whoever wishes to correct them should consult our Latin translation of this book, in which we have also printed the rest of the tables, which contain numbers only. The reader must also be told that the abjad letters have the same values in the tables as in the Escorial copy, that is, by the usage of the people of the West: so Ṣ stands for 60, Ḍ for 90, S for 300 and Ẓ for 800.

End, end.

End.

The chronological tables

In the name of God, the Merciful, the Compassionate. God bless our lord Muḥammad, God's noble Messenger, and the Prophet's family and companions, and give them peace.

Ar. p. 228

Table of the dates of the Greek kings from Nabonassar the First, and from Nabonassar by the dating of the Almagest

Names of the kings	Nallino's reading	Years they reigned	Sum of the years	Notes
Bukhtanaṣṣar the First	Nabonassar	14	14	
Nadiyūs	Nadius	2	16	
Khinzīrūs	Chinzer	5	21	
al-Mīwā	Ilulaeus	5	26	
Mardūqanfadh	Mardokempad	12	38	
Arqīnwā	Arkeanus	5	43	
Afsīlīṭūs the First	the first interregnum (abasileutos)	2	45	
Bīl	Bilibus	3	48	
Afrāndiyūs	Aparanadius	6	54	
Arsafl	Rhegebelus	1	55	
Afsīlṭūs the Second	the second interregnum	4	59	
Masīsīmūrdaqs	Mesesimordakus	8	67	
Ardūsūn	Asaridinus	13	80	
Sasdūkhanas	Saosduchinus	20	100	
Qanīladnūs	Kiniladanus	22	122	
Bukhtanaṣṣar the Second	Nabopolassar	21	143	
Bukhtanaṣṣar the Third, the conqueror of Jerusalem	Nabokolassar (Nebuchadnezzar)	43	186	
Barʿilyā Līqwā	Illoarudamus	2	188	
Balshaṣṣar	Nerigasolassar	4	192	
Daryūs the Mede	Nabonadius	17	209	
Kūrash	Cyrus	9	218	
Qambūsūs	Cambyses	8	226	
Daryūs	Darius	36	202†	total: Part II 262
Akhshaqyūs	Xerxes	21	283	
Arṭaḥshast the First	Artaxerxes the Elder	43	326	
Daryūs	Darius	19	345	
Arṭaḥshast the Second	Artaxerxes the Younger	46	391	
Akhūs	Ochus	21	412	
Ghayrūn	Arogus	10	422	
Daryūs Arsakh	Darius, son of Arsakh	6	428	
al-Iskandar the Macedonian	Alexander the Macedonian	6	434	
Ar. p. 229				
After this the kings of Athūr				
Fīyāfūs, the father of Dhū l-Qarnayn	Philip	7	7	
al-Iskandar the Builder	Alexander the Founder	12	19	
Baṭlamiyūs the Hare	Ptolemy Lagus	20	39	
Baṭlamiyūs Fīlādhalfūs	Ptolemy Philadelphus	38	77	
Baṭlamiyūs Ūrghaṭas the First	Ptolemy Euergetes the Elder	25	102	
Baṭlamiyūs Fīlīfaṭūr	Ptolemy Philopator	17	119	
Baṭlamiyūs Afīfanīs	Ptolemy Epiphanes	24	143	
Baṭlamiyūs Fīlīmīṭūr	Ptolemy Philometor	35	178	
Baṭlamiyūs Ūrghaṭas the Second	Ptolemy Euergetes the Younger	29	207	
Baṭlamiyūs Sūṭar	Ptolemy Soter	36	243	
Baṭlamiyūs Diyūnsiyūs	Ptolemy Dionysus	29	272	
Baṭlamiyūs Qalūbaṭrā	Ptolemy Cleopatra	22	294	
After this the kings of the Rūm				
Aghusṭus	Augustus	43	337	
Ṭībariyūs	Tiberius	22	359	

Names of the kings	Nallino's reading	Years they reigned	Sum of the years	Notes
Ghāʾiyūs	Gaius	4	363	
Qalūdhiyūs	Claudius	14	377	
Nārūn	Nero	14	391	
Wisfasiyānūs	Vespasian	10	401	
Ṭīṭūs	Titus	3	404	
Dūmiṭiyānūs	Domitian	15	419	
Nārūs	Nerva	1	420	
Ṭarāyānūs	Trajan	19	439	
Adhriyānas	Hadrian	21	460	
Anṭūnīnas	Antoninus	23	483	
Qūmadhūs	Commodus	32	515	
Sāwīras	Severus	25	540	
Anṭūnīnūs alone	Antoninus alone	4	544	
Alaksandarus Barghamā	Alexander, the son of Mamaea	13	557	
Maksimiyānūs	Maximinus	3	560	
Ghūrdiyānūs	Gordian	6	566	
Fīlifus	Philip	6	572	
Dhāqiyānas	Decius	1	573	
Ghālus	Gallus	3	576	
Wālirīnas	Valerian	15	591	
Ar. p. 230				
Qalūdhiyūs	Claudius	1	592	
Ūrīlīnūs	Aurelian	6	598	
Farbūs	Probus	7	605	
Qārūs and Qārīnūs	Carus and Carinus	2	607	
Daqlaṭiyānūs	Diocletian	21	628	
After this the kings of Christendom				
Qūsṭanṭīnas	Constantine	32	660	
Qūsṭūs	Constantine	24	684	
Yūliyānas the Pagan	Julian the Pagan	2	686	
Yūbiyānas	Jovian	1	687	
Thādhūsiyūs	Theodosius [sic]	14	701	
Walīs	Valens [sic]	17	718	
Arqādhiyūs	Arcadius	13	731	
Thāwudhusiyūs	Theodosius the Younger	42	773	
Mārqiyānas	Marcian	6	779	
Laʾūn	Leo	18	797	
Zīnūn	Zeno	17	804†	total: Part II 814
Anasṭāsiyūs	Anastasius	27	841	
Yūsṭīnas the First	Justin the Elder	9	850	
Yūsṭīnīnūs	Justinian	37	887	
Yūsṭīnas the Second	Justin the Younger	14	901	
Ṭībariyūs	Tiberius	4	905	
Māwurqiyūs	Maurice	20	925	
Fūqās	Phocas	8	933	
Hiraqlas, the lord of the Arabs	Heraclius	31	964	
Qusṭanṭinas	Constantine	1	965	
Qūsṭanṭiyūs	Constantine	27	992	
Lasṭabūs	Leontius	16	1008	
Ṭībariyūs the Second	Tiberius the Younger	10	1018	
Yūsṭīnas	Justinian	3	1021	
Fīqūs	Philippicus	7	1028	
Yūsṭīnīnas	Constantine	6	1034	

Names of the kings	Nallino's reading	Years they reigned	Sum of the years	Notes
Fīlifqūs	Philippicus	3	1037	
Anasṭās	Anastasius	2	1039	
Thāwudhusiyūs	Theodosius	1	1040	

Table of what lies between the eras

Ar. p. 231

	Years	Notes
From the reign of Nabonassar the First to the death of Alexander the Macedonian, in Egyptian years	434*	years: codex 424
Then Philip, the father of Dhū l-Qarnayn, reigned after that; from Philip's reign to the reign of Augustus the Roman	294	
From the reign of Augustus the Roman to the reign of Diocletian, who is of the kings of Christendom	313	
From the reign of Diocletian to the reign of Julian the Pagan	77	
Then Julian reigned, and the kingdom returned to Christendom, and then Jovian reigned	2	
From the reign of Diocletian to the reign of Heraclius, the lord of the Arabs	326†	years: Part II 336
Then the Arabs reigned: from the Hijra of the Prophet to the dynasty of Muʿāwiya the Umayyad	39	
And until rule passed to the ʿAbbāsids, and remained with the ʿAbbāsids	127	

Table of the dates of the caliphs from the Hijra, the Hijra of the Prophet, on whom be God's blessing and peace

Names of the rightly guided caliphs from the Hijra, on the reckoning that the first day of al-Muḥarram is a Friday, while the day used in the dating is the Thursday; this is the Muḥarram of the first year of the Hijra	What each of them reigned			Sum of the years			Notes
	Years	Months	Days	Years	Months	Days	
The Hijra of the Prophet Muḥammad, on whom be God's blessing and peace, from Mecca to Medina was in the first year of it	0	2	8	0	2	8	
The Prophet stayed as an emigrant in Medina until taken	9	11	22	10	2	0	
Abū Bakr ibn Abī Quḥāfa, of the Banū Taym	2	3	8	12	4†	8	total months: Part II 5
ʿUmar ibn al-Khaṭṭāb, of the Banū ʿAdī	10	6	17	22	11	25	
There was the council after ʿUmar ibn al-Khaṭṭāb	0	0	3	22	11	28	
ʿUthmān ibn ʿAffān, of the Banū Umayya	11	11	19	34	11	17	
ʿAlī ibn Abī Ṭālib, and the civil war	4	9	0	39	8	16†	total days: Part II 17

Ar. p. 232

Names of the rightly guided caliphs from the Hijra, on the reckoning that the first day of al-Muḥarram is a Friday, while the day used in the dating is the Thursday; this is the Muḥarram of the first year of the Hijra	What each of them reigned			Sum of the years			Notes
	Years	Months	Days	Years	Months	Days	
And until the oath of allegiance to Muʿāwiya ibn Abī Sufyān	0	6	3	40	2	20	
Muʿāwiya ibn Abī Sufyān ibn Ḥarb ibn Umayya	19	3	25	59	6	15	
Yazīd ibn Muʿāwiya ibn Abī Sufyān	3	8	0	63	2	15	
Muʿāwiya ibn Yazīd ibn Muʿāwiya	0	3	22	63	6	7	
ʿAbd Allāh ibn al-Zubayr and Marwān ibn al-Ḥakam	0	4	0	63	10	7	
ʿAbd Allāh ibn al-Zubayr, of the Banū Asad	8	5	0	72	3	7	
ʿAbd al-Malik ibn Marwān, until Ibn al-Zubayr was killed	1	2	3	73	5	10	
ʿAbd al-Malik ibn Marwān ibn al-Ḥakam	12	4	6†	85	9	15	days: Part II 5
al-Walīd ibn ʿAbd al-Malik ibn Marwān	9	7	29	95	5	14	
Sulaymān ibn ʿAbd al-Malik	2	7	29	98	1	13	
ʿUmar ibn ʿAbd al-ʿAzīz ibn Marwān	2	5	13	100	6	26	
Yazīd ibn ʿAbd al-Malik ibn Marwān	4	0	1	104	6	24†	total days: Part II 27
Hishām ibn ʿAbd al-Malik ibn Marwān	19	8	9	124	3	6	
al-Walīd ibn Yazīd ibn ʿAbd al-Malik ibn Marwān	1	2	21	125	5	27	
There was the civil war after the killing of al-Walīd	0	2	25	125	8	22	
Yazīd ibn al-Walīd ibn ʿAbd al-Malik	0	2	9	125	11	1	
Ibrāhīm ibn al-Walīd ibn ʿAbd al-Malik	0	2	11	126	1	12	
Marwān ibn Muḥammad ibn Marwān, until killed	5	2	0	131	3	12	
Then rule returned to the Banū Hāshim							
Abū l-ʿAbbās ʿAbd Allāh ibn Muḥammad al-Saffāḥ	4	8	2	135	11	14	
And until the oath of allegiance came to Abū Jaʿfar	0	0	14	135	11	28	
Ar. p. 233							
Abū Jaʿfar al-Manṣūr ʿAbd Allāh ibn Muḥammad	21	11	8	157	11	6	
And until the news reached al-Mahdī	0	0	12	157	11	18	
al-Mahdī Muḥammad ibn Abī Jaʿfar al-Manṣūr	10	1	5	168	0	13†	total days: Part II 23

Names of the rightly guided caliphs from the Hijra, on the reckoning that the first day of al-Muḥarram is a Friday, while the day used in the dating is the Thursday; this is the Muḥarram of the first year of the Hijra	What each of them reigned			Sum of the years			Notes
	Years	Months	Days	Years	Months	Days	
And until the news reached Mūsā ibn al-Mahdī	0	0	8	168	1	1	
al-Ṣādiq Mūsā ibn Muḥammad al-Mahdī	1	1	15	169	2	16	
al-Rashīd Hārūn ibn Muḥammad al-Mahdī	23	2	16†	162†	5	3	days: Part II 17; total years: Part II 192
And until the news reached Muḥammad ibn Hārūn	0	0	12	162†	5	15	total years: Part II 192
al-Amīn Muḥammad ibn al-Rashīd, until deposed and imprisoned	3	0	25	165†	6	10	total years: Part II 195
Al-Amīn remained imprisoned	0	0	2	165†	6	12	total years: Part II 195
Then al-Amīn was brought out, received the oath of allegiance, fought and was besieged until killed	1	6	13	167†	0	25	total years: Part II 197
al-Maʾmūn ʿAbd Allāh ibn Hārūn al-Rashīd	20	5	22	217	6	17	
al-Muʿtaṣim Muḥammad ibn Hārūn al-Rashīd	8	5†	2	226	2	19	months: Part II 8
al-Wāthiq bi-llāh Hārūn ibn Muḥammad al-Muʿtaṣim	5	9	5	231	11	24	
al-Mutawakkil ʿalā llāh Jaʿfar ibn Muḥammad al-Muʿtaṣim	14	9	9	246	9	3	
al-Muntaṣir bi-llāh Muḥammad ibn al-Mutawakkil	0	6	0	247	3	3	
al-Mustaʿīn bi-llāh, until going down to the City of Peace	2	9	3	250	0	6	
And until the oath of allegiance was given to al-Muʿtazz bi-llāh at Surra man raʾā	0	0	8	250	0	14	
And until the Friday sermon was given for al-Muʿtazz bi-llāh in the City of Peace	0	11	20	251	0	4	
And until al-Muʿtazz bi-llāh was deposed	3	6	23	254	6	27	
And until the oath of allegiance was given to al-Muhtadī bi-llāh	0	0	2	254	6	29	
al-Muhtadī bi-llāh ibn al-Wāthiq bi-llāh	0	11	18	255	6	17	
Ar. p. 234							
al-Muʿtamid ʿalā llāh Aḥmad ibn al-Mutawakkil	28	0	3	278	6	20	
al-Muʿtaḍid bi-llāh Aḥmad ibn al-Muwaffaq	9	9	2	288	3	22	
al-Muktafī bi-llāh ʿAlī ibn al-Muʿtaḍid	7†	6	4	294	9	26	years: Part II 6

Names of the rightly guided caliphs from the Hijra, on the reckoning that the first day of al-Muḥarram is a Friday, while the day used in the dating is the Thursday; this is the Muḥarram of the first year of the Hijra	What each of them reigned			Sum of the years			Notes
	Years	Months	Days	Years	Months	Days	
al-Muqtadir bi-llāh Jaʿfar ibn Aḥmad	24	11	15	319	3	18	
al-Qāhir bi-llāh Muḥammad ibn Aḥmad	1	6	6	320	10	24	
al-Rāḍī bi-llāh Muḥammad ibn Jaʿfar	6	10	9	327	9	3	
al-Muttaqī li-llāh Ibrāhīm ibn Jaʿfar	3	11	4	331	8	7	
al-Mustakfī bi-llāh ʿAbd Allāh ibn ʿAlī	1	6	15	333	2	22	
al-Muṭīʿ li-llāh al-Faḍl ibn Jaʿfar							

The geographical tables

Table of the middles of the countries, which are ninety-four countries, as in the Book of the Figure of the Earth

Ar. p. 234

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
1	The island Yūbarniyā, Barhaṭāniqā	Ivernia (Ireland), a British island	13	0	58*	30	latitude °: codex 18
2	The island Alwiyūn, Barhaṭāniqī	Albion (Great Britain), a British island	20	0	54	0	
3	Sfāniyā Bahṭiqā, over al-Andalus	Hispania Baetica	9	9†	38	20	longitude ′: Part II 20
4	Sfāniyā Lusiṭāniyā, al-Andalus	Hispania Lusitania	8	0	39	9†	latitude ′: Part II 20
5	Sfāniyā Ṭārāqūnīsiyā, al-Andalus	Hispania Tarraconensis	11	0	42	0	
6	Ghāliyā Aqwīṭāniyā	Gallia Aquitania	18*	0	45	30	longitude °: codex 13
7	Ghāliyā Lūghdunīsiyā	Gallia Lugdunensis	20	40	48	2	
8	Ghāliyā Balghīqī	Gallia Belgica	26	50	47	1	
9	Ghāliyā Narbūnīsiyā	Gallia Narbonensis	22	0	44	30	
10	Great Jahrmāniyā	Germania Magna	34	2	52	0	
11	Rāṭiyā Wīndalīqiyā	Raetia and Vindelicia	32	30	46	30	
12	Nūrīqun	Noricum	36*	0	46	0	longitude °: codex 34
Ar. p. 235							
13	Upper Bānūniyā	Pannonia Superior	39	30	47	13	
14	Lower Bānūniyā	Pannonia Inferior	41	2	45	4	
15	Īlūris Libūrniyā	Illyris, Liburnia	45	0	44	0	
16	Dalmāṭiyā	Dalmatia	46	0	42	0	
17	The island Īṭāliya	Italy	36	40	41	40	
18	The island Qurnus	Corsica	32	0	40	2	
19	The island Sardāniya	Sardinia	31	50	38	6	

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
20	The island Siqilliya	Sicily	39	8	36	19	
21	Sarmāṭiyā Ūrūfī	European Sarmatia	57*	0	49	0	longitude °: codex 37
22	Ṭāwrīqī Karsūnīsus Bārālās	the Tauric Chersonese; Bārālās perhaps paralia, «the coast» (Nallino)	62	0	48*	0	latitude °: codex 38
23	Yāzūghūs Mahṭānīsā	the Iazyges Metanastae	43	0	48	0	
24	Dāqiyā	Dacia	50	0	44†	0	latitude °: Part II 46
25	Upper Mūhsiyā	Moesia Superior	46	0	43	0	
26	Lower Mūhsiyā	Moesia Inferior	53	0	45	0	
27	Māqī, the country of Constantinople	Thrace; Nallino reads «what is in», or a corruption of Tharāqī, Thrace	52	0	43	0	
28	Karsūnīsus Aṭrabzmālīqa	the Chersonese; the second word is corrupt (Nallino)	54	0	41	0	
29	Māqādhūniyā	Macedonia	50	0	41	0	
30	Īfīrūs	Epirus	46	0	39	0	
31	Akhāyā	Achaea	50	0	38	30	
32	The island Hawbuwā	Euboea	52	0	37	0	
33	The island Fūlūfūnīsūs	the Peloponnese	51	0	36	0	
34	The island Ṭarqī	Crete; Nallino reads Qirīṭī	54	0	35	0	
35	Mūriṭāniyā Ṭanjiṭāniyā, the country of Ṭanja	Mauretania Tingitana, the country of Tangier	8	0	32	0	
36	Mūriṭāniyā Qahsarnsiyā	Mauretania Caesariensis	18*	0	32	0	longitude °: codex 13
37	The country of Ifrīqiya	Africa	36	0	31	0	
38	Nūmīdhiya	Numidia	30	30	30	0	
39	Fanṭāfūlūs	Pentapolis (Cyrenaica)	50	0	29	0	
40	Marmārīqī	Marmarica	52	0	28	0	
41	Lībuwāy	Libya	57	0	29	0	
42	Lower Aghifṭus, the country of Miṣr	Lower Egypt	61*	0	32	0	longitude °: codex 41
43	Thībāyis	the Thebaid	62*	0	24	0	longitude °: codex 46
44	Lībuwāy within Ifrīqiya	Inner Libya	38*	0	22	0	longitude °: codex 18
45	Kūsh, which is above Miṣr	Ethiopia below Egypt	62	0	16*	0	latitude °: codex 36
46	Inner Kūsh, which is beyond the equator	Inner Ethiopia	50	0	2†		latitude °: Part II 12
47	Bīthūniyā	Bithynia	58	0	42	0	
48	Āsiyā	Asia	58	0	38	0	
49	Frūjiyā	Phrygia	63*	0	38	0	longitude °: codex 68
Ar. p. 236							
50	Lūqiyā	Lycia	60	0	37	0	
51	Ghālāṭiyā Qāriyā	Galatia; Caria	62	0	41	0	
52	Faflāghūniyā	Paphlagonia	63	0	44	0	
53	Fānfūliyā	Pamphylia	64	0	37	0	
54	Qāfādhūqiyā	Cappadocia	67	0	41	0	

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
55	The country of Lesser Armīniya	Armenia Minor	71	0	39	0	
56	Qilīqiya, the country of Ṭarasūs	Cilicia, the country of Tarsus	68	0	37	0	
57	Sarmāṭiyā, which is in Āsiyā	Asian Sarmatia	74	0	47*	0	latitude °: codex 37
58	Qūlkhīs	Colchis	73	0	45	0	
59	Ībīriyā	Iberia	75	0	45	0	
60	Albāniyā, the country of al-Bāb	Albania, the country of the Gate (Derbent)	78	0	45	0	
61	Greater Armīniya	Armenia Major	77	0	41	0	
62	The island Qubrus	Cyprus	66	0	35	0	
63	Deep Sūriyā, the country of Ḥalab and al-ʿAmq	Coele Syria, the country of Aleppo and al-ʿAmq	71	0	36	0	
64	Sūriyā Fūnīqī, the country of al-Ghawr and Dimashq	Syria Phoenice, the country of the Jordan valley and Damascus	71	0	33	0	
65	The lands of the Jews, Filasṭīn	Palestine, Judaea	67	0	31	0	
66	The inhabited lands of the Bedouin Arabs	Arabia Petraea (Nallino)	68	0	29	0	
67	Babilūniyā, the country of Bābil	Babylonia	78	0	32	0	
68	Athūr, the country of al-Mawṣil	Assyria, the country of Mosul	80	0	37	0	
69	Ādharbayjān	Media (Nallino)	83	0	39	0	
70	al-Sūs, the country of al-Ahwāz	Susiana	83	0	34	0	
71	The country of Fāris	Persis	90	0	32	0	
72	The country of Iṣfahān	Isfahan	96	0	37	0	
73	Desert Kirmān	Carmania Deserta	96	0	32	0	
74	Inhabited Kirmān	Carmania	99	0	25	0	
75	The inhabited land of the Bedouin Arabs, al-Yaman and al-Ḥijāz	Arabia Felix	83	0	22	0	
76	The country of Jurjān	Hyrcania	95	0	40	0	
77	The country of Marw al-Rūdh	Margiana	104	0	41	0	
78	The country of Balkh	Bactria	116	0	41	0	
79	The country of al-Ṣughd	Sogdiana	114	0	45	0	
80	The country of al-Shāsh	al-Shāsh (Tashkent)	108†	0	43	0	longitude °: Part II 133
81	The country of the Turks within Mount Himāwus	Scythia within Imaus	120	0	56	0	
82	The country of the Turks beyond the mountain	Scythia beyond Imaus	150	0	48	0	
83	The country of Ṭabaristān	Tabaristan	165	0	45	0	
84	The country of Harāt	Herat	104	0	37	0	
85	The country of Farghāna	Farghana	116	0	35	0	
86	The country of Sijistān	Sistan	108	0	29	0	
87	The country of al-Rukhkhaj	Arachosia	115	0	29	0	
88	The country of al-Sind	Sind	110	0	23	0	
89	al-Hind, which is within the river Ghanjis	India within the Ganges	132	0	27	0	

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
Ar. p. 237							
90	al-Hind, which is beyond the river	India beyond the Ganges	150*	0	22	0	longitude °: codex 180
91	The island Sarandīb	Sri Lanka	124	0	3	0	
92	The middle of the lands of Ḥimyar	Himyar	82*	0	12	30	longitude °: codex 102
93	The country of al-Ṣīn	China	177	0	22	0	
94	[Jīrā] Mītrūfūlis	a metropolis; Jīrā is supplied by Nallino	36	30	18	0	
95	Najīrā		25	5	17	15	
96	Sūnāthliyā		80	0	16	30	
97	Sāffārā		78	0	14*	30	latitude °: codex 17
98	The island Sarāfis		94*	0	17	30	longitude °: codex 64
99	Thīnā	Thinae	180	0	13	0	
100	Great Diyusfūlīs	Diospolis Magna (Thebes)	62	0	23	50	
101	Great Uwasīs	Oasis Magna	59	50	28*	30	latitude °: codex 23
102	Bajalzā		43	0	23	30	
103	Mecca, God guard it; its longitude, by the tested value, is 77;53	Mecca	71	0	21	40	
104	Yathrib the Holy	Medina	75	0	25	0	
105	Great Khalqīdhun	Chalcedon	34	10	32	40	
106	Great Lahfṭis	Leptis Magna	41	0	31	0	
107	Great Qāṭābāthmūs	Catabathmus Magnus	54	30	31	10	
108	Great Uwasīs	Oasis Magna	59	5	27	10	
109	al-Iskandariyya, which is in Miṣr	Alexandria in Egypt	60	30	30	18	
110	Qaysāriyā Afūmiyūs	Caesarea	67	25	33	20	
111	Filasṭīn	Palestine	66	15	32	30	
112	Suqrāṭāwus		67	30	33	40	
113	ʿAsqalān	Ashkelon	65	0	31	50	
114	Sabasṭiya	Sebaste	66*	30	31	50	longitude °: codex 67
115	al-Ramla	Ramla	65	50	31	35	
116	Lādhiqiyā Frūjis	Laodicea in Phrygia	59	45	38	40	
117	The island Rūdhis	Rhodes	58	40	36	0	
118	Salmāwus		66	45	35	30	
119	Ṭarasūs	Tarsus	67	40	36	55	
120	Adhana	Adana	68	15	36	50	
121	al-Maṣṣīṣa	Mopsuestia	68*	50	36	45	longitude °: codex 67
122	al-Lādhiqiyya	Latakia	68	30	35	5	
123	Aṭrābulus	Tripoli in Syria	67	30	34	20	
124	ʿIrqa	ʿArqa	68	30	34	0	
125	Ṣūr	Tyre	67	0	33	20	
126	Ṣaydāʾ	Sidon	67	20	33	30	
127	ʿAkkā	Acre	66	50	33	0	
128	Ḥimṣ	Homs	69	5	34	0	
129	al-Rastan	al-Rastan	69	30	34	10	
130	Ḥamāh	Hama	69	30	34*	20	latitude °: codex 35

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
131	Salamiyya	Salamiyya	69	50	34*	50*	latitude °: codex 36; latitude ′: codex 5
132	Fāmiya	Apamea	70	0	34	45	
Ar. p. 238							
133	Dimashq	Damascus	69	0	33	0	
134	Baʿlabakk	Baalbek	68	20	33	15	
135	Tadmur	Palmyra	72	0	34	0	
136	Ḥalab	Aleppo	71	0	34	50	
137	Qinnasrīn	Qinnasrin	70	40	35	35	
138	Maʿarrat al-Nuʿmān	Maʿarrat al-Nuʿman	69	55	34	0	
139	Qūrus	Cyrrhus	70	10*	36	20	longitude ′: codex 50
140	Dulūk	Doliche	70	40	37	0	
141	Raʿbān	Raʿban	71	0	37	15	
142	Anṭākiya	Antioch	69	0	35	30	
143	Malaṭya	Malatya	71	0	39	0	
144	Shimshāṭ	Shimshat	73	20	38	40	
145	Mayyāfāriqīn	Mayyafariqin (Silvan)	76	0	38	0	
146	Āmid	Amid (Diyarbakır)	75	15	38	0	
147	Arzan	Arzan	76	40	38	0	
148	Sumaysāṭ	Samosata	72	0	34†	50	latitude °: Part II 37
149	Bālis	Balis	71	40	35	50	
150	The city of al-Raqqa, tested	Raqqa	73	15	36	0	
151	Qirqīsiyāʾ	Circesium	74	40	35*	20	latitude °: codex 34
152	Ḥarrān	Harran	73	0	36	40	
153	al-Ruhāʾ	Edessa (Urfa)	72	50	37	0	
154	Manbij	Manbij	71	15	36	15	
155	Tall Mawzan	Tall Mawzan	73	30	37	0	
156	Raʾs al-ʿAyn	Raʾs al-ʿAyn	74	0	36	50	
157	Kafar Tūthā	Kafar Tutha	74	35	37	5	
158	Naṣībīn	Nisibis	75	30	37	0	
159	Dārā	Dara	75	15	37	10	
160	Māridīn	Mardin	75	0	37	15	
161	Balad	Balad	77	40	36	35	
162	al-Mawṣil	Mosul	78	10	36	30	
163	Sinjār	Sinjar	77	30	36	0	
164	Khilāṭ	Akhlat	78	0	39	20	
165	Dabīl	Dvin	79	40	42	0	
166	Taflīs	Tbilisi	82	0	43	0	
167	Bardhaʿa	Barda	84	0	42	0	
168	Baghdād, the City of Peace, tested	Baghdad	80	0	33	9	
169	Surra man raʾā	Samarra	79	10	34	0	
170	al-Kūfa	Kufa	79	30	31	30	
171	Bābil the famous	Babylon	79	0	35	0	
172	al-Rayy	Rayy	86*	0	36	30	longitude °: codex 66
173	Nīnawā	Nineveh	78	0	36	6†	latitude ′: Part II 40
174	al-Baṣra	Basra	84*	0	31	0	longitude °: codex 110
175	Sīrāf	Siraf	89	30	29	29	

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
176	Wāsiṭ	Wasit	81	30	32*	30	latitude °: codex 30
Ar. p. 239							
177	Dimyāṭ	Damietta	63	30	31	25	
178	al-Fusṭāṭ	Fustat	63	0	30*	0	latitude °: codex 31
179	ʿAyn Zarba	Anazarbus	68	30	37*	0	latitude °: codex 30
180	al-Jisr, the Bridge of Anṭākiya	the bridge of Antioch	69	4	35*	40	latitude °: codex 30
181	Great Rūmiya	Rome	36	40	41	40	
182	al-Qusṭanṭīniyya	Constantinople	56*	40	43	10	longitude °: codex 36
183	ʿAmmūriya	Amorium	38	20	39*	44†	latitude °: codex 49; latitude ′: Part II 45
184	Ṣanʿāʾ	Sanaa	73	0	14*	30	latitude °: codex 34
185	ʿAdan	Aden	74	0	13*	38	latitude °: codex 33
186	Tubbat	Tibet	130*	0	38	0	longitude °: codex 86
187	Jurzān	Georgia	81	0	44	0	
188	Suwān of al-Ḥabasha		65	0	22	30	
189	al-Daybul	Daybul	100	0	25	20	
190	Qazwīn	Qazvin	84*	0	37	0	longitude °: codex 24
191	The city of Harāt	Herat	95*	0	37	0	longitude °: codex 85
192	al-Yamāma	al-Yamama	76	0	21	30	
193	al-Ṭāʾif	Taif	74	30	21	20	
194	Tinnīs	Tinnis	64	0	31	20	
195	al-Faramā	Pelusium	64	40	31	30	
196	al-Ṭurāraband		106	0	36	0	
197	Qumm	Qom	85*	0	36	0	longitude °: codex 84
198	Ḥulwān	Hulwan	81	0	35*	0	latitude °: codex 38
199	Qisṭifān, al-Madāʾin	Ctesiphon	80	0	35	55	
200	Madīnat al-Abwāb	Derbent	80	0	47	0	
201	al-Ruṣāfa	Rusafa	72*	50	35	40	longitude °: codex 75
202	Jubayl	Byblos	60†	30	33	45	longitude °: Part II 67
203	Jazīl, which is in ruins		80	0	37	55	
204	Ūrim		71	40	37	20	
205	Zughma	Zeugma	71	40	37	9	
206	Shayzar	Shayzar	69	20	34	30	
207	Tall Mannas		70	0	35	0	
208	Ḥuwwārīn		70	0	33	40	
209	al-Māqūl	al-ʿĀqūl (Nallino)	79	0	33	55	
210	Hamadhān	Hamadan	83*	20	36	0	longitude °: codex 60
211	ʿAmawās	Emmaus	66*	10	31	45	longitude °: codex 90

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
212	Rāfiya	Raphia	65	0	31	30	
213	Asdūd	Ashdod	65	15	31	55	
214	Zibaṭra	Zibatra	70	0	38	44	
215	Kusūmī, the city of the king of Kūsh	Axum	65	0	11	0	
216	Dāfā, the city of the Persians		71	0	6	0	
217	Athīnas, the city of the sages	Athens	52	40	37	20	
218	Ṭrāqiya		54*	0	41	40	longitude °: codex 57
219	al-Iskandarūna	Alexandretta (İskenderun)	69	0	36	10	
220	Jindāris	Gindarus	70	0	35†	40	latitude °: Part II 36
Ar. p. 240							
221	Wajh al-Ḥajar		67	35	34†	15†	latitude °: Part II 34; latitude ′: Part II 10
222	Arthūsiya	Arethusa	67	35	34*	20	latitude °: codex 33
223	Sanja		71	0	37*	22	latitude °: codex 36
224	Jabala	Jableh	68	22	34	35	
225	Rūsis	Rhosus	69	20	35	40	
226	Qārā	Qara	69	49	33	30	
227	Bayrūt	Beirut	69	30	33	20	
228	Bayt Jibrīn	Bayt Jibrin	66	0	31	0	
229	Sūrā	Sura	100†	30	36	0	longitude °: Part II 80
230	Arām, the house of the king		69	20	32	0	
231	Sīrās, the country of the Turks		77	0	38	55	
232	Niṣībis, which is in Harāt		111	0	35	20	
233	The country of Ūr, the king of kings, and the country of the Turks		70	0	24	0	
234	The city of al-Qis, of al-Yaman		73	0	32†	15*	latitude °: Part II 12; latitude ′: codex 55
235	Mārā, of al-Yaman		73	0	15*	55	latitude °: codex 55
236	Barhūr, of al-Yaman		79	0	13*	0	latitude °: codex 53
237	Ḥaḍramawt	Hadramawt	81	0	14	30	
238	Madīnat al-Ṭīb		82†	0	5*	30	longitude °: Part II 81; latitude °: codex 4
239	The city of al-Mayd		107	0	9	0	
240	The city of al-Muʿallā		83	55	55†	42	latitude °: Part II 15
241	Ẓafār	Zafar	88	0	55†	0	latitude °: Part II 15
242	Sabaʾ	Saba	74*	0	17*	0	longitude °: codex 64; latitude °: codex 57

No.	Of the names of the countries	The place	Longitude		Latitude		Notes
			°	′	°	′	
243	Jurash	Jurash	75	0	17	0	
244	Mahra	Mahra	74	0	18*	30	latitude °: codex 58
245	Tabāla	Tabala	77	0	39†	0	latitude °: Part II 19
246	al-Baḥrayn	Bahrain	84	20	25	45	
247	ʿUmān	Oman	94	30	19	45	
248	al-Nīrūn		104*	20	28†	30	longitude °: codex 64; latitude °: Part II 23
249	Miṣra, of al-Yaman		66	0	25	25	
250	Akhmīm	Akhmim	66	30	25*	30	latitude °: codex 35
251	Qūṣ	Qus	65	30	20	30	
252	al-Qulzum	Clysma (Suez)	66	30	27	30	
253	al-Jār, the coast of Mecca	al-Jār; «of Mecca» [sic] (Nallino)	69	30	30	0	
254	Hajar	Hajar	83	20	25*	45	latitude °: codex 45
255	Jīruft	Jiroft	68†	0	31	15	longitude °: Part II 98
256	Kābul	Kabul	110	0	28	0	
257	Dunqula, the city of al-Nūba	Dongola, in Nubia	63	0	14	15	
258	al-Rūyān	Ruyan	86	35	37	10	
259	al-Muḥammadiyya		100	0	31	45	
260	Qaṣr al-Milḥ		61†	0	32	0	longitude °: Part II 91
261	al-Sīrajān	Sirjan	93	0	32*	0	latitude °: codex 14
262	Dunbāwand	Damavand	115†	30	36*	35	longitude °: Part II 86; latitude °: codex 57
263	Āmul	Amol	87	20	37	45	
Ar. p. 241							
264	Sāriya	Sari	87	30	38	0	
265	Aṭrābazunda	Trebizond	73	0	43	0	
266	Khuwayy	Khoy	80†	0	41	40	longitude °: Part II 82
267	Usrūshana	Ushrusana	101	10	36	40	
268	ʿAbbādān	Abadan	84	55	31	0	
269	Ṭūs	Tus	62†	0	37*	0	longitude °: Part II 92; latitude °: codex 35
270	Sarakhs	Sarakhs	94*	0	37	0	longitude °: codex 106
271	Hīt	Hit	28†	30	33	35	longitude °: Part II 78
272	Arādhūs	Aradus (Arwad)	68*	0	34	30	longitude °: codex 98
273	Bayt al-Maqdis	Jerusalem	66	30	31	50	

The longitudes of known cities and fortresses, tested, and their latitudes, in al-Andalus and the Maghrib

No.	Of the names of the cities	The place	Longitude °	Longitude ′	Latitude °	Latitude ′	Notes
A01	Aṭrābulus of Barqa	Tripoli in Barca	41	40	32	0	
A02	Qarṭajanna of al-Andalus	Cartagena	33	45	52	0	
A03	Qurṭuba	Córdoba	27	0	38	38	
A04	Ishbīliya	Seville	25	40	37	15	
A05	Ṭulayṭula	Toledo	28	0	40	0	
A06	Gharnāṭa	Granada	27	30	37	30	
A07	Shantarīn	Santarém	23	40	45	15	
A08	Mālaqa	Málaga	26	22	37	0	
A09	al-Mariyya	Almería	28	0	36	30	
A10	Mursiya	Murcia	29	29	37	37	
A11	Balansiya	Valencia	30	30	37	37	
A12	Saraqusṭa	Zaragoza	29	55	41	30	
A13	Ṭanja	Tangier	24	10	35	55	
A14	Fās	Fez	25	0	33	0	
A15	Sabta	Ceuta	25	40	35	20	
A16	Bijāya	Béjaïa	36	0	36	30	
A17	al-Qalʿa		36	17	36	37	
B01	Salāʾ	Salé	10	0	27	0	
B02	Āṣīlāʾ	Asilah	26	15	40†	15	latitude °: Part II 35
B03	Mārida	Mérida	8	0	41	55	

Ar. p. 242

B04	Madīnat Sālim	Medinaceli	9	30	40	15	
B05	Ṭurṭūsha	Tortosa	32	0	37	15	
B06	Saraqusṭa	Zaragoza	8	30	41	30	
B07	Tudmīr	Tudmir	10	15	37	30	
B08	Ghāna	Ghana	10	0	17	0	
B09	Jayyān	Jaén	28	0	38	0	
B10	al-Jazīra al-Khaḍrāʾ	Algeciras	26	0	36	30	
B11	Baṭalyūs	Badajoz	25	20	39	30	
B12	Qalʿat Rabāḥ	Calatrava	9	20	39	30	

The figure of the seven climes

Folio 196 verso of the codex

The circuit of the seven climes, represented by the circles of the horizons, and the degrees of the azimuth of the risings and settings of the signs on the horizon of each clime: that is, the amount of their distance from the rising and setting points of the equinox, in the north and in the south

The azimuth of the south, 90		The first clime		2, 25		3, 30		The fourth clime		5, 41		6, 45		The seventh clime		
The azimuth of the north, 90, its hours		13 h		13 h 30 m		14 h		14 h 30 m		15 h		15 h 30 m		16 h		
Signs	**Line**	°	′	°	′	°	′	°	′	°	′	°	′	°	′	**Notes**
Aries, Libra	rising	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
[Libra, Aries]	setting	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
Scorpio, Pisces	rising, south	12	3	12	39	13	27	14	23	15	26	16	33	17	43	
[Scorpio, Pisces]	setting, south	12	3	12	19†	13	27	14	23	15	26	16	33	17	43	clime 2, minutes: Part II 39
Aquarius, Sagittarius	rising, south	21	11	22	38†	23	45	25	49†	27	26	29	33	31	46	clime 2, minutes: Part II 18; clime 4, minutes: Part II 29
Aquarius, Sagittarius	setting, south	21	11	22	18	23	25†	25	29	27	26	29	33	31	46	clime 3, minutes: Part II 45
Capricorn	rising, south	24	39†	26	0	27	42	29	48	32	8	34	57†	37	28	clime 1, minutes: Part II 41; clime 6, minutes: Part II 43
Capricorn	setting, south	24	39†	26	0	27	52†	29	48	32	38†	36†	37†	37	28	clime 1, minutes: Part II 41; clime 3, minutes: Part II 42; clime 5, minutes: Part II 8; clime 6, degrees: Part II 34; clime 6, minutes: Part II 43
Virgo, Taurus	rising, north	12	3	12	39	403†	27	14	23	15	26	16	33	17	43	clime 3, degrees: Part II 13
[Virgo, Taurus]	setting, north	12	3	12	19†	13	27	14	23	15	26	16	33	17	23†	clime 2, minutes: Part II 39; clime 7, minutes: Part II 43
Gemini, Leo	rising, north	21	11	22	18	23	45	25	49†	27	26	29	33	31	46	clime 4, minutes: Part II 29
Gemini, Leo	setting, north	21	11	22	18	23	25†	25	29	27	26	29	33	31	16†	clime 3, minutes: Part II 45; clime 7, minutes: Part II 46
Cancer	rising, north	24	19†	26	0	27	12†	29	48	32	8	34	17†	37	28	clime 1, minutes: Part II 41; clime 3, minutes: Part II 42; clime 6, minutes: Part II 43
Cancer	setting, north	24	39†	26	0	27	12†	29	18†	32	8	34	57†	37	28	clime 1, minutes: Part II 41; clime 3, minutes: Part II 42; clime 4, minutes: Part II 48; clime 6, minutes: Part II 43

Place in the figure	Name as written	Nallino's reading	Name
upper left corner: The winter risings	اورى نطس		Euronotos
upper right corner: The winter settings	قاطرغربا		Karbas (?)
lower left corner: The summer risings	اريقنفوس		Ornithias (?)
lower right corner: The summer settings	ارقطوس		Argestes (?)
inner circle, 0° from the south (S)	بوطس	نوطس νότος	Notos
inner circle, 22½° from the south (SSE)	بوبوطس	اورونوطس εὐρόνοτος (= φοινικίας)	Euronotos
inner circle, 45° from the south (SE)	هوبعس	فونقيس φοινικίας	Phoinikias
inner circle, 67½° from the south (ESE)	صدوس	اوروس εὖρος	Euros
inner circle, 90° from the south (E)	افلطس	افليوطس ἀπηλιώτης	Apeliotes
inner circle, 112½° from the south (ENE)	سعانس	ثيبانس θηβάνας (= καικίας)	Thebanas
inner circle, 135° from the south (NE)	بوربوب	بورياس βορέας	Boreas
inner circle, 157½° from the south (NNE)	بطس...افر	افرقطيس ἀπαρκτίας (= ὀρνιθίας)	Aparktias
inner circle, 180° from the south (N)	بعدباس	ارنثياس ὀρνιθίας	Ornithias
inner circle, 202½° from the south (NNW)	افريقس	قرقيس κερκίας (= θρασκίας)	Kerkias
inner circle, 225° from the south (NW)	برقسس	ثرسقيس θρασκίας	Thraskias
inner circle, 247½° from the south (WNW)	اناقونس	يافوقس ἰάπυξ	Iapyx
inner circle, 270° from the south (W)	رهفرس	زهفرس ζέφυρος	Zephyros
inner circle, 292½° from the south (WSW)	لبعوس	ليبوس λίψ (from the genitive λιβός)	Lips
inner circle, 315° from the south (SW)	ليبونطس	ليبونطس λιβόνοτος	Libonotos
inner circle, 337½° from the south (SSW)	بونطس	لوقونطس λευκόνοτος (= λιβόνοτος)	Leukonotos

The astrological figure

Folio 197 recto of the codex

This circle contains the lords of the terms of the twelve signs, the lords of their triplicities by day and by night, the lords of the faces, the lords of the houses and the lords of the exaltations, God willing.

	Aries	**Taurus**	**Gemini**	**Cancer**	**Leo**	**Virgo**	**Libra**	**Scorpio**	**Sagittarius**	**Capricorn**	**Aquarius**	**Pisces**
Terms	Jupiter 5†	Venus 8	Mercury 8†	Mars 7†	Mercury 6†	Mercury 7	Saturn 6	Mars 6	Jupiter 8	Venus 6	Saturn 6	Venus 8
	Venus 8	Mercury 7	Jupiter 6†	Jupiter 6†	Venus 7†	Venus 5†	Venus 5	Jupiter 8	Venus 6	Mercury 8†	Mercury 6	Jupiter 6
	Mercury 6†	Jupiter 6†	Venus 7	Venus 7	Jupiter 6	Jupiter 6†	Jupiter 8	Venus 7	Mercury 5	Jupiter 7	Venus 8	Mercury 7†
	Mars 5	Saturn 3†	Mars 3†	Mercury 7	Saturn 7†	Mars 6	Mercury 6†	Mercury 7†	Saturn 6	Mars 3†	Jupiter 5	Mars 5†
	Saturn 5†	Mars 6†	Saturn 4	Saturn 3	Mars 4†	Saturn 5†	Mars 5†	Saturn 6†	Mars 5	Saturn 6†	Mars 5	Saturn 4
Nallino's degrees	*6 8 7 5 4*	*8 7 7 4 4*	*7 7 7 5 4*	*6 7 7 7 3*	*7 6 6 6 5*	*7 6 5 6 6*	*6 5 8 5 6*	*6 8 7 6 3*	*8 6 5 6 5*	*6 6 7 6 5*	*6 6 8 5 5*	*8 6 6 6 4*
Triplicities, outer circle	Sun, Jupiter, Saturn	Venus, Moon, Mars	Saturn, Mercury, Jupiter	Venus, Mars, Moon	Sun, Jupiter, Saturn	Venus, Moon, Mars	Saturn, Mercury, Jupiter	Venus, Mars, Moon	Sun, Jupiter, Saturn	Venus, Moon, Mars	Saturn, Mercury, Jupiter	Venus, Mars, Moon
Triplicities, inner circle	Jupiter, Sun, Saturn	Moon, Venus, Mars	Mercury, Saturn, Jupiter	Mars, Venus, Moon	Jupiter, Sun, Saturn	Moon, Venus, Mars	Mercury, Saturn, Jupiter	Mars, Venus, Moon	Jupiter, Sun, Saturn	Moon, Venus, Mars	Mercury, Saturn, Jupiter	Mars, Venus, Moon
Faces	Mars	Mercury	Jupiter	Venus	Saturn	Sun	Moon	Mars	Mercury	Jupiter	Venus	Saturn
	Sun	Moon	Mars	Mercury	Jupiter	Venus	Saturn	Sun	Moon	Mars	Mercury	Jupiter
	Venus	Saturn	Sun	Moon	Mars	Mercury	Jupiter	Venus	Saturn	Sun	Moon	Mars
Houses	Bahrām (Mars)	Venus	Mercury	Moon	Sun	Mercury	Venus	Mars	Jupiter	Saturn	Saturn	Jupiter
Exaltations	Sun 19	Moon 3	the Head 3	Jupiter 14†	0	Mercury 15	Saturn 21	0	the Tail 3	Mars 28	0	Venus 27

The first circle is for the terms, the one next to it for the triplicities, the one next to these two for the faces, the one next to it after the three for the houses, and the one next to all of them, which is inside it, for the exaltations. It is not from the original copy.

In the codex the houses and the exaltations change places in this sentence; Nallino keeps the codex's errors in the drawing of the circles (Nallino).

In the codex the circles of the houses and of the exaltations are drawn as one, and the circle of the triplicities is split in two (Nallino); its outer half names the lord by day first, its inner half the lord by night.

In 4 signs the codex's terms do not add up to 30 degrees: Aries 29, Gemini 28, Virgo 29, Scorpio 34. Nallino's figure gives Ptolemy's terms, after the Frankfurt version of the Tetrabiblos; the row «Nallino's degrees» lists them, planet by planet.

0 is the codex's zero sign: these signs have no exaltation. Nallino reads 15 for the 14 of Jupiter in Cancer.

Nallino holds that the figure is not al-Battānī's: al-Battānī never mentions it, and it concerns judicial astrology only (Part II pp. 308–313).

The star catalogue

Folios 226 recto to 237 recto of the codex

Ar. p. 245

The beginning of the tables of the names of the fixed stars and of their positions for the year 1191 of Dhū l-Qarnayn

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
Of the names of the fixed stars in the constellations north of the belt of the signs								
Of the Little Bear								The heading is not in the codex (Nallino)
The star on the tip of the tail of the Little Bear	α UMi	71	20	66	0	N	3	
The one on the root of the tail of this Little Bear	ε UMi	87*	10*	74	20	N	4	longitude °: codex 101; longitude ′: codex 20
The southern one of the following side of the quadrilateral	β UMi	118*	20	72	50*	N	2	The Arabic has «second» for «following», as the codex does (Nallino); longitude °: codex 153; latitude ′: codex 10
The northern one of this following side of the quadrilateral	γ UMi	127*	20	74	50	N	2	The Arabic has «second» for «following», as the codex does (Nallino); longitude °: codex 157
And of the Great Bear								The heading is not in the codex (Nallino)
The star on the muzzle of the Great Bear	o UMa	96*	30	39	50*	N	4	longitude °: codex 176; latitude ′: codex 22
The one on the left knee of this Bear	θ UMa	111	50	35	0	N	3	
The northern one on the tip of its left fore foot	ι UMa	106	40	29	20	N	3	
The star south of it	κ UMa	107	30	28	20	N	3	
The star on its back, in the quadrilateral	α UMa	118	50	49	0	N	2	
The one on the soft part of the belly of this Great Bear	β UMa	123*	20	44	30*	N	2	longitude °: codex 133; latitude ′: codex 10
The star at the root of its tail	δ UMa	134	20*	51	0	N	3	longitude ′: codex 0
The one on the root of its left hind thigh	γ UMa	134*	10*	46	30	N	2	longitude °: codex 133; longitude ′: codex 30
The leading one on the tip of its left hind foot	λ UMa	123	50*	29*	20	N	3	longitude ′: codex 30; latitude °: codex 49
The star that follows this	μ UMa	125	20	28	15*	N	3	latitude ′: codex 55
Ar. p. 246								
The northern one of those on the tip of its right hind foot	ν UMa	141	20†	25*	47†	N	3	The Arabic has «southern», as the codex does (Nallino); longitude ′: Part II 0; latitude °: codex 45; latitude ′: Part II 50
The star south of these	ξ UMa	141	30	25*	0	N	3	latitude °: codex 28
The leading one of the three on its tail	ε UMa	143*	20	53	30	N	2	longitude °: codex 173
The middle one of these three	ζ UMa	149	10	55	40	N	2	
The third, on the tip of its tail	η UMa	161	0	54	31†	N	2	latitude ′: Part II 0

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
And of those that are not part of the figure of the Bear								
The one under the tail, on the south	12 CVn	159	0	39*	45	N	3	latitude °: codex 59
The one between the fore foot of the Bear and the head of the Lion	40 Lyn	116	10	17*	15	N	4	latitude °: codex 57
The faint one that follows the three remaining faint ones	10 LMi	117	20	20	0	N	faint	
The faint one that precedes this star		113	20	22*	50	N	faint	latitude °: codex 24
The one of the faint ones ahead of this star		112	20	20	20	N	faint	
The one ahead of it, between it and the Twins	31 Lyn	101	10	22	15	N	faint	
And of the stars of the Dragon								
The star on the tip of the tongue of the Dragon	μ Dra	217	50*	76	30	N	4	longitude ′: codex 30
The star above its head	γ Dra	250*	50*	75	30*	N	3	longitude °: codex 251; longitude ′: codex 10; latitude ′: codex 10
The star above the eye of the Dragon	β Dra	234	20	75*	40	N	3	latitude °: codex 74
The one of the triangle on the west	ζ Dra	169	30	84*	50	N	3	latitude °: codex 85
The northern one of the two towards the west	η Dra	171	10	78	0	N	3	
The one that follows the leading, distant one of the two	α Dra	142	20	65	30	N	3	
The one that follows this star	κ Dra	104†	20	61	15*	N	3	longitude °: Part II 120; latitude ′: codex 45
The star on the tip of the tail of the Dragon	λ Dra	104†	20*	56	15	N	3	longitude °: Part II 114; longitude ′: codex 40
Ar. p. 247								
And of the stars of the Inflamed, which is Qīfāwus								
The adjoining star on its right shoulder	α Cep	307†	50	69	0	N	3	longitude °: Part II 357
The adjoining one on its right elbow	η Cep	350	30	72	0*	N	4*	latitude ′: codex 15; magnitude: codex 4 greater
The star on its left forearm	ι Cep	18*	40*	62	30	N	4 greater*	longitude °: codex 68; longitude ′: codex 13; magnitude: codex 4
The southern one of the three on its cap	ε Cep	500†	30*	60	15	N	5*	The Arabic has «middle», as the codex does; the numbers are those of the southern one (Nallino); longitude °: Part II 357; longitude ′: codex 13; magnitude: codex 4
And of the stars of the Ghoul, the Guardian of the North, which is the Herdsman								
The one on its left shoulder	γ Boo	180	50	49	0	N	3	
The star on its head	β Boo	187	50	53	50	N	4 greater	
The star on its right shoulder	δ Boo	196	50	48	40	N	4 greater	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The star under its northern shoulder		198	50	46	30	N	4 greater	
The one on its right thigh, in the belt and the band	ε Boo	191	10	40	15	N	3	
The leading one of the two in its belt	ρ Boo	186	10	42	10*	N	4 greater	latitude ′: codex 30
The star on its right hock	ζ Boo	196*	30	28	0	N	3	longitude °: codex 166
The northern one of the three on its left shank	η Boo	182*	20†	28	0	N	3	longitude °: codex 172; longitude ′: Part II 30
The middle star of these three	τ Boo	171†	40	26	30	N	4	longitude °: Part II 181
The southern one of these three	υ Boo	172†	30*	25	0	N	4*	longitude °: Part II 182; longitude ′: codex 10; magnitude: codex 3
The Lance-bearing Simāk, which is between the thighs of the Ghoul and not in its figure	α Boo	188	10	31	30	N	1	
Ar. p. 248								
And of the stars of al-Fakka								
The bright one of the stars of al-Fakka	α CrB	205	50	44	30	N	2 greater	
The leading one of the stars of al-Fakka	β CrB	202	50	46	30	N	4 greater	
And of the stars of the Kneeler								
The one on the head of the Kneeler	α Her	238	50	37	30	N	3	
The one on its right shoulder, by the armpit	β Her	224	50	43	0	N	3	
The one on its right arm	γ Her	222	50	40	10	N	3	
The one on its left shoulder	δ Her	237	50	48	0	N	3	
The one on its left arm	λ Her	243	10	49	30	N	4 greater	
The one on its left elbow	μ Her	248	50	52	0	N	4 greater	
The southern one of the three on its left forearm	ξ Her	252	40	53	0	N	3	
The star on the right side	ζ Her	224*	50	50	40	N	3 greater	longitude °: codex 227
The one on the root of its left thigh	c Her	232*	22†	58	30	N	3	longitude °: codex 235; longitude ′: Part II 20
The one of the three in its left thigh that follows this	ρ Her	237	30	61	15	N	4 greater	
The one on the root of its right thigh	η Her	221*	50*	64	0	N	4 greater	longitude °: codex 223; longitude ′: codex 10
The one on its right knee	τ Her	206	50	65	30	N	4 greater	
The Falling Eagle								
The bright one on the cap of the holder of the lyre, which is the Eagle	α Lyr	268	30	62	0	N	1	
The northern one of the two near it	ε Lyr	271	30	62	40	N	4 greater	
Ar. p. 249								
The southern star of the two	ζ Lyr	271	30	61	0	N	4 greater	
The southern one of the two at the front of the leading pan of the balance	ν¹ Lyr	272	0	55	0	N	4 lesser	
The southern one of the two at the front of the trailing pan of the balance	λ Lyr	272	10	54	45	N	4 lesser	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The first northern one of the two in the trailing pan of the balance	β Lyr	272	10	56	10*	N	3	latitude ′: codex 40
The second northern one of the two in the trailing pan of the balance	γ Lyr	276	20	55	20	N	3	
And of the stars of the Hen								
The one on the beak of the Hen	β Cyg	284*	50*	49	20	N	3	longitude °: codex 287; longitude ′: codex 20
The one in the middle of the neck of the Hen	η Cyg	297	30	54	30	N	4*	magnitude: codex 3
The one in the breast of the Hen	γ Cyg	309	40	57	20	N	3	
The bright star on the tail of the Hen	α Cyg	320	20	60	0	N	2	
The star on the elbow of its right wing	δ Cyg	300	30	64	40	N	3	
The middle one of the three in the right wing	ι² Cyg	302	20	71*	30*	N	4 greater	The Arabic has «left», an error of the codex (Nallino); latitude °: codex 74; latitude ′: codex 10
The star north of this, which is on the tip of the wing	κ Cyg	297	50	74	0	N	4 greater	
The one on the elbow of the left wing	ε Cyg	312	0	49	30	N	3	The Arabic has «tip» for «elbow», as the codex does (Nallino)
The one on its left foot	ν Cyg	321	10	55	10	N	4 greater	
The one on its left knee	ξ Cyg	325*	40*	57	0	N	4 greater	longitude °: codex 326; longitude ′: codex 20
Ar. p. 250								
And of the stars of the Lady of the Chair								
The star on the head of the Lady of the Chair	ζ Cas	19	0	45	20	N	3	
The star in the breast	α Cas	22*	0	46	45	N	3	longitude °: codex 52
The northern one of these, on the girdle	η Cas	24*	10*	47	50	N	4 greater	longitude °: codex 23; longitude ′: codex 50
The star on the knee	δ Cas	31	50	45	30	N	3	
The star in the middle of the chair	β Cas	19	0	51	40	N	3*	magnitude: codex 4 lesser
The one above the foot of the chair	κ Cas	26	10	52	40	N	4 lesser*	magnitude: codex nebulous
And of the stars of Farsāwus, the Horseman holding the head of the Ghoul								
The one on the tip of the right hand of the Horseman, who holds the head of the Ghoul	χ Per	37	50	40	30	N	nebulous*	magnitude: codex 4 lesser
The bright one in the right side	α Per	46	0	30	0	N	2*	magnitude: codex 3
The one on the right shoulder	γ Per	43	50	34	30	N	3*	magnitude: codex 2
The trailing one of the three in the right side	δ Per	48	50	27	20	N	4 greater	
The one on the left thigh	ν Per	43†	0	21	50	N	4†	longitude °: Part II 48; magnitude: Part II 4
The bright one of those in the head of the Ghoul	β Per	40	50	23	0	N	2	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The star on the left hock	ο Per	45	20*	12	0	N	3 lesser	longitude ′: codex 0
The one that follows this, on the left foot	ζ Per	47	30	11	0	N	3	
Ar. p. 251								
And of the stars of the Holder of the Reins, the southern Goatherd								
The star on the head of the Holder of the Reins	δ Aur	73	40	30	0	N	4*	magnitude: codex 3
The star on the left shoulder, which is al-ʿAnz, the She-goat	α Aur	66	10	22	30	N	1	The Arabic has al-ʿAyyūq, Nallino's emendation of the codex's al-ʿayr; in Part II Nallino reads al-ʿanz, as the codex has it in the tables of 1211
The one on the right shoulder	β Aur	74	0	20	0	N	2	
The star on the left hock	ι Aur	61	0	10	10	N	3 lesser	
The one on the right hock	γ Aur	260†	50*	5	0	N	3 greater	longitude °: Part II 66; longitude ′: codex 10
And of the stars of the Serpent-charmer who holds the Serpent								
The star on the head of the Serpent-charmer, who holds the Serpent	α Oph	246	0	36	0	N	3 greater	
The leading one of the two in the right shoulder	β Oph	249	10	27	15	N	4	
The first of the two on the tip of the left hand	δ Oph	226	10	17	0	N	3	
The star that follows this, on the tip of the hand	ε Oph	227	10	16	30	N	3	
The star on the right knee	η Oph	242	20*	7	30	N	3	longitude ′: codex 40
The star on the right shank	40 Oph	244	50	2	15	N	3 greater	
The second of the four on the foot		245	30	1	30*	N	4 greater	latitude ′: codex 35
The northern one in the line of the three northern ones	ζ Oph	233*	20	11	50	N	3 greater	longitude °: codex 253
And of the stars of the Serpent that the Serpent-charmer holds								
The star in the temple of the Serpent that the Serpent-charmer holds	γ Ser	255†	30	36	0	N	3	longitude °: Part II 215
The adjoining one in the nostrils of the Serpent	ρ Ser	252†	50	40	0	N	4	longitude °: Part II 212
Ar. p. 252								
The one where the neck of the Serpent comes out	β Ser	253†	10	34	15*	N	3	longitude °: Part II 213; latitude ′: codex 10
The one after the leading vertebra in the neck of the Serpent	δ Ser	252†	50	29*	15	N	3	longitude °: Part II 212; latitude °: codex 59
The middle one of the three after it	α Ser	255†	30	25	20	N	3	longitude °: Part II 215
The southern star of them	ε Ser	257†	30	24	0	N	3 greater	longitude °: Part II 217
The southern star behind the thigh of the Serpent-charmer	ν Ser	258†	50*	10*	30	N	4 greater	longitude °: Part II 244; longitude ′: codex 10; latitude °: codex 17
The one next to the first of the three on the tail of the Serpent	η Ser	259	50	21	15	N	4 greater	
The one on the tip of the tail of the Serpent	θ Ser	269	30	27	0	N	4	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
Of the stars of Ūyisṭus, which is the Arrowhead								«The Arrowhead» is Nallino's conjecture for the codex's «al-nawl»
The single star on its shaft	γ Sge	291	20	39	20	N	4	
The star at the end of the arrow	β Sge	284	30	38	40	N	5*	magnitude: codex 4
And of the stars of the Flying Eagle								
The leading one of the two in its left shoulder	γ Aql	284*	20	31	30	N	3	longitude °: codex 294
The one that follows the one in the middle of its head, which is on its neck	β Aql	286*	0*	27	10	N	3	longitude °: codex 284; longitude ′: codex 20
The Flying Eagle, which is the bright one between its shoulders	α Aql	285	0	29	10	N	2 greater*	magnitude: codex 3 greater
The northern star near the Flying Eagle	o Aql	285*	50*	30	0	N	3 lesser	longitude °: codex 286; longitude ′: codex 10
The one under the Eagle and far from it, at the edge of the Milky Way	ζ Aql	273	20	36	20	N	3	
Ar. p. 253								
And of the stars of the Dolphin, which is the Cross								
The leading one of the three on the tail of the Dolphin, which is the Cross	ε Del	298	50	29	10	N	3 lesser	
The southern, leading one of the first side	β Del	299	40	32	0	N	3 lesser	
The adjoining southern one in the line of the support of the beak	δ Del	302	30*	32*	0	N	3 lesser	longitude ′: codex 10; latitude °: codex 33
The northern one of the trailing side	γ Del	304	40	33	10	N	3 lesser	
The northern one of the first side	α Del	301	20	33	50	N	3 lesser	
And of the stars of Burṭūmus, which is the Horse								
The first, leading one of the two in the head of Burṭūmus, which is the Horse	α Equ	307	30	20	30	N	faint	
The second, which is the trailing one of them	β Equ	309	10	20*	40	N	faint	latitude °: codex 25
The leading one of the two in its mouth	γ Equ	307	30	25	30	N	faint	
The trailing star of them	δ Equ	308	50*	25	0*	N	faint	longitude ′: codex 0; latitude ′: codex 30
The middle one of those in the head of Andrūmīdhus, who is the Woman without a husband	α And	358	30	26	0	N	2 lesser	
The star on the back of the Horse, at the top of its shoulder	γ Peg	353	20	12	30	N	2 lesser	
The Shoulder of the Horse, which is on its right shoulder, where the foot of the Horse comes out	β Peg	333†	20	31	0	N	2 lesser	longitude °: Part II 343

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The one between its shoulders, in the shoulder of the wing of the Horse	α Peg	337	50	19	40	N	2 lesser	
The northern one of the two in its right knee	η Peg	340	10	35	0	N	3	
The leading one of the two in its neck	ζ Peg	330	0	18	0	N	3	
Ar. p. 254								
The northern one of the two in its head	θ Peg	320	20	16*	50	N	3	latitude °: codex 56
The star on its throat	ε Peg	316*	30*	22	30	N	3 greater	longitude °: codex 346; longitude ′: codex 33
The one on its right hock	π^2 Peg	334	50	41*	10	N	4 greater	latitude °: codex 21
The star on its left knee	ι Peg	328	50*	34	15	N	4 greater	longitude ′: codex 30
The star on its left hock	κ Peg	323	30	36	50	N	4 greater	
And of the stars of Andrūmīdhus, who is the Woman who has not seen a husband								
The one between the shoulders of Andrūmīdhus	δ And	6	30	24	30	N	3	
The southern one of the three above the girdle	β And	15	0	26	20	N	3	
The leading one outside the three in the right hand	ο And	352*	50	44	0	N	3	The Arabic has «in the head», an error for «in the right hand» (Nallino); longitude °: codex 335
The star above the left foot	γ And	28	0	28	0	N	3	
And of the stars of Ṭarīghānus, which is the Triangle								
The star at the top of the Triangle	α Tri	22*	10	16	30	N	3	longitude °: codex 82
The leading one of the three at its base	β Tri	27*	10	20	40	N	3	longitude °: codex 23
The star at the end of these three	γ Tri	28	0	19	0	N	3	

The beginning of the names of the fixed stars in the constellations that are seen in the belt of the signs, for the year 1191 of Dhū l-Qarnayn, which is the year 271 of the Hijra

The year 1191 of Dhū l-Qarnayn began on 1 September 879, in the year 266 of the Hijra; the year 271 of the Hijra began in June 884

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The names of the stars of the figure of the Ram								
The leading star of the two in the horn of the Ram	γ Ari	17*	50*	7	20	N	3 lesser	longitude °: codex 14; longitude ′: codex 40
Ar. p. 255								
The trailing star of them	β Ari	18	50*	8	20	N	3	longitude ′: codex 40
The northern one of the two in the mouth of the Ram	η Ari	22	10	7	40	N	5	
The southern star of them	θ Ari	22	40*	6	0	N	5	longitude ′: codex 20
The star on the neck of the Ram	ι Ari	17	40	5	30	N	5	
The one on the back of the Ram	ν Ari	28	40	6	0	N	6	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The one where its rump comes out	ε Ari	32	30	4	50*	N	5	latitude ′: codex 40
The leading one of the three on its rump	δ Ari	35	0	1	40*	N	4	latitude ′: codex 50
The middle star of them	ζ Ari	36	30	2	30	N	4	
The trailing one of these three	τ^2 Ari	38	10	1	50	N	4	
The star behind the thigh of the Ram	ρ^1 Ari	30	50*	1	10	N	5	longitude ′: codex 30
The one above the middle of its thigh	σ Ari	29	10	1	30*	S	5	latitude ′: codex 10
The one on the back of its hind foot		26†	10	5	15	S	4 greater	longitude °: Part II 28
And of those that are not in its figure								
The one above its head	α Ari	21	30	10	0	N	3	
Of the names of the stars in the figure of the Bull								
The northern one of the four on the cut-off part of the Bull	*f* Tau	37*	30	6	0	S	4	longitude °: codex 36
The second of these four, which follows it	*s* Tau	37*	10*	7	15	S	4	longitude °: codex 36; longitude ′: codex 50
The southern one of these four on its cut-off part	o Tau	35	30	9	15	S	4	
The star on the breast of the Bull	λ Tau	44*	50*	8	0	S	3	longitude °: codex 46; longitude ′: codex 30
The one on its right shoulder	*e* Tau	40	50*	9	50†	S	5*	longitude ′: codex 30; latitude ′: Part II 30; magnitude: codex 4
The one in the face of the Bull, on its nose, one of the stars of al-Dabarān	γ Tau	50	10*	5	45	S	3 lesser	longitude ′: codex 0
Ar. p. 256								
The one between this star and its northern eye	δ^1 Tau	51	30	4*	15	S	3 lesser	latitude °: codex 1
al-Dabarān, which is on its eye and under its southern horn	α Tau	53	50	5	10	S	1	
The one between the first and its other, southern eye	θ^1 Tau	52	0	5	50	S	3 lesser	
The one that follows this, on its northern eye	ε Tau	53	0	3	0	S	3*	magnitude: codex 4
The one on the root of its horn, by its southern ear	*i* Tau	58*	40	4	0	S	5	longitude °: codex 57
The one on the middle of its southern horn, of the two	*m* Tau	61	30	5	0	S	5	
The one on the root of its northern horn	τ Tau	56	50	4	0	S	4	
The one on the tip of its southern horn	ζ Tau	68	50	2	30*	S	3	latitude ′: codex 50
The one on the tip of its northern horn, which is on the foot of the Holder of the Reins	β Tau	66	50	5	0	N	3	
The northern one in the leading row of the Pleiades		43	20	4*	30	N	5*	latitude °: codex 5; magnitude: codex 3
The northern one at the end of the leading side of the Pleiades		43	30	3	40	N	4	Nallino's translation has «southern»
The small trailing one at the rear of the Pleiades		44	50	3	20	N	5*	magnitude: codex 3

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The small one outside the Pleiades on the north		44	50	5	0	N	4	
The names of the stars in the figures of the Twins								
The one on the head of the leading Twin	α Gem	94	30	9	30*	N	2	latitude ′: codex 20
The one on the head of the trailing Twin	β Gem	97	50	6	15	N	2	
The one ahead of the foot of the leading Twin	η Gem	77	40	1	30	S	4 greater	
The one on the tip of the foot of the leading Twin	ν Gem	81*	20	3	30	S	4 greater	longitude °: codex 101
The one on the tip of the left foot of the trailing Twin	γ Gem	83*	10	7	30	S	3	longitude °: codex 103
Ar. p. 257								
The one on the tip of the right foot of the trailing Twin	ξ Gem	85*	50	10	30	S	4	longitude °: codex 105
The one on the left knee of the trailing Twin	ζ Gem	89*	40	2	30	S	3	longitude °: codex 109
The one on the middle of the right flank of this Twin	λ Gem	92	50	6	0	S	3	
The one on the left side of this Twin	δ Gem	92	50	0	30	S	3	
The one on the left knee of the leading Twin	ε Gem	84*	10	1	30*	S	4 greater	longitude °: codex 104; latitude ′: codex 10
The names of the stars in the figure of the Crab								
The middle of the Manger, which is the nebulous one in the breast of the Crab	ε Cnc	111	30	0	40	N	nebulous	
The northern one of the two by the nebulous square, in the darkness	η Cnc	108*	50	1	15	N	4 lesser	longitude °: codex 111
The southern star of them; the two are called the Square	θ Cnc	109*	10	11†	10	S	4 lesser	longitude °: codex 112; latitude °: Part II 1
The one on the northern claw of the Crab	ι Cnc	109	30	11	50	N	4 greater	
The one on the southern claw of the Crab	α Cnc	117*	40	5	30	S	4	longitude °: codex 111
The one on the tip of its southern hind foot	β Cnc	108	20	7	30	S*	4*	side: codex N; magnitude: codex 5
The one on the tip of its northern hind foot	μ^2 Cnc	103	50	1	0	N	5*	magnitude: codex 4
The southern one of the two that we have mentioned	β Cnc	108	20	7	30	S	4 greater	
The northern one of the two by the nebulous one, which are the Two Asses	γ Cnc	111	30	2	40	N	4 greater	
The southern star of them	δ Cnc	112	30	5†	10	S	4	latitude °: Part II 0
Ar. p. 258								
The names of the stars of the figure of the Lion								
The star on the tip of the nostril of the Lion	κ Leo	119	30	10	0	N	4	
The northern one of the two in the head of the Lion	μ Leo	125	30*	12	0	N	3	longitude ′: codex 0
The middle one of the three in its neck	γ Leo	133	20	8	30	N	2	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The leading one of the three in its neck, which is the northern one	ζ Leo	131*	20	11	0	N	3*	longitude °: codex 135; magnitude: codex 4
The southern one of these three in the neck of the Lion	η Leo	101†	50	4	30	N	3	longitude °: Part II 131
The Heart of the Lion, which is called al-Mākin	α Leo	134	0	0	10	N	1	Nallino takes «al-Mākin» for an error for «al-Malakī», «the royal»
The leading one of the two on its back	*b* Leo	142	30	12	15	N	5	
The star that follows this	δ Leo	145*	20	13	40	N	2 lesser*	longitude °: codex 144; magnitude: codex 4 lesser
The one in the hind thigh of the Lion	ι Leo	151*	30	5*	50	N	3	longitude °: codex 152; latitude °: codex 4
The second, also in its hind thigh	σ Leo	152	50	1	15	N	4	
The one in the middle of its hind thigh too	υ Leo	158	40	3	0	S	5	
al-Ṣarfa, which is the star on the tip of its tail	β Leo	154†	40	11	50*	N	1	longitude °: Part II 155; latitude ′: codex 30
The northern one of the two in the rear of the Lion	71 Leo	145	30	11	30	N	5	
The southern star of them	θ Leo	147	30	9	40	N	3	
The star on the right knee of the Lion	ψ Leo	128	30*	0	0	–	5	longitude ′: codex 20
Of the stars of the Lock, which are not of the figure of the Lion								
The first of them, Bulūqāmus, which is the star between the tail of the Lion and the Lance-bearing Simāk		156	0	30	15	N	conspicuous	
Ar. p. 259								
The large leading one on the braid, which is called the Mane of the Lion	4 Com	155	30	25	0	N	faint	
The star that follows it on the braid	21 Com	159	40	25	30	N	faint	
These three are called the Locks								
The names of the stars of the figure of the Virgin and the Ear of Grain								
The southern one of the two in the head of the Virgin	ν Vir	157	30	4	15	N	5	
The star north of it	ξ Vir	158	10	5	40*	N	5	latitude ′: codex 10
The one on the back, by the left wing	β Vir	160	10	0*	10	N	3	latitude °: codex 1
The leading one of the four in the left wing	η Vir	169*	25	1*	10	N	3*	longitude °: codex 161; latitude °: codex 0; magnitude: codex 4
The star that follows this	γ Vir	174*	20	2	50	N	3	longitude °: codex 172
The one in the right side, under the breast	δ Vir	175*	30	8	30	N	3	longitude °: codex 172
The trailing one of these four that were mentioned	θ Vir	182*	10	1	40	N	4	longitude °: codex 172
The one on the tip of the left foot	λ Vir	201	10	0	30	N	4	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The one on the tip of the right, northern foot	μ Vir	203	50	9	50	N	4	The Arabic has «the northern one on the tip of the right foot», as the codex does (Nallino)
The one along the train of the Ear of Grain	ι Vir	197	50	7	30	N	4	
The one of the three in the northern wing, the Forerunner of the Vintage	ε Vir	173*	20	15	10*	N	3	longitude °: codex 203; latitude ′: codex 30
The bright one on the tip of the left hand, which is the Ear of Grain and is called the Unarmed Simāk	α Vir	187*	50*	2	0	S*	1	longitude °: codex 207; longitude ′: codex 30; side: codex N
The star on the girdle and on the right buttock	ζ Vir	186*	0	8	40	N*	3	longitude °: codex 206; side: codex S
Ar. p. 260								
The names of the stars of the figure of the Balance								
The bright star of the stars of the southern pan	α Lib	209	10	2	0	N	2	
The faint one north of this star	μ Lib	208	10	2	30	N	5	
The bright one of the stars at the end of the northern pan	β Lib	213	20*	8	20	N	2	longitude ′: codex 5
The middle one of those in the southern pan	ι¹ Lib	215	10	1	40	S*	4	side: codex N
The star that precedes this star	ν¹ Lib	212	30	1	15	N	4	The Arabic has «follows», as the codex does (Nallino)
The middle star of the northern pan	γ Lib	219	0	4	45	N	4	
The names of the stars of the figure of the Scorpion								
The northern one of the three between the eyes of the Scorpion	β Sco	227	40	1	20	N	3	
The middle one of these three	δ Sco	226	50*	1	40*	S	3	longitude ′: codex 30; latitude ′: codex 20
The southern star of these three	π Sco	226	50*	5	0	S	3	longitude ′: codex 30
The leading one of the three bright ones in the breast of the Scorpion	σ Sco	231	30	3	45	S	3	
The Heart of the Scorpion, which is the red middle one of them	α Sco	233	50*	4	0	S	2	longitude ′: codex 30
The trailing star of these three	τ Sco	235	40*	5	30	S	3	longitude ′: codex 30
The star that follows this, on the first vertebra	ε Sco	239	40	11	0	S	3	
The one on the second vertebra	μ Sco	240	0	15	0	S	3	
The northern one of the double star on the third vertebra	ζ¹ Sco	241	10	18	40	S	4	The Arabic has «the double northern one», as the codex does; Nallino follows Ptolemy
The one that follows it, on the fourth vertebra	η Sco	244*	20	19	30	S	3*	longitude °: codex 245; magnitude: codex 4

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The one following it, on the fifth vertebra	θ Sco	249	20	18	50	S	3	
The one that follows it, on the sixth vertebra	ι Sco	251	40	16	40	S	3	
Ar. p. 261								
The one on the seventh vertebra, by the sting, which is al-Shawla	κ Sco	250	10	15	10	S	3	
The trailing one of the two in al-Shawla	λ Sco	248	40	13	20	S	3	
The leading one of them	υ Sco	248	10	13	30	S	4*	magnitude: codex 3
And of those not in a figure								
The northern nebulous one that follows al-Shawla		252	20*	13	15*	S	nebulous	longitude ′: codex 0; latitude ′: codex 20
The names of the stars of the figure of the Archer, the Bow and the Arrow together								
The star on the point of the arrow	γ Sgr	255	40	6	20	S	3	
The one on the grip of the left hand	δ Sgr	258	50*	6	30	S	3	longitude ′: codex 30
The star in the southern part of the bow	ε Sgr	259	10	10	50	S	3*	magnitude: codex 4
The southern one of the two in the northern part of the bow	λ Sgr	260	10	1	30	S	3	
The northern one of them, which is at the end of the bow	μ Sgr	257	50	2	50	N	3	
The star on the shoulder of the Archer	σ Sgr	266	30	3	10	S*	3*	side: codex N; magnitude: codex nebulous
The one ahead of this, which is on the arrow	φ Sgr	264	10	4†	45	S*	4 lesser	latitude °: Part II 3; side: codex N
The nebulous double star on the eye of the Archer	ν² Sgr	266	20	0	45	N	nebulous*	magnitude: codex 3
The one on the left fore hock of the Archer	β Sgr	268	50*	23	0	S	3	Nallino is unsure of the correction of the longitude, since the copy of the catalogue that al-Ṣūfī used also had 30′; the magnitude 3, where Ptolemy has 2, may be al-Battānī's own correction (Nallino); longitude ′: codex 30
The middle one of the three on the back of the Archer, which is on the shoulder	τ Sgr	268	50*	4	30	S	4*	The codex's magnitude 3 may be al-Battānī's own correction (Nallino); longitude ′: codex 30; magnitude: codex 3
The following one, which is under the armpit and next to the middle one of those on the back	ζ Sgr	267	30	6	45	S	3	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
Ar. p. 262								
The one on the knee of the Archer's left leg	α Sgr	268	10	18	0	S	3	The magnitude 3, where Ptolemy has 2, seems to be al-Battānī's own (Nallino)
The one on the hock of the fore leg	η Sgr	257	50*	13	0	S	3	longitude ′: codex 30
The one in the left thigh	θ Sgr	278	30	13	30	S	3	
The one on the right hind shank of the Archer	ι Sgr	277	30	20	10	S	3	
The northern one of the four at the root of the rump, which is the Hock of the Archer	ω Sgr	274	0	6	30	S	1	Among other Arabic authors the Hock of the Archer is the ninth star; the numbers differ widely from Ptolemy's, but al-Battānī computed the tables of 1211 from them (Nallino)
The one that follows it in the northern line	A Sgr	280	0*	4	50	S	5	longitude ′: codex 20
Of the names of the stars of the figure of the Kid								
The leading one of the three in its trailing horn	α^1 Cap	288	30	7	20	N	3	Nallino: more correctly «the northern one»
The middle one of these three	ν Cap	288	50*	6	40	N	6	longitude ′: codex 30
The southern one of these three that were mentioned	β Cap	288	30	5	0	N	3	
The southern one of the three in the mouth of the Kid	ο Cap	290	10	0*	45	N	6	latitude °: codex 45
The leading one of the two that remain of the three in the mouth of the Kid	π Cap	289	50	1	45	N	6	
The third star, which follows it in its mouth	ρ Cap	290	0	1	30	N	6	
The one under the right knee of the Kid	ψ Cap	292	0	6	30	S*	4	side: codex N
The one on its left knee	ω Cap	292	50	8	40	S	4	
The leading one of the two close together in the belly of the Kid	ζ Cap	301	20	6	50	S	4	
The star that follows this in its belly		301	30	6	0	S	5	
The leading one of the two by the tail of the Kid	γ Cap	305*	0	2	10*	S	3	longitude °: codex 309; latitude ′: codex 30
The star that follows it	δ Cap	307	30	2	0	S	3	The Arabic has «the leading one of the four in the north of its tail», the name of a star the catalogue leaves out: the codex displaces the names of the twelfth to fifteenth stars (Nallino)

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
Ar. p. 263								
The southern one of these three that remain	μ Cap	309	50	0	0	–	5	The Arabic has «the middle one of these three that remain», the name of the next star (Nallino)
The middle one of these three	λ Cap	308	50	2	50	N	5	The Arabic has «the northern one of those on the tip of its tail», the name of the next star (Nallino)
The northern one of those on the tip of its tail	c^1 Cap	309	50	4	20	N	5	The Arabic has «the star that follows it», the name of the twelfth star (Nallino)
The leading one of the two in the spine of the Kid	ε Cap	304	30	4	45	S	4	The Arabic has «of the one in the back of the Kid», an error for «of the two in the spine» (Nallino)
The leading one of the two stars in its back	θ Cap	297	50	0	0	S	4	
The southern one of the four in the north of its tail	μ Cap	303	0	0*	0	S	5*	The thirteenth star repeated, with its longitude from a misreading (Nallino); latitude °: codex 3; magnitude: codex 4
Of the names of the stars of the Bucket and the Water-pourer								
The star on the head of the Bucket	*d* Aqr	311	30	15*	45	N	5	latitude °: codex 5
The bright one of the two on the right shoulder of the Water-pourer	α Aqr	317	30	11	0	N	3	
The faint star under it	o Aqr	316	20	9	40*	N	5	latitude ′: codex 50
The one on the left shoulder of the Water-pourer	β Aqr	307	40*	8	50	N	3	longitude ′: codex 20
The following one of the three in the left hand	ν Aqr	298	50	5	30	N	3	The Arabic has «the one that follows the three»: the codex omits «of» (Nallino)
The middle one of these three	μ Aqr	297	20	8	0	N	4	
The leading star of these three	ε Aqr	295	50	8	40*	N	3	latitude ′: codex 20
The one on the right arm of the Water-pourer	γ Aqr	320	40	8	45*	N	3	The Arabic has «in the thigh of the right shank», an error for «the arm of the Water-pourer» (Nallino); latitude ′: codex 7
The northern one of the three on the tip of the hand	π Aqr	322	50	10	45	N	3	The Arabic has «on the tip of its tail», an error for «the hand» (Nallino)
The leading one of the two southern ones that remain	ζ Aqr	323	10	9	0	N	3	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The star that follows this	η Aqr	324	30	8	30	N	3	
The southern one of the two in the right shank	δ Aqr	322	50	7	30	S*	3	side: codex N
The leading one of the five in the outflow of the water		326	10	2	0	N	4	
Ar. p. 264								
The one that follows it on the south	λ Aqr	326	0	0	10	N	4	
The one that follows this, after the handle	*h*¹ Aqr	328	50	1	10	S	4	
The one that follows it too	φ Aqr	321†	10*	0*	30*	S	4	longitude °: Part II 331; longitude ′: codex 40; latitude °: codex 3; latitude ′: codex 0
The southern one of those in the handle	χ Aqr	331	30†	1	40	S	4	longitude ′: Part II 40
The trailing one of those in the outflow of the water, which is the Mouth of the Southern Fish	α PsA	318	10	20	20	S	1	
The northern one of the two to the south of those in the handle	ψ¹ Aqr	330	10	3	30	S	4	
The leading one of the two close together in the shank of the Water-pourer	θ Aqr	322	50	4†	30	N	3	Nallino: all the numbers but the side are those of the twelfth star; the true ones are 317° 20′, 3° 0′ north, magnitude 4; latitude °: Part II 7
The northern one of the two on the southern side of the handle		330	10	3	30	N	5	The nineteenth star repeated in the codex; Nallino leaves the row out of the Latin translation
The one on the right buttock of the Water-pourer	σ Aqr	319	50	0*	50*	S	5	latitude °: codex 3; latitude ′: codex 20
The middle one of the three in the first bend of the handle	A² Aqr	333	20*	14	45	S*	5*	longitude ′: codex 0; side: codex N; magnitude: codex 4
The first of the three in the second bend of the handle	*c*¹ Aqr	323*	0	14	45	S	4	longitude °: codex 328
The southern one of the two in the left buttock	ι Aqr	312*	50	1*	40	S	4	longitude °: codex 317; latitude °: codex 11
The middle one of the other three in the second bend of the handle	*b*² Aqr	328	40	15	0	S	4	Nallino's translation has «first», as the codex does
The northern one of the two in the left shank, under the knee	*g*¹ Aqr	319	0	9	0	S*	5	side: codex N
And of those not in the figure								
The leading one of the three that follow the handle of the jar	2 Cet	337	50*	15	30	S	4 greater*	longitude ′: codex 30; magnitude: codex 2 greater
Ar. p. 265								
The northern one of the two that remain	6 Cet	340	50	14	40	S	4 greater	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The star that follows them, just after the handle of the jar	7 Cet	340	10	18	15	S	4 greater	
Of the names of the stars of the figures of the two Fishes								
The one in the mouth of the leading Fish, the southern one	β Psc	332	50	9	15	N	4 greater	
The southern one of the two in the head of this Fish	γ Psc	335*	20	7	30	N	4*	longitude °: codex 334; magnitude: codex 3
And the northern one of these two stars in its head	*b* Psc	337	10	9	20	N	4	
The leading one of the two in its back	θ Psc	339	20	9	30	N	4	
The second star of the two in its back	ι Psc	341	50	7*	30	N	4	latitude °: codex 20
The leading one of the two in the belly of the southern Fish	κ Psc	337*	10	4*	30	N	4	longitude °: codex 340; latitude °: codex 3
The trailing star of them	λ Psc	340*	50	3	30	N	4	longitude °: codex 342|347
The star in the tail of this Fish	ω Psc	347	10	6	20	N	4	
The leading one of those in its tail, on the flaxen cord	*d* Psc	352	10	5	45	N	6	Ptolemy has «the first of those on the cord, counting from the tail»; the translators read «on» for «from» (Nallino)
The one that follows this star	51 Psc	354*	10	3	45	N	6*	longitude °: codex 355; magnitude: codex 5
The leading one of the three bright ones after those mentioned before	δ Psc	358	20	2	15	N	4	
The middle one of them	ε Psc	1	40	1	10	N	4	
The one that follows this, of the three	ζ Psc	4	10	6	0	S*	4	side: codex N
The northern one of the two close together in the handle	*e* Psc	3	30	2	0	S*	6	«The handle» is an error, here and at the sixteenth star, for «the bend» of the cord (Nallino); side: codex N
The southern star of them	*f* Psc	4	30	5	0	S*	6	side: codex N
The middle one of the three after the handle	ν Psc	9	30	4	40	S†	4	side: Part II S
The one on the knot of the two flaxen cords	α Psc	13	40	8	30	N†	3	side: Part II S
Ar. p. 266								
The leading one north of the knot of the flaxen cord	ο Psc	11	40	1	20	N	5†	magnitude: Part II 4
The middle one of the three in the knot	η Psc	11	50	5	20	N	3	
The northern one of the two in the mouth of the northern Fish	*g* Psc	13	10	21	45	N	5	
The northern one of the three on the tip of the tail	ρ Psc	11	40	9	0	N	4	
The leading one of the three on the spine of this Fish	ψ¹ Psc	6	50	14	20	N	4	
The middle one of them	ψ² Psc	7	50	13	0	N	4*	magnitude: codex 3
The trailing one of these three	ψ³ Psc	8	50	12	0	N	4	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The northern one of the two in its belly	υ Psc	13	20	17	0	N	4*	magnitude: codex 6
The southern star of them	φ Psc	11	0	15	20	N	4	
The one on its trailing spine, by its tail	χ Psc	11	10	11	45	N	4	
And of those not in their figures, the one just under the quadrilateral	27 Psc	342*	20*	2	40	S	4	longitude °: codex 352; longitude ′: codex 46

Of the names of the fixed stars in the constellations south of the belt of the signs, for the year 1191 of Dhū l-Qarnayn

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
Of the stars of Qīṭus, which is the Beast of the Sea								
The one on the tip of the nose of the Beast of the Sea, which is Qīṭus	λ Cet	28	50	7	45	S	4*	magnitude: codex 3
The trailing one of the three in its throat, on the tip of its jaw	α Cet	28	50	12	20	S	3	
The middle one of them, which is in the middle of its mouth	γ Cet	23	50	11	30	S	3	
The leading one of the three on its chin	δ Cet	21	40	14	0	S	3	
The one on its forehead, above its eye	ν Cet	21	20	8	10*	S	4	latitude ′: codex 45
The southern one of its trailing side	π Cet	18	10	27	30	S	3	
Ar. p. 267								
The middle one of the three in its body	τ Cet	3	10	25	20	S	3	
The northern one of these three	ζ Cet	6	10	20	0	S	3	
The trailing one of the two stars in its tail	θ Cet	0	50	15	20	S	3	
The leading one of them	η Cet	356*	10	15	40*	S	3	longitude °: codex 346; latitude ′: codex 30
The northern one in its leading side		350	30	13	0	S	5 greater	
The northern one by the two on the tip of its tail	ι Cet	345	50	9	40	S	3 lesser*	magnitude: codex 3 greater
The southern star on the tip of its tail	β Cet	346*	50	20	20*	S	3 greater*	longitude °: codex 345; latitude ′: codex 40; magnitude: codex 4 lesser
And of the stars of the Giant								
The nebulous one in the head	λ Ori	68	10	16	30	S	nebulous	
The bright one on the right shoulder, which is the Shoulder of al-Jawzāʾ	α Ori	73	10	17	0	S	1 lesser	
The one on the left shoulder	γ Ori	65	10	17	30	S	2 greater†	magnitude: Part II 2 lesser

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
And the one under this one on the left shoulder	A Ori	66	10*	18*	0	S	4 lesser	This row is written in the margin of the codex (Nallino); longitude ′: codex 20; latitude °: codex 8
The northern one of the nine on the pelt in the left hand	15 Ori	61	40	8	0	S	4	
The star on the right elbow	μ Ori	75	30	14	30	S	4	
The sixth of them, in the north	π^1 Ori	56	0	15	50	S	3	
The seventh, after this one in the north	π^3 Ori	56	0	17	10	S	3	
The eighth, after it in the north	π^5 Ori	56	30	20*	20	S	3	latitude °: codex 21
The ninth, which is in the south of those on the pelt and is called al-Mijlad, the Whip	π^6 Ori	57	30	21*	30	S	3	«Al-Mijlad» is Nallino's conjecture for the codex's «المحلة»; Nallino knows the name from nowhere else; latitude °: codex 29
The leading one of the three in the belt	δ Ori	66	30	24	10	S	2	
Ar. p. 268								
The middle one of them	ε Ori	68	30	24	50*	S	2	latitude ′: codex 30
The trailing one of the three in the belt	ζ Ori	69	20	25	40	S	2	
The one by the hilt of the sword	η Ori	65	0	25	50	S	3	
The northern one of the three adjoining ones by the tip of the sword	*c* Ori	67	40*	28*	40	S	4	longitude ′: codex 50; latitude °: codex 20
The middle one of these three	θ^2 Ori	67	50	29	10	S	3 lesser	
The leading one of these three, which is the southern one of them	ι Ori	67	50	29	20†	S	3	latitude ′: Part II 50
The bright one on the tip of the left foot, which is the Foot of al-Jawzāʾ	β Ori	61	0	31	30	S	1	
The star north of this, which is above the ankle	τ Ori	62	10	30	15	S	4	
The outlying one under the left heel	*e* Ori	64	30	31	10	S	4	
The one under the trailing right knee	κ Ori	71	20	33	30	S	3 greater	
And of the stars of the River								
The one on the tip of the foot of the Giant, which is at the head of the River	λ Eri	59*	30	31*	50	S	4 greater	longitude °: codex 69; latitude °: codex 30
The large bright one, which is the last of the stars of the River	θ Eri	11	20	53*	30	S	1	latitude °: codex 33
The following one of the four in the stretch	γ Eri	38	10	32	50	S	3	The Arabic has «the one that follows the four»: the codex omits «of» (Nallino)
The third, ahead of the middle one	δ Eri	35	20	28	50	S	3	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The leading one of the four	ε Eri	33	10	28	0	S	3	
The trailing one of the four	ζ Eri	28	20*	25	30	S	3	longitude ′: codex 30
The third star, which is before this fourth one	η Eri	23	20	23	30	S	3	
The one in the bend of the River, which is at the end of the breast of Qīṭus	τ¹ Eri	16	20	32	10	S	4	
Ar. p. 269								
The northern one in the leading side of the four in the Ford	τ⁶ Eri	32	30	41	20	S	4	«The Ford» is Nallino's tentative conjecture for the codex's «الجوزا», which Nallino does not understand; Ptolemy has «in the trapezium»
The trailing one of these four	τ⁹ Eri	35	50	43	20	S	4	
The trailing one of the two after the bend, which is called al-Turba	υ⁵ Eri	39	20	53	50	S	4	«The bend» is Nallino's conjecture for the codex's «the desert»; the name al-Turba, «the grave», is certainly a false reading (Nallino)
The trailing one of the three after the two	υ³ Eri	29	0	53	0	S	4	
The northern one of the two facing each other	υ⁶ Eri	45	20	53*	20	S	4	latitude °: codex 63
The southern one of them	υ Eri	46	10	51	45*	S	4	latitude ′: codex 50
And of the stars of the Hare								
The northern one of the four on its back, in the leading side	ι Lep	60	30	35	0	S	5	«On its back» is wrong: Ptolemy and the others have «on its ears» (Nallino)
The northern one of the trailing side of them	ν Lep	62	30	35	40	S	5	
The southern one of those in the leading side	κ Lep	61	0	36	30	S	5	The codex leaves out the name of this star but keeps its numbers, so that the names down to the fifth star of the Dog stand one row too high, until the scribe inserts a false name. Nallino's translation, like the English, gives each row its genuine name. The Arabic has «the star on the chin of the Hare»
The star on the chin of the Hare	μ Lep	60	20	39	15	S	4 greater	The Arabic has «the one ahead of the tip of its left fore foot»
The one ahead of the tip of its left fore foot	ε Lep	57	20	45	15	S	4 greater	The Arabic has «the one on the middle of its body»

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The one on the middle of its body	α Lep	67*	0	41	30	S	3	The Arabic has «the star under its belly»; longitude °: codex 61
The star under its belly	β Lep	65	30	44	20*	S	3	The Arabic has «the northern one of the two in the hind feet»; latitude ′: codex 50
The northern one of the two in the hind feet	δ Lep	72	10	44	0	S	4 greater	The Arabic has «the southern star of them»
The southern star of them	ɣ Lep	70	10	45	50*	S	4 greater	The Arabic has «the star on its back»; latitude ′: codex 45
The star on its back	ζ Lep	71	10	38	20*	S	4 greater	The Arabic has «the star on the tip of its rump»; latitude ′: codex 40
Ar. p. 270								
The star on the tip of its rump	η Lep	73	50	38	10	S	4 greater	The Arabic has «the star on its ears», and puts the row under the heading of the Dog
The names of the stars of the figure of the Dog								
The star on its ears	θ CMa	90	50*	35	0	S	4	The Arabic has «the star in its head»; longitude ′: codex 30
The star in its head	μ CMa	92	30	36	30	S	5	The Arabic has «the bright one in the mouth of the Dog, which is al-Shiʿrā al-Yamāniya»
The bright one in the mouth of the Dog, which is al-Shiʿrā al-Yamāniya	α CMa	88*	50	39*	10	S	1	The Arabic has «the one on the tip of its fore foot»; longitude °: codex 108; latitude °: codex 59
The one on the tip of its fore foot	β CMa	82*	10	41	20	S	3	The Arabic has «the one at the root of its left thigh»; longitude °: codex 102
The one at the root of its left thigh	δ CMa	97	50	48	45	S	3 lesser	The Arabic has «the one at the root of its right thigh», the name that the scribe inserts to restore the order (Nallino)
The one under its belly, between its thighs	ε CMa	94	50	51	30	S	3	
The one on its right foot	ζ CMa	80*	50	53	45	S	3	longitude °: codex 100
The star in its tail	η CMa	103	20	50*	40	S	3 lesser*	latitude °: codex 30; magnitude: codex nebulous lesser
And of those not in its figure								
The trailing one of the two bright ones	β Col	70	10	59	40	S	2	
The leading one of them	α Col	67	10	57	40	S	2	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
Of the stars of the Forerunner of the Dog								
The one in the Forerunner of the Dog, which is on its neck	β CMi	96	10	14*	0	S	4	latitude °: codex 54
The bright following one, in its loins, which is al-Shiʿrā al-Shāmiya	α CMi	100	20	16*	10	S	1	The word printed «حقه» is read here as «حقوه», «its loins»; Nallino's translation leaves it out; latitude °: codex 56

The rest of the stars of the figure of Aqrāṭīr, which is the Cup

A folio of the codex is lost here: it held the stars of the Ship and of the Water-snake and the first stars of the Cup (Nallino)

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The star on the northern rim of the mouth of the Cup	ε Crt	160	30	13	40	S	4	
Ar. p. 271								
The star on the southern handle of the Cup	η Crt	170*	20	16	10	S	4	longitude °: codex 171
The one on the northern handle of the Cup	θ Crt	162	50	11	50*	S	4*	latitude ′: codex 30; magnitude: codex 5
The names of the stars of the figure of the Crow								
The one on the beak of the Crow, by the Water-snake	α Crv	176*	30	21	40	S	3	longitude °: codex 186
The one on its neck, near its head	ε Crv	175*	30	19	40	S	3	longitude °: codex 188
The one in the right, leading wing	γ Crv	174	40	14	50	S	3	
The leading one of the two in the trailing wing	δ Crv	177	50*	12	30	S	3	longitude ′: codex 30
The trailing star of them	η Crv	178	10	11	45†	S	4	latitude ′: Part II 45
The one on the tip of its foot, by the Water-snake	β Crv	181	40	18	50†	S	4†	latitude ′: Part II 10; magnitude: Part II 3
Of the names of the stars of Qanṭāwurus, which is the figure of a man and a horse and is called al-Ẓulmān, the Male Ostriches								
The southern one of the four in the head of Qanṭāwurus	*g* Cen	201	40*	21	40	S	5 greater	longitude ′: codex 20
The northern star of them	*h* Cen	201	10	18	50	S	5 greater	
The leading one of the two middle ones that remain	*i* Cen	200	20	20	30	S	4 greater	
The trailing one of these two, which is the remaining one of the four	*k* Cen	201	10	20	0	S	5 greater	The Arabic has «the second of the four», an error for «the remaining one» (Nallino)
The one on the left, leading shoulder	ι Cen	197	20	25	40	S	3	
The one on the right, trailing shoulder	θ Cen	206	50*	22	30	S	3	longitude ′: codex 30
The one of the two that remain, on the top of the shoot	π Cen	213	10	18	15	S	4 greater	
The leading one of the three on the right side	τ Cen	204	30	28	20	S	4 greater	
The middle one of them	υ Cen	205	10	29	20	S	4 greater	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
Ar. p. 272								
The trailing one of these three	φ Cen	206	20	28	0	S	4 greater	
The one on the right arm	*m* Cen	207	30	26	30	S	? greater†	magnitude: Part II 4 greater
The one on the right forearm	κ Cen	214	0	25	15	S	3	
The bright one at the root of the left side	λ Cen	209	10	33	30	S	3	
The trailing one of the faint stars north of it	*n* Cen	208	50	31	0	S	5*	magnitude: codex 4
The leading one of the faint stars north of it	χ Cen	208	0	30	20	S	5	
The trailing one of the three on the flank, on the right	μ Cen	197*	0	40	0	S	3	longitude °: codex 193
The leading one of the two close together in the right thigh of the horse	β Cen	193	50*	46	10	S	3	longitude ′: codex 30
The leading one of the two under the belly of the horse		207	30*	43	0	S	2	longitude ′: codex 20
The trailing star of them		208	50	43	45	S	3	Al-Ṣūfī says that there is no star at this place (Nallino)
The one in the right thigh, near the foot	ν Cen	201	10	51	10	S	2	Other Arabic authors call it the Foot of Qanṭāwurus. The longitude comes from a misreading of the sign, 9° 30′ of Libra for 9° 30′ of Scorpio; al-Ṣūfī notes the same error in al-Battānī, in many copies of the Almagest and in the Verified Tables (Nallino)
The one on the left foot, on the hoof	ζ Cen	202	20	55	20	S	2	
The bright one on the tip of the right fore foot, which is the Foot of the Horse	α Cen	199	30	41	10	S	1	Perhaps «the Horse» is an error for «Qanṭāwurus»; compare the last line of p. 275 (Nallino)
The star on the left knee of the leg	γ Cen	215*	20*	45	20	S	2	longitude °: codex 216; longitude ′: codex 0
The one on the right hock	ξ Cen	206*	30	51	40	S	2	longitude °: codex 207
The sixth of those on the right hind leg	ε Cen	205	50	49	10	S	4†	Ptolemy has «the outlying one under the right hind foot»: the translation that al-Battānī used read «sixth» (ἕκτος) for «outside» (ἐκτός) (Nallino); magnitude: Part II 4
The one under the middle of the left thigh	*f* Cen	197	30	55	10	S	4	

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The names of the stars of the figure of the Beast								
The star on the tip of the hind foot of the Beast	ο Lup	219	10	24	50	S	3	Baily reads «fore» for «hind», more correctly (Nallino)
Ar. p. 273								
The one on the middle of its hind thigh	α Lup	217*	0*	29	10	S	3	longitude °: codex 216; longitude ′: codex 40
The northern one of the three on the tip of its tail	κ Lup	214	10	29	20	S	4 greater	
The southern one of the two in its fore foot	ε Lup	218	20	11	30	S	4 greater	
The northern one of the two in its neck	μ Lup	230	30	15	20	S	4 greater	
The northern one of the two in its fore foot	δ Lup	217	40	10	0	S	4 greater	
Of the names of the stars of the figure of the Censer, which is called the Spreader of Scent								
The northern one of the two at the bottom of the Censer	γ Ara	248	50	22	40	S	5	
The one in the middle of its top, which is the place of the fire	α Ara	247	20	26	30	S	4 greater	
The southern one of the two close together in the flame of the fire	ζ Ara	246	20	34	10	S	4 greater	
The one on the tip of the flame, of the tongue of fire		242	0	34	0	S	4	
[The southern one of the two at the bottom of the Censer]		254	10	25*	45	S	4	The scribe leaves out the name of this star; Nallino supplies it; latitude °: codex 21
The names of the stars of the figure of the Southern Crown								
The leading one of the six in the arc of the Southern Crown	α CrA	260	20	21	30	S	4	
The fourth star of these six	β CrA	266	0	20	0	S	4	
The one that follows it, which is ahead of the knee of the Archer	η CrA	267	20	18	30	S	5	
The bright one that follows this on the north	θ CrA	268	10	17	10	S	2	
The one north of this bright one	γ CrA	268*	0	16	0	S	4	longitude °: codex 272
The leading one of the two faint ones	ν CrA	265	50	14	50	S	6	
The remaining star of the faint ones	ι CrA	263	0	14	40	S	5	
Ar. p. 274								
The one preceding this, too	κ CrA	260	50*	15	50	S	5	longitude ′: codex 30
The remaining star, south of this	λ CrA	260	20	18	30*	S	5	latitude ′: codex 50

Description	Star	Longitude °	′	Latitude °	′		Magnitude	Notes
The names of the stars of the figure of the Southern Fish								
[The leading one of the three in the southern curve of the head]	β PsA	311	50	20	20	S	4	The Arabic has the name of the first star, «the star in the mouth of the Southern Fish, at the end of the water». Al-Battānī leaves out the numbers of that star, which is the eighteenth of the Water-pourer; the scribe gave it the numbers of this star and left out this star's name (Nallino)
The one that follows this star	γ PsA	315	20	22	15†	S	4	latitude ′: Part II 15
The third, trailing one of these three preceding ones	δ PsA	316	30	22	10†	S	4	latitude ′: Part II 30
The star in the throat of the Fish	ε PsA	315	30	16	15*	S	4 greater	latitude ′: codex 10
The southern one on the southern spine	μ PsA	306	20	19*	30	S	5	latitude °: codex 9
The trailing one of the two in its belly	ζ PsA	312	20	15	10	S	5*	magnitude: codex 4
The leading one of them	λ PsA	310	0	14	40	S	4*	magnitude: codex 3
The trailing one of the three on the northern spine	η PsA	306	20	15*	0	S	4	latitude °: codex 12
The middle one of these three	θ PsA	303	0	16	30	S	4	
The leading one of these three	ι PsA	302	10	18	10	S	4	
The one on the tip of its tail	κ PsA	301	20	22	15	S	4	
And near it, of those not in its figure								
The leading one of the three bright ones		289	10	22	20	S	3 lesser	
The middle one of these three		292*	20*	22	10	S	3 lesser	longitude °: codex 262; longitude ′: codex 10
The trailing one of these three		295	10	21	0	S	3 lesser†	magnitude: Part II 3 lesser
The faint star ahead of it		293	10	20	50	S	5*	magnitude: codex 4

Folio 237 verso of the codex

Ar. p. 275

The states of the well-known fixed stars of the first magnitude for the year 1211 of Dhū l-Qarnayn

The Arabic has 1251, here and in the following titles, clearly an error for 1211 (Nallino)

No.	The names of the fixed stars of the first magnitude and some of the second	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
1	The Lance-bearing Simāk	α Boo	25	39	N	79	39	100†	25	202	58†	180	31	239	7	1	half stay °: Part II 110; culminating ′: Part II 48
2	The Falling Eagle	α Lyr	38	25	N	92*	25	125	8	269	20	224*	25	314	25	1	altitude °: codex 96; rising °: codex 124
3	al-ʿAnz, which is al-ʿAyyūq	α Aur	43	10	N	97*	10	132	58	61	34	25	45	84*	28	1	altitude °: codex 67; setting °: codex 107
4	al-Dabarān	α Tau	13	19	N	67	19	99	54	55*	25	61	4*	51*	32	1	culminating °: codex 35; rising ′: codex 10; setting °: codex 251
5	The Heart of the Lion	α Leo	16	47	N	70	47	102	50	134	20	134	5	134	43	1	
6	The Tail of the Lion	β Leo	19	36	N	73	36	105	1	160	52	153	5	175	48	1	
7	The trailing one of the outflow of the water	α PsA	33	45	S*	20	15	63*	50	325	25	350*	15*	312	6	1	direction: codex N; half stay °: codex 303; rising °: codex 307; rising ′: codex 40
8	The Unarmed Simāk	α Vir	4	49	S*	49	11*	86*	31	186	43	188*	0	184*	20	1	direction: codex N; altitude ′: codex 41; half stay °: codex 106; rising °: codex 173; setting °: codex 174
9	The root of the tail of the Archer	ω Sgr	30	0	S*	24	0	65	12	274	30	280	40	268	43	1	Al-Battānī computed it from the numbers that the catalogue gives to the sixteenth star of the Archer (Nallino); direction: codex N
10	The Shoulder of al-Jawzāʾ	α Ori	5	30	N	59	30	94	0	76	25	89*	45	64	50	1	rising °: codex 109
11	The Foot of al-Jawzāʾ	β Ori	10	20	S*	43	40	82*	21	69	56	94	0	49*	40*	1	direction: codex N; half stay °: codex 102; setting °: codex 44; setting ′: codex 0
12	The trailing one of the stars of the River	θ Eri	43	45	S*	10	15	45	48	39	3	98	20	353	43	1	direction: codex N

No.	The names of the fixed stars of the first magnitude and some of the second	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
13	al-Shiʿrā al-Yamāniya	α CMa	15	51	S*	38	9	78	5*	89*	22	115	33	63*	18	1	direction: codex N; half stay ′: codex 50; culminating °: codex 109; setting °: codex 353
14	al-Shiʿrā al-Shāmiya	α CMi	6	25	N	60	25	94	41	99	25	110	53	86*	46	1	setting °: codex 106
15	Suhayl al-Yamānī	α Car	51	25	S	2	35	24	26	89*	30	159*	20	19*	44	1	culminating °: codex 109; rising °: codex 119; setting °: codex 59
16	The Foot of Qanṭāwurus	β Col	37	3	S	16	57	56	44	78	50	123	36	36	39*	2*	The name is wrong: the numbers are those of β Col, the ninth star of the Dog in the catalogue, which returns under its own name as the sixtieth star here; the numbers of α Cen stand at the seventieth (Nallino); setting ′: codex 19; magnitude: codex 1
Ar. p. 276																	
17	The side of the Little Bear	β UMi	91	17	N	145	17			130	0					2	
18	Its side too	ɣ UMi	91	15	N	145	15			142	24					2	
19	The back of the Great Bear	α UMa	306†	20	N	120	20			142	0					2	The degrees of the distance are written «سو», 66 in the Eastern values of the letters and 306 in the Western ones; distance °: Part II 66
20	The soft part of its belly	β UMa	60	30	N	114	30			143	10					2	
21	Its thigh	ɣ UMa	57	45	N	111	45			178	35					2	
22	Its tail	ε UMa	60	27	N	114	26			168	10					2	
23	Its tail too	ζ UMa	59	40	N	113	40			187	20					2	
24	Its tail too	η UMa	54	15	N	108	15			196	0					2	
These eight stars are always visible above the earth: they do not rise and do not set, but cross the line of the middle of the sky twice in each revolution, once above the pole, with the degrees set against them in this table, and once below the pole																	Compared with the catalogue, the numbers of these eight stars show some very serious errors whose cause Nallino could not find

Folio 238 recto of the codex

The states of the well-known fixed stars of the second magnitude for the year 1211 of Dhū l-Qarnayn

The Arabic has 1251, as in the first title (Nallino)

No.	The names of these stars mentioned, of the second magnitude and some of the third	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
25	The bright one of al-Fakka	α CrB	31	46	N	85*	46	134	18	224	11*	192	32	267	6	2	altitude °: codex 105; culminating ′: codex 51
26	The tail of the Hen	α Cyg	42	21	N	96	21	131	27	298	54	245	7	345*	31	2	setting °: codex 344
27	The beak of the Hen	β Cyg	26	19	N	80	19	111	2	279	4	244	24	311	4	3*	magnitude: codex 2
28	The side of Farsāwus, the bearer of the head of the Ghoul	α Per	44	9	N	98	9	134	52	34	30	340	0	63*	0	2	setting °: codex 303
29	The head of the Ghoul in the hand of Farsāwus	β Per	36	2	N	90	2	121	55	32	12	356*	53*	50	43	2	rising °: codex 353; rising ′: codex 3
Ar. p. 277																	
30	The hilt of the knife	χ Per	50	39	N	104	39	152*	26	17	40	264†	30	64	20	nebulous*	half stay °: codex 112; rising °: Part II 295; magnitude: codex 2
31	The shoulder of the Holder of the Reins	β Aur	42	17	N	96	17	131	20	69	46	40	28	90	53	2	
32	The Flying Eagle	α Aql	6	22	N	60	22	94	44	282	18	261	12	301	10	2	
33	The head of Andrūmīdhus, which is the head of the Woman	o And	37	14	N	91*	14	122	27	331	22	281	54	4	52	3*	The name is wrong, as in the catalogue, where the Arabic has «in the head» for «in the right hand» (Nallino); altitude °: codex 94; magnitude: codex 2
34	The wing of the Horse	α Peg	10	16	N	64	16	97	35	330	45	309*	0	343	48*	2	rising °: codex 69; setting ′: codex 40
35	The Shoulder of the Horse	β Peg	22	31	N	76	31	107	32	330	24	296	46	351*	44*	2	setting °: codex 354; setting ′: codex 4
36	The back of the Horse	γ Peg	9	7	N	63	7	96	42	348	18*	332	48	356	43	2	culminating ′: codex 38
37	Where the neck of the Serpent comes out	β Ser	20	5	N	74	5	105	24*	225	27	202	42	257	20	3*	half stay ′: codex 46; magnitude: codex 2

No.	The names of these stars mentioned, of the second magnitude and some of the third	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
38	The head of Afullun	α Gem	32	49	N	106	49	117	57*	95	10	86*	28	104	32	2	Apollo, the leading Twin; the name is not in the catalogue (Nallino). The altitude should be 86° 49′, 54° plus the distance from the equator: «قو», 106, stands for «فو», 86, a slip that Nallino corrects elsewhere in these tables but not here; half stay ′: codex 17; rising °: codex 106
39	The head of Īraqlās	β Gem	29	32	N	103	32	114	18	98	33	93	12	104	35*	2	Heracles, the trailing Twin; the name is not in the catalogue (Nallino). The altitude should be 83° 32′, 54° plus the distance from the equator: «جڤ», 103, stands for «جفّ», 83, a slip that Nallino corrects elsewhere in these tables but not here; setting ′: codex 30
40	The middle of the Pleiades, nebulous	η Tau	19	18*	N	73	18*	104	45	43	13	39*	22	44*	17*	4*	distance ′: codex 38; altitude ′: codex 38; rising °: codex 59; setting °: codex 144; setting ′: codex 30; magnitude: codex 3
41	The breast of the Crab, nebulous	Praesepe	22	10	N	76	10	107	15*	111	54	111	36	112	16	nebulous*	half stay ′: codex 45; magnitude: codex 3
42	The back of the Lion	δ Leo	25	2	N	79	2	109	51	151*	0	141	34*	168	44*	3†	culminating °: codex 111; rising ′: codex 30; setting ′: codex 40; magnitude: Part II 2
43	The head of al-Jawzāʾ	α And	19	38	N	73	38	105	2	347	15	319	30	2*	44	3	The name is wrong: the head of the Giant is the fifty-fourth star here. The numbers fit the head of the Woman, α And, whose name stands wrongly at the thirty-third (Nallino); setting °: codex 202
44	The Woman, which is the Dyed Hand	α Oph	14	18	N	68	18	100	38	251	56	228	58*	278	34	3	The name is wrong: the numbers are those of the first star of the Serpent-charmer, α Oph (Nallino); rising ′: codex 50

The states of the well-known fixed stars of the third magnitude for the year 1211 of Dhū l-Qarnayn

The Arabic has 1251, as in the first title (Nallino). From here on the codex gives no magnitudes, and the title calls all the stars of the third magnitude; Nallino's translation supplies the magnitudes from the catalogue

No.	Of their names, explained in Arabic	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
45	The southern pan of the Balance	α Lib	8	42	S	45	18	83*	38	210	14	208	25*	213	27		half stay °: codex 103; rising ′: codex 35
46	The northern pan of the Balance	β Lib	3*	43*	S	50	17*	87*	18	216	35	210	32	227	0		distance °: codex 8; distance ′: codex 47; altitude ′: codex 37; half stay °: codex 107
47	The Heart of the Scorpion	α Sco	22	10	S	31	50	72	40	229	15*	232	27	224	5*		The author computed from a false longitude, 230° 0′ for 233° 50′ (Nallino); culminating ′: codex 55; setting ′: codex 15
48	The hock of the Archer	β Sgr	46	34	S	7	26	39	52	268	28	300	52	235	18		
49	The one following the Shawla of the Scorpion, nebulous		35	23	S	18*	37	58*	56	250	40	262	27	235	0		altitude °: codex 13; half stay °: codex 18
50	The eye of the Archer, nebulous	ν² Sgr	22	46	S	31	14*	72	16	266	39	266*	0	267	20		altitude ′: codex 54; rising °: codex 267
51	The point of the arrow of the Archer	ɣ Sgr	29	8*	S	24*	52*	66	8	255	17*	260	31	248	52		distance ′: codex 0; altitude °: codex 25; altitude ′: codex 0; culminating ′: codex 47
52	The lock of the Lion, the braid	Com, first	36	10	N	90	10	121	58*	170	43	146	40	215*	50		half stay ′: codex 18; setting °: codex 255
53	One of the two faint ones in the Scorpion	Com, second	31	40	N	85	40	116	41	167	14*	148	22	203	29		Perhaps «the Scorpion» is corrupted from «the braid»: the star is the second of the Lock (Nallino); culminating ′: codex 54
54	The head of the Giant	λ Ori	5	16	N	59	16*	93	46	71	0	84*	30	59	45		altitude ′: codex 56; rising °: codex 85
55	The left shoulder of the Giant	ɣ Ori	3	47	N	57	47	92	44	68	22	82	50	56	42		
56	The first of those in the belt	δ Ori	2	32	S	51	28	88	11*	70	33	89	18	54	54		half stay ′: codex 51
57	The middle one of them	ε Ori	2	54	S	51	6	87*	55	72	20	91	40	55	53		half stay °: codex 107
58	The third of them	ζ Ori	3	35	S	50	25	87*	24	73	10	92	33	56	33*		half stay °: codex 107; setting ′: codex 30

No.	Of their names, explained in Arabic	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
59	The bright one following the Dog	α Col	35	25*	S	18*	35	58	55	76	38	120	0	36	34		distance ′: codex 20; altitude °: codex 58
60	The second from it	β Col	37	3	S	16*	57	56	44	78	50	123	36	36	39		The sixteenth star repeated (Nallino); altitude °: codex 56
61	The curve of the Ship	ε Car	38	30	S	15*	30	54	58	124	55	165	23	75	43		Not in the catalogue, whose folio with the Ship is lost; Ptolemy's thirty-first star of the Ship (Nallino); altitude °: codex 55
62	The cut of its deck	? (Argo)	36	19	S	17*	41	57	40	128	30	166	10	81	10		Ptolemy's thirty-second star of the Ship, «the one on the cut of the deck» (Nallino); altitude °: codex 57

The states of the well-known fixed stars of the third magnitude for the year 1211 of Dhū l-Qarnayn

The Arabic has 1251, as in the first title (Nallino)

Ar. p. 279

No.	Of their names, explained in Arabic	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
63	The one under the deck	ζ Pup	37	45	S	59	55	52	14*	118	20	162	0	67*	40		Ptolemy's thirty-fifth star of the Ship (Nallino); half stay ′: codex 54; setting °: codex 307
64	The one under its breast	? (Argo)	50	42*	S	3	18*	27	25*	112	30	177	24	42	27		Ptolemy's thirty-sixth star of the Ship, «the bright one below, on the keel» (Nallino); distance ′: codex 52; altitude ′: codex 8; half stay ′: codex 0

No.	Of their names, explained in Arabic	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
65	The leading one of its three	? (Argo)	52	8*	S	1	52	20	56	122*	43	191	40	45	53		Ptolemy's thirty-seventh star of the Ship (Nallino); distance ′: codex 2; culminating °: codex 132
66	The bright one of the Water-snake	α Hya	2	55	S	51	5	107†	53*	125	58	139	20	107	20		Not in the catalogue, whose folio with the Water-snake is lost (Nallino); half stay °: Part II 87; half stay ′: codex 13
67	The belly of the horse of Qanṭāwurus	? (Cen)	48	45	S	5	15	35	10	192	30	239	0	118	10		Schiaparelli could not correct the numbers of this star (Nallino)
68	The middle of the thigh of the horse	ν Cen	53*	3	S	0	57	30	0	169	52	221	35	92	0		The twentieth star of the Centaur in the catalogue; for the degrees of rising and setting the author took the arc of the day for half of it (Nallino); distance °: codex 13
69	The hoof of this horse	ζ Cen	56*	37	S					165	7						Not seen at al-Raqqa (Nallino); distance °: codex 16
The star of this line is always hidden under the southern horizon and does not rise; for this reason it has no stay above the earth and no culmination																	
70	The foot of this horse	α Cen	44	38	S	9	22	44	10*	177	30	215	46	113	20		The codex's minutes of the half stay go back to the author, who read 45° 7′ for 45° 50′ (Nallino); half stay ′: codex 53
71	The knee of this horse	γ Cen	53	57	S	0	3	2	0	191	53	261	30*	85*	3		rising ′: codex 0; setting °: codex 125
72	The bright one of the stars of the Crown	θ CrA	40	44	S	13	16*	51*	14*	268	27	288	10	248	11*		altitude ′: codex 36; half stay °: codex 11; half stay ′: codex 54; setting ′: codex 4
73	The beginning of the outflow of the water from the handle of the Bucket	? (Aqr)	16	21	S	37	39	77	39	323	0	325	45	321	30		The numbers belong to a place in the Water-pourer where the catalogue has no star (Nallino)
74	The middle of the outflow of the water from the handle	? (Aqr)	10	7	S	43	53	82*	33*	325	46	322	45	327*	30		The thirteenth star of the Water-pourer in the catalogue (Nallino); half stay °: codex 111; half stay ′: codex 53; setting °: codex 337

No.	Of their names, explained in Arabic	Star	Their distances from the equator		Direction	Their altitude in the middle of the sky		Half their stay above the earth		The degrees that culminate with them		The degrees with which they rise		The degrees with which they set		Ranks of magnitude	Notes
			°	′		°	′	°	′	°	′	°	′	°	′		
75	The end of the outflow of the water from the handle	χ Aqr	12	25	S	41	35	80*	48	332	26	333*	0*	1030†	33		The seventeenth star of the Water-pourer in the catalogue (Nallino). The degrees of setting are written «شل», 330 in the Eastern values of the letters and 1030 in the Western ones; half stay °: codex 102; rising °: codex 332; rising ′: codex 20; setting °: Part II 330